# **ANSI/AHRI Standard 551/591-2023 (SI)**

Performance Rating of Water-chilling and Heat Pump Water-heating Packages Using the Vapor Compression Cycle





2311 Wilson Boulevard, Suite 400 Arlington, VA 22201, USA www.ahrinet.org PH 703.524.8800 FX 703.562.1942

we make life better\*



©Copyright 2023, by Air-Conditioning, Heating, and Refrigeration Institute
Registered United States Patent and Trademark Office
Printed in U.S.A.

# IMPORTANT SAFETY DISCLAIMER

AHRI does not set safety standards and does not certify or guarantee the safety of any products, components or systems designed, tested, rated, installed or operated in accordance with this standard/guideline. It is strongly recommended that products be designed, constructed, assembled, installed and operated in accordance with nationally recognized safety standards and code requirements appropriate for products covered by this standard/guideline.

AHRI uses its best efforts to develop standards/guidelines employing state-of-the-art and accepted industry practices. AHRI does not certify or guarantee that any tests conducted under its standards/guidelines will be non-hazardous or free from risk.

ICS Code: 27.200

Note:

This standard supersedes AHRI Standard 551/591-2020 (I-P) (Addendum 1). For SI ratings, see AHRI Standard 550/590-2023 (I-P).

#### AHRI CERTIFICATION PROGRAM DISCLAIMER

AHRI Standards are developed independently of AHRI Certification activities and can have scopes that include products that are not part of the AHRI Certification Program. The scope of the applicable AHRI Certification Program can be found on AHRI's website at <a href="http://www.ahrinet.org">http://www.ahrinet.org</a>.

#### Intent

This standard is intended for the guidance of the industry, including manufacturers, engineers, installers, contractors, and users.

#### **Review and Amendment**

This standard is subject to review and amendment as technology advances.

#### 2023 Edition

This edition of ANSI/AHRI 551/591 (SI), *Performance Rating of Water-chilling and Heat Pump Water-heating Packages Using the Vapor Compression Cycle*, was prepared by Chiller Standards Technical Committee. The standard was approved by the Applied Standards Subcommittee on 6 February 2023. The standard was approved as an American National Standard (ANS) on 5 June 2023.

#### Origin and Development of AHRI Standard number

The initial publication was AHRI Standard 551/591-2011, *Performance Rating of Water-chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle*. Subsequent revisions were:

ANSI/AHRI Standard 551/591 (SI) with Addendum 1-2012, Performance Rating of Water-chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle

AHRI Standard 551/591 (SI)-2011 (with Addenda 1 and 2), Performance Rating of Water-chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle

AHRI Standard 551/591 (SI)-2011 (with Addenda 1, 2 and 3), Performance Rating of Water-chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle

AHRI Standard 551/591 (SI)-2015, Performance Rating of Water-chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle

AHRI Standard 551/591 (SI)-2015 (with Errata), Performance Rating of Water-chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle (with Errata)

AHRI Standard 551/591 (SI)-2015 (with Addendum 1), Performance Rating of Water-chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle (with Addendum 1)

AHRI Standard 551/591 (SI)-2018, Performance Rating of Water-chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle

AHRI Standard 551/591 (SI)-2018 (with Errata), Performance Rating of Water-chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle

AHRI Standard 551/591 (SI)-2020, Performance Rating of Water-chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle

AHRI Standard 551/591-2020 (SI) (Addendum 1), Performance Rating of Water-chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle

#### **Summary of Changes**

ANSI/AHRI Standard 551/591-2023 (SI) contains the following update(s) to the previous edition:

- Revise current ANS to align with 2020 versions
- Incorporate Addendum 1 from AHRI 551/591-2020 (SI)
- Addresses three interpretations to AHRI 551/591-2020 (SI)
  - o Interpretation to AHRI Standards 550/590 2020 (I-P) and 551/591 2020 (SI) 1
  - Interpretation to AHRI Standards 550/590 2020 (I-P) and 551/591 2020 (SI) -2
  - o Interpretation to AHRI Standards 550/590 2020 (I-P) and 551/591 2020 (SI) 3
- Editorial corrections and minor clarifications as needed
- Update references

#### **Committee Personnel**

### **Chiller Standards Technical Committee**

Participant	Interest Category Classification	Voting Member Role	State or Province / Country
Frank Giunta Trane U.S. Inc.	Product Manufacturer	Chair	WI, USA
Darrin Anderson Multistack LLC	Product Manufacturer	Primary	WI, USA
Azzeddine Aoune Smardt Chiller Group Inc.	Product Manufacturer	Primary	QC, Canada
John Bade 2050 Partners	General Interest	Primary	CA, USA
John Cummings LG Electronics, Inc.	Product Manufacturer	Primary	GA, USA
Chandra Gollapudi Samsung Electronics Co., Ltd.	Product Manufacturer	Primary	South Korea
Tim Hammond WaterFurnace International, Inc.	Product Manufacturer	Primary	IN, USA
Phillip Johnson Daikin Applied Americas Inc.	Product Manufacturer	Primary	VA, USA
Richard Lord Carrier Corporation	Product Manufacturer	Primary	TN, USA
Kevin Teakell Aaon, Inc.	Product Manufacturer	Primary	OK, USA
Drew Turner Danfoss Turbocor Compressors	Component Manufacturer	Primary	CO, USA
Jeff Whitelaw Mitsubishi Electric Cooling & Heating	Product Manufacturer	Primary	GA, USA
Stephen Zardus Johnson Controls, Inc.	Product Manufacturer	Primary	PA, USA
Yunqian Zhang Chongqing Midea General Refrigeration Equipment Co., Ltd.	Product Manufacturer	Primary	China
Ben Dingel Trane U.S. Inc.	Product Manufacturer	Alternate to Frank Giunta	WI, USA
Dana Fischer Mitsubishi Electric Cooling & Heating	Product Manufacturer	Alternate to Jeff Whitelaw	GA, USA
Natasha Helsper Trane U.S. Inc.	Product Manufacturer	Alternate to Frank Giunta	WI, USA
Ryan Holdmeyer Trane U.S. Inc.	Product Manufacturer	Alternate to Frank Giunta	WI, USA
David Ritter Johnson Controls, Inc.	Product Manufacturer	Alternate to Stephen Zardus	PA, USA
Brad Schafer Multistack LLC	Product Manufacturer	Alternate to Darrin Anderson	WI, USA
Ken Schultz Trane U.S. Inc.	Product Manufacturer	Alternate to Frank Giunta	WI, USA
George Singh Trane U.S. Inc.	Product Manufacturer	Alternate to Frank Giunta	WI, USA
Doug Tucker Mitsubishi Electric Cooling & Heating	Product Manufacturer	Alternate to Jeff Whitelaw	GA, USA
Michael Zamalis Johnson Controls, Inc.	Product Manufacturer	Alternate to Stephen Zardus	PA, USA
Jaime Yeh	AHRI Staff Liaison		

#### **Chiller Standards Technical Committee Scope:**

The Chiller Standards Technical Committee is responsible for the development and maintenance of AHRI standards and guidelines pertaining to Performance Rating of Liquid-Chilling and Heat Pump Liquid-Heating Packages using the Vapor Compression Cycle, Absorption Liquid Chilling and Liquid Heating Packages, Fouling Factor Applications related to Air Conditioning and Refrigeration, and Non-condensable Gas Purge Equipment for use with Low Pressure Centrifugal Liquid Chillers.

Out of scope for this STC are water-to-water heat pumps with a capacity less than 135,000 Btu/h as covered by ASHRAE/AHRI/ISO Standard 13256-2, and air-to-water units designed exclusively to heat potable water as covered by AHRI Standard 1300.

Product definitions are as defined on the AHRI website Applied Sector page.

#### **Applied Standards Subcommittee**

Participant	Interest Category Classification	Voting Member Role	State or Province / Country
Patrick Marks Johnson Controls, Inc.	Product Manufacturer	Chair	PA, USA
Brandon Bates Energistics Laboratory	Testing Laboratory	Primary	TX, USA
Craig Burg Desert Aire Corp.	Product Manufacturer	Primary	WI, USA
Jennifer Butsch Emerson Commercial and Residential Solutions	Product Manufacturer	Primary	OH, USA
Jeff deRoos Carrier Corporation	Product Manufacturer	Primary	FL, USA
Henry Ernst Daikin Applied Americas Inc.	Product Manufacturer	Primary	MN, USA
Armin Hauer ebm-papst Inc.	Product Manufacturer	Primary	CT, USA
Darcy Lee Trane U.S. Inc.	Product Manufacturer	Primary	GA, USA
Tom McDermott Swegon North America Inc.	Product Manufacturer	Primary	ON, CA
Eric Sakal GE Appliances, a Haier Company	Product Manufacturer	Primary	KY, USA
Jeff Whitelaw Mitsubishi Electric Cooling & Heating	Product Manufacturer	Primary	GA, USA
Karl Best	AHRI Staff Liaison		•

#### **Applied Standards Subcommittee Scope:**

The scope of the Applied Standards Subcommittee is standards and guidelines related to the end products that are part of the AHRI Applied Industry Sector. (The definition of and list of products associated with each sector are found on the AHRI website.

These lists represent the membership at the time the Standards Technical Committee and Standards Subcommittee were balloted on the final text of this edition. Since that time, changes in the membership may have occurred. Membership on these committees shall not in and of itself constitute an endorsement by the committee members or their employers of any document developed by the committee on which the member serves.

# **Applied Consensus Body**

Participant	Interest Category Classification	State / Country
Curtis Eichelberger Eichelberger Acoustics LLC	Testing Laboratory	PA, USA
Aaron Gunzner Air Movement and Control Association International, Inc.	Testing Laboratory	IL, USA
Byron Horak Intertek	Testing Laboratory	NY, USA
Satheesh Kulankara Johnson Controls, Inc.	Product Manufacturer	PA, USA
James Lee Zhongshan Saiver-Welaire Air Conditioning Equipment Co., Ltd.	Product Manufacturer	China
Douglas Mischley APV North America Heat Transfer (SPX Flow Inc.)	Product Manufacturer	NC, USA
Joe Pessa Dynamic Air Quality Solutions	Component Manufacturer	NJ, USA
Aniruddh Roy Energy Solutions	General Interest	CA, USA
Doug Tucker Mitsubishi Electric Cooling & Heating	Product Manufacturer	GA, USA
Sebastian Wejchert Swiss Rotors Inc.	Component Manufacturer	GA, USA

## **TABLE OF CONTENTS**

SECTION		PAGE
Section 1.	Purpose	1
Section 2.	Scope	1
Section 3.	Definitions	1
Section 4.	Test Requirements	5
Section 5.	Rating Requirements	12
Section 6.	Minimum Data Requirements for Published Ratings	26
Section 7.	Units of Measure, Conversions and Water Properties	30
Section 8.	Symbols and Subscripts	32
Section 9.	Marking and Nameplate Data	37
Section 10.	Conformance Conditions	37
Section 11.	Operating Requirements	37
	TABLES	
Table 1.	Definition of Operating Condition Tolerances and Stability Criteria	9
Table 2.	Temperature Measurement Requirements	11
Table 3.	Criteria for Air Distribution and Control of Air Temperature	12
Table 4.	Standard Rating Conditions	14
Table 5.	Full and Part-load Application Rating Conditions	15
Table 6.	Part-load Conditions for Rating	17
Table 7.	Definition of Tolerances	24
Table 8.	Published Values	27
Table 9.	Conversion Factors	30
Table 10.	Symbols and Subscripts	32

# **TABLE OF CONTENTS (Continued)**

# **FIGURES**

Figure 1.	Air Sampling Array	11
Figure 2.	Interpolated IPLV.SI Condition	18
Figure 3.	Allowable Tolerance (Tol <sub>1</sub> ) Curves for Full and Part-load Points	25
Figure 4.	IPLV.SI and NPLV.SI Tolerance (Tol <sub>2</sub> ) Curve	25
	APPENDICES	
Appendix A.	References – Normative	38
Appendix B.	References – Informative	39
Appendix C.	Atmospheric Pressure Adjustment – Normative	40
Appendix D.	Derivation of Integrated Part-load Value (IPLV.IP) – Informative	42
Appendix E.	Averaging – Informative	50
Appendix F.	Examples – Informative	60
Appendix G.	Indian Rating Conditions – Informative	70
	TABLES FOR APPENDICES	
Table C1		41
Table C1.	Correction Factor (CF) Coefficients	
Table D1.	Group 1 Air-cooled IPLV.IP Data and Calculation	47
Table D2.	Group 1 Water-cooled IPLV.IP Data and Calculation	48
Table D3.	Group 1 – 4 IPLV.IP Summary	49
Table E1.1.	Summary of Example #1	50
Table E1.2.	Data for Example #1	51
Table E2.1.	Summary of Example #2	55
Table E2.2.	Data for Example #2	56
Table F1.	Example F2.3.1 Test Results	61
Table F2.	Example F2.3.1 Calculations	61
Table F3.	Example F2.3.2 Test Results	62

Table F4.	Example F2.3.2 Calculations	62
Table F5.	Example F2.3.3 Test Results	63
Table F6.	Example F2.3.3 Calculations	63
Table F7.	Example F2.3.4 Test Results	65
Table F8.	Example F2.3.4 Calculations	65
Table F9.	Example F2.3.5 Test Results	66
Table F10.	Example F2.3.5 Calculations	66
Table F11.	Example F2.3.6 Test Results	66
Table F12.	Example F2.3.6 Calculations	67
Table F13.	Example F2.3.7 Test Results	67
Table F14.	Example F2.3.7 Calculations	67
Table G1.	Indian Standard Rating Conditions	70
Table G2.	Indian Full and Part-load Application Rating Conditions	71
Table G3.	Part-load Conditions for Ratings	71
Table G4.	Weighting Coefficients A to D for Calculation of ISEER	72
Table G5.	Chiller Part-load Values Data	73
	FIGURES FOR APPENDICES	
Figure D1.	Ton <sub>R</sub> -hour Distribution Categories	44
Figure D2.	Bin Groupings – Ton <sub>R</sub> -hours	45
Figure D3.	Group 1 Ton <sub>R</sub> -hour Distribution Categories	45
Figure D4.	Group 2 Ton <sub>R</sub> -hour Distribution Categories	46
Figure E1.	Example #1 Charts	54
Figure E2.	Example #2 Charts	59
Figure F1.	Rating Point Interpolation	64

# PERFORMANCE RATING OF WATER-CHILLING AND HEAT PUMP WATER-HEATING PACKAGES USING THE VAPOR COMPRESSION CYCLE

#### Section 1. Purpose

**1.1** *Purpose*. This standard establishes definitions, test requirements, rating requirements, minimum data requirements for Published Ratings, marking and nameplate data, conversions and calculations, nomenclature, and conformance conditions for Water-chilling and Heat Pump Water-heating Packages using the vapor compression cycle.

#### Section 2. Scope

- **2.1** *Scope.* This standard applies to factory-made Water-chilling and Water-heating Packages utilizing the vapor compression cycle as defined in Section 3. These Water-chilling and Water-heating Packages include:
  - **2.1.1** Water-cooled, Air-cooled, or Evaporatively-cooled Condensers
  - **2.1.2** Water-cooled heat recovery Condensers
  - **2.1.3** Air-to-water heat pumps
  - **2.1.4** Water-to-water heat pumps with a Capacity greater or equal to 40 kW.
- 2.2 Exclusions.
  - **2.2.1** Water-to-water heat pumps with a Capacity less than 40 kW are covered by the latest edition of ASHRAE/ANSI/AHRI/ISO Standard 13256-2.
  - **2.2.2** Air-to-water units designed exclusively to heat potable water as covered by the latest edition of ANSI/AHRI Standard 1300.
  - **2.2.3** Water-chilling Packages are excluded when the Condenser is actively adiabatically-cooled. An adiabatically-cooled Condenser is an Air-cooled Condenser that uses evaporative cooling to pre-cool air before that air reaches the dry heat transfer surface.
  - **2.2.4** Water-chilling or Water-heating packages with both an Air-cooled Condenser and a Water-cooled Condenser are outside the scope of this standard when operating in any mode (cooling, heating, heat recovery, or simultaneous heating and cooling) with the heat rejection split between the Air-cooled Condenser and Water-cooled Condenser.
  - 2.2.5 Units with Evaporators or Condensers that use any liquid other than water are outside the scope of this standard.

#### Section 3. Definitions

All terms in this document follow the standard industry definitions in the ASHRAE Terminology website unless otherwise defined in this section.

- **3.1** *Expressions of Provision.* Terms that provide clear distinctions between requirements, recommendations, permissions, options, and capabilities.
  - **3.1.1** "Can" or "cannot". Express an option or capability
  - **3.1.2** *"May"*. Signifies a permission expressed by the document.
  - **3.1.3** *"Must"*. Indication of unavoidable situations and does not mean that an external constraint referred to is a requirement of the document.

- **3.1.4** *"Shall" or "shall not"*. Indication of mandatory requirements to strictly conform to the standard and where deviation is not permitted.
- **3.1.5** *"Should" or "should not".* Indication of recommendations rather than requirements. In the negative form, a recommendation is the expression of potential choices or courses of action that is not preferred but not prohibited.
- **3.2** *Standard Specific Definitions* 
  - **3.2.1** Auxiliary Power. Power provided to devices that are not integral to the operation of the vapor compression cycle such as, but not limited to: oil pumps, refrigerant pumps, control power, fans and heaters.
  - **3.2.2** *Bubble Point.* Refrigerant liquid saturation temperature at a specified pressure.
  - **3.2.3** Capacity. A measurable physical quantity that characterizes the water side heat flow rate. Capacity is the product of the water mass flow rate and the change in water enthalpy entering and leaving the heat exchanger, measured at the point of the field connection. For this standard, the enthalpy change is approximated as the sensible heat transfer using specific heat and temperature difference.
    - **3.2.3.1** *Net Heating Capacity.* The Capacity of the heating Condenser available for useful heating of the thermal load external to the Water-heating Package and is calculated using only the sensible heat transfer. (Refer to Equations 20 and 21.)
    - **3.2.3.2** *Net Refrigerating Capacity*. The Capacity of the Evaporator available for cooling of the thermal load external to the Water-chilling Package and it is calculated using only the sensible heat transfer. (Refer to Equation 18.)

Note: The method of test referenced in Sections 4.1 and 4.2 defines and makes use of gross heating capacity and gross refrigerating capacity, which consider the energy associated with water-side pressure losses.

- **3.2.4** Compressor Saturated Discharge Temperature. For single component and azeotrope refrigerants, it is the saturated temperature corresponding to the refrigerant pressure at the compressor discharge measured downstream of any refrigerant circuit components like mufflers, oil separators and discharge valves at the point of field connection. For zeotropic refrigerants, it is the arithmetic average of the Dew Point and Bubble Point temperatures corresponding to refrigerant pressure at the compressor discharge.
- **3.2.5** *Condenser.* A refrigeration system component which condenses refrigerant vapor. Desuperheating and subcooling of the refrigerant can occur as well.
  - **3.2.5.1** Air-cooled Condenser. A component which condenses refrigerant vapor by rejecting heat to air mechanically circulated over its heat transfer surface causing a rise in the air temperature.
  - **3.2.5.2** Evaporatively-cooled Condenser. A component which condenses refrigerant vapor by rejecting heat to a water and air mixture mechanically circulated over its heat transfer surface, causing evaporation of the water and an increase in the enthalpy of the air.
  - **3.2.5.3** *Remote Condenser.* Any Condenser that is installed as a separate assembly from the rest of the Water-chilling or Water-heating Package with field installed interconnecting piping.
  - **3.2.5.4** *Water-cooled Condenser.* A component which utilizes refrigerant-to-water heat transfer means, causing the refrigerant to condense and the water to be heated.
  - **3.2.5.5** Water-cooled Heat Recovery Condenser. A component or components which utilizes refrigerant-to-water heat transfer means, causing the refrigerant to condense and the water to be heated. This Condenser can be a separate Condenser, the same as, or a portion of the Water-cooled Condenser. The heat rejected can be done through a single or multiple heat exchangers, including desuperheaters as defined in ANSI/AHRI Standard 470.

- **3.2.6** *Dew Point.* Refrigerant vapor saturation temperature at a specified pressure.
- 3.2.7 Energy Efficiency.
  - **3.2.7.1** Cooling Energy Efficiency.
    - **3.2.7.1.1** Cooling Coefficient of Performance  $(COP_R)$ . A ratio of the Net Refrigerating Capacity to the Total Input Power at any given set of Rating Conditions. (Refer to Equation 14.)
  - **3.2.7.2** Heating Energy Efficiency.
    - **3.2.7.2.1** *Heating Coefficient of Performance (COP<sub>H</sub>).* A ratio of the Net Heating Capacity to the Total Input Power at any given set of Rating Conditions. (Refer to Equation 15.)
  - **3.2.7.3** Energy efficiency metrics for simultaneous heating and cooling operating modes.
    - **3.2.7.3.1** Heat Recovery Coefficient of Performance ( $COP_{HR}$ ). A ratio of the Net Heat Recovery Capacity plus the Net Refrigerating Capacity to the Total Input Power at any given set of Rating Conditions.  $COP_{HR}$  applies to units that are operating in a manner that uses either all or only a portion of heat generated during chiller operation,  $Q_{hrc}$ , to heat a load, while the remaining heat,  $Q_{cd}$ , if any, is rejected to the outdoor ambient.  $COP_{HR}$  takes into account the beneficial cooling Capacity,  $Q_{ev}$ , as well as the Heat Recovery Capacity,  $Q_{hrc}$ . (Refer to Equation 16.)
    - **3.2.7.3.2** Simultaneous Heating and Cooling Coefficient of Performance ( $COP_{SHC}$ ). A ratio of the Net Heating Capacity plus the Net Refrigerating Capacity to the Total Input Power at any given set of Rating Conditions.  $COP_{SHC}$  applies to units that are operating in a manner that uses both the net heating and refrigerating capacities generated during operation.  $COP_{SHC}$  takes into account the beneficial Capacity,  $Q_{ev}$ , as well as the heating Capacity,  $Q_{cd}$ . (Refer to Equation 17.)
- **3.2.8** *Evaporator.* A refrigeration system component which evaporates refrigerant liquid. Superheating of the refrigerant can occur as well.
  - **3.2.8.1** *Remote Evaporator.* Any Evaporator that is installed as a separate assembly from the rest of the Waterchilling or Water-heating Package with field installed interconnecting piping.
- **3.2.9** Fouling Factor ( $R_{foul}$ ). The thermal resistance due to fouling accumulated on the water side or air side heat transfer surface.
  - **3.2.9.1** Fouling Factor Allowance  $(R_{foul,sp})$ . A specified value for Published Ratings as a provision for anticipated thermal resistance due to water side or air side fouling during use, expressed in  $m^2 \cdot K/kW$ .
- **3.2.10** *Liquid Refrigerant Temperature.* The temperature of the refrigerant liquid leaving the Condenser but prior to the expansion device.
- **3.2.11** *Part-load Value (PLV).* A single number figure of merit expressing part-load efficiency for equipment on the basis of weighted operation at various partial load capacities for the equipment.
  - **3.2.11.1** *Integrated Part-load Value (IPLV.SI)*. A single number part-load efficiency figure of merit calculated per the method described in this standard at Standard Rating Conditions.
  - **3.2.11.2** *Non-Standard Part-load Value (NPLV.SI)*. A single number part-load efficiency figure of merit calculated per the method described in this standard referenced to conditions other than IPLV.SI conditions (i.e. for units that are not designed or selected to operate at Standard Rating Conditions).
- **3.2.12** *Percent Load (%Load).* The ratio of the part-load rated net Capacity to the Full Load Capacity, stated in decimal format (e.g.100% = 1.0).

- **3.2.12.1** Full Load (100% Load). The highest Capacity at which the chiller has been rated at specific conditions. Corresponds to the 100% Load point utilized in IPLV.SI or NPLV.SI.
- **3.2.13** *Published Ratings*. A statement of the assigned values of those performance characteristics, under stated Rating Conditions, by which a unit can be chosen to fit its application. These values apply to all units of like nominal size and type (identification) produced by the same manufacturer. The term Published Rating includes the rating of all performance characteristics shown on the unit or published in specifications, advertising or other literature controlled by the manufacturer, at stated Rating Conditions.
  - **3.2.13.1** *Application Rating.* A rating based on tests performed at Application Rating Conditions (other than Standard Rating Conditions).
  - **3.2.13.2** Standard Rating. A rating based on tests performed at Standard Rating Conditions.
- **3.2.14** *Rating Conditions.* Any set of operating conditions under which a single level of performance results and which causes only that level of performance to occur.
  - **3.2.14.1** *Appplication Rating Conditions.* A set of operating conditions within the range of Table 5 selected for a customer application (other than Standard Rating Conditions).
  - **3.2.14.1** *Standard Rating Conditions.* A set of operating conditions used as the basis of comparison for performance characteristics, per Table 4.
- **3.2.15** *Significant Figure(s).* Each of the digits of a number that are used to express it to the required degree of accuracy, starting from the first nonzero digit. (Refer to Sections 4.3 and 6.2.)
- **3.2.16** *Total Input Power* ( $W_{input}$ ). Combined power input of all components of the unit, including Auxiliary Power and excluding integral pumps.
- **3.2.17** Water-chilling or Water-heating Package. A factory-made and prefabricated assembly (not necessarily shipped as one package) of one or more compressors, Condensers and Evaporators, with interconnections and accessories designed for the purpose of cooling or heating water. It is a machine specifically designed to make use of a vapor compression refrigeration cycle to remove heat from water and reject the heat to a cooling medium, usually air or water. The refrigerant Condenser can be an integral or separate part of the package.
  - **3.2.17.1** Heat Recovery Water-chilling Package. A factory-made package designed for the purpose of chilling water and containing a Condenser for recovering heat. Where such equipment is provided in more than one assembly, the separate assemblies are to be designed to be used together, and the requirements of rating outlined in this standard are based upon the use of matched assemblies. It is a package specifically designed to make use of the refrigerant cycle to remove heat from the water source and to reject the heat to another fluid for heating use. Any excess heat can be rejected to another medium, usually air or water.
  - **3.2.17.2** Heat Pump Water-heating Package. A factory-made package designed for the purpose of heating water. Where such equipment is provided in more than one assembly, the separate assemblies are to be designed to be used together, and the requirements of rating outlined in this standard are based upon the use of matched assemblies. It is a package specifically designed to make use of the refrigerant cycle to remove heat from an air or water source and to reject the heat to water for heating use. This unit can include valves to allow for reverse-cycle (cooling) operation.
  - **3.2.17.3** Condenserless Chiller. A factory-made package designed for the purpose of chilling water but is not supplied with a Condenser. A separate air, water or evaporatively cooled Condenser interfaces with the Condenserless Chiller.
- **3.2.18** *Water Pressure Drop.* The reduction in static water pressure associated with the flow through a water-type heat exchanger.

#### Section 4. Test Requirements

- **4.1** *Test Requirements.* Ratings shall be established at the Rating Conditions specified in Section 5. Testing to validate ratings shall be conducted in accordance with the test method and procedures described in this standard and ANSI/ASHRAE Standard 30. Where there are discrepancies between this standard and ANSI/ASHRAE Standard 30, this standard shall prevail.
- **4.2** Tests shall report measurement values and calculated results in accordance with methods and procedures described in ANSI/ASHRAE Standard 30. Refer to Appendix E for examples showing average data samples collected between each time stamp for the test data points in accordance with ANSI/ASHRAE Standard 30.
- **4.3** Rounding. Calculations shall use measurement values without rounding as defined below. Reported measurement data and calculated test results shall round values to a number of Significant Figures per Section 6. Energy balance and voltage balance shall be rounded to four (4) Significant Figures.
  - **4.3.1** Numerical data are often obtained (or at least calculations can be made) with more digits than are justified by their accuracy or precision. For clarity, such data shall be rounded to the number of figures consistent with the confidence that can be placed in them when reported in final form. However, more digits shall be retained at intermediate stages of calculation to avoid compounding of rounding errors; retain no less than two additional Significant Figures than the final reported value, or as many digits as possible. The number of Significant Figures is the number of digits remaining when the data are rounded.
  - **4.3.2** The rules for identifying Significant Figures when writing or interpreting numbers are as follows:
    - **4.3.2.1** All non-zero digits are considered significant. For example, 91 has two Significant Figures (9 and 1), while 123.45 has five Significant Figures (1, 2, 3, 4 and 5).
    - **4.3.2.2** Zeros appearing anywhere between two non-zero digits are significant. Example: 101.1203 has seven Significant Figures: 1, 0, 1, 1, 2, 0 and 3.
    - **4.3.2.3** Leading zeros are not significant. For example, 0.00052 has two Significant Figures: 5 and 2.
    - **4.3.2.4** Trailing zeros in a number containing a decimal point are significant. For example, 12.2300 has six Significant Figures: 1, 2, 2, 3, 0 and 0. The number 0.000122300 still has only six Significant Figures (the zeros before the 1 are not significant). In addition, 120.00 has five Significant Figures since it has three trailing zeros. This convention clarifies the precision of such numbers; for example, if a measurement precise to four decimal places (0.0001) is given as 12.23 then it can be misunderstood that only two decimal places of precision are available. Stating the result as 12.2300 makes clear that it is precise to four decimal places (in this case, six Significant Figures).
    - **4.3.2.5** The significance of trailing zeros in a number not containing a decimal point can be ambiguous. For example, it is not always clear if a number like 1300 is precise to the nearest unit (and just happens coincidentally to be an exact multiple of a hundred) or if it is only shown to the nearest hundred due to rounding or uncertainty. One of the following conventions shall be used to address this issue:
      - **4.3.2.5.1** Place a bar over the last Significant Figure; any trailing zeros following this are insignificant. For example, 1300 has three Significant Figures (and hence indicates that the number is precise to the nearest ten).
      - **4.3.2.5.2** Underline the last Significant Figure of a number; for example, "2000" has two Significant Figures.
      - **4.3.2.5.3** Place a decimal point after the number; for example, "100." indicates specifically that three Significant Figures are meant.
      - **4.3.2.5.4** In the combination of a number and a unit of measurement, choose a suitable unit prefix. For example, the number of Significant Figures in a power measurement specified as 1300 W is ambiguous, while a power of 1.30 kW is not.

- **4.3.2.5.5** Use scientific notation or exponential notation; for example, 1.30×10<sup>3</sup> W.
- **4.3.2.6** In multiplication and division, the operation with the least number of Significant Figures determines the numbers to be reported in the result. For example, the product  $1256 \times 12.2 = 15323.2$  is reported as 15300. In addition and subtraction, the least number of figures to either the right or the left of the decimal point determines the number of Significant Figures to be reported. Thus, the sum of 120.05 + 10.1 + 56.323 = 156.473 is reported as 156.5 because 10.1 defines the reporting level. In complex calculations involving multiplications and additions, for example, the operation is done serially, and the final result is rounded according to the least number of Significant Figures involved. Thus:  $(1256 \times 12.2) + 125 = 15323.2 + 125 = 15400$ .
- **4.3.3** The following rules shall be used in rounding values:
  - **4.3.3.1** When the digit next beyond the one to be retained is less than five, the retained figure is kept unchanged. For example: 2.541 becomes 2.5 to two Significant Figures.
  - **4.3.3.2** When the digit next beyond the one to be retained is greater than or equal to five, the retained figure is increased by one. For example; 2.453 becomes 2.5 to two Significant Figures.
  - **4.3.3.3** When two or more figures are to the right of the last figure to be retained, they are to be considered as a group in rounding decisions. Thus in 2.4(501), the group (501) is considered to be >5 while for 2.5(499), (499) is considered to be <5.
- **4.4** *Water Connections*. Ratings shall be established with a single entering and single leaving connection per water circuit as follows:
  - **4.4.1** *Water-cooled Condensers.* Units with multiple Water-cooled Condenser heat exchangers shall be tested with all Water-cooled Condenser heat exchangers connected for the duration of the test.
  - **4.4.2** Water-cooled Heat Recovery Condenser. Units with multiple Water-cooled Heat Recovery Condenser heat exchangers shall be tested with all Water-cooled Heat Recovery Condenser heat exchangers connected for the duration of the test.
  - **4.4.3** *Evaporator.* Units with multiple Evaporator heat exchangers shall be tested with all Evaporator heat exchangers connected for the duration of the test.
- **4.5** Refrigerant Tubing for Remote Condenser or Remote Evaporator. The unit shall be installed with interconnecting refrigerant tubing. The equivalent length of that tubing shall be no less than the rated length per Section 5.9. All refrigerant tubing and components shall be installed within the same test room as all other parts of the tested equipment. Refrigerant tubing line sizes, insulation, and details of installation shall be in accordance with the manufacturer's published recommendation and shall be recorded prior to testing.
- **4.6** *Corrections*. This section defines fouling factor related adjustments to target temperature values, as well as corrections to test measurements for water-side pressure drop, and corrections to test results for atmospheric pressure.
  - **4.6.1** *Method for Simulating Fouling Factor Allowance.* The calculations in this section apply to evaporators and Condensers using water, for full load and part load operating conditions. The resultant fouling factor correction,  $\Delta T_{adj}$ , is added or subtracted to the target test water temperature as appropriate to simulate the fouled condition.

$$\Delta T_{\rm range} = \left| T_{\rm out,w} - T_{\rm in,w} \right|$$

$$\Delta T_{\text{small.sp}} = |T_{\text{sat.r}} - T_{\text{out.w}}|$$

Where  $T_{\text{sat,r}}$  is the saturated vapor temperature for single component or azeotrope refrigerants, or for zeotropic refrigerants  $T_{\text{sat}}$  is the arithmetic average of the Dew Point and Bubble Point temperatures, corresponding to refrigerant pressure.

Calculate the Log Mean Temperature Difference ( $\Delta T_{LMTD}$ ) for the evaporator and/or Condenser using the following equation at the Fouling Factor Allowance ( $R_{foul}$ ) specified by the rated performance, and the corresponding specified small temperature difference,  $\Delta T_{small,sp}$ .

$$\Delta T_{LMTD} = \frac{\Delta T_{range}}{\ln\left(1 + \frac{\Delta T_{range}}{\Delta T_{small,sp}}\right)}$$

Calculate the incremental log mean temperature difference ( $\Delta T_{ILMTD}$ ) using Equation 4:

$$\Delta T_{\text{ILMTD}} = R_{\text{foul}} \left( \frac{Q}{A_w} \right)$$

Where Q is the rated net Capacity and  $A_w$  is the water-side heat transfer surface area for the heat exchanger, which is inside or outside surface area depending on the heat exchanger design.

The water temperature adjustment needed to simulate the additional fouling,  $\Delta T_{adj}$ , can now be calculated:

$$Z = \frac{\Delta T_{\text{range}}}{\Delta T_{\text{LMTD}} - \Delta T_{\text{LMTD}}}$$

$$\Delta T_{\text{small,clean}} = \frac{\Delta T_{\text{range}}}{e^{Z} - 1}$$

$$\Delta T_{adj} = \Delta T_{small,sp} - \Delta T_{small,clean}$$

Where  $\Delta T_{small,sp}$  is the small temperature difference as rated at a specified Fouling Factor Allowance, and  $\Delta T_{small,clean}$  is the small temperature difference as rated in a clean condition with no fouling.

 $\Delta T_{adj}$  is used for both Evaporator and Condenser water temperature corrections and shall be calculated separately for each heat exchanger.  $\Delta T_{adj}$  shall be added to the controlled target temperature for condensing heat exchangers and subtracted from the controlled target temperature for evaporating heat exchangers. Operating condition tolerance limits per Table 1 apply to the adjusted target temperature. The test requires control over one temperature and the flow rate in a heat exchanger; the uncontrolled, unadjusted temperature can vary.

Note: See informative Appendix F for calculation examples of Fouling Factor Allowances to correct temperature targets.

**4.6.1.1** Condensing heat exchangers in cooling mode. The corrected water temperature target for condensing heat exchangers in cooling mode shall be calculated using Equation 8:

$$T_{\text{in,adi}} = T_{\text{in,w}} + \Delta T_{\text{adi}}$$

**4.6.1.2** Evaporating heat exchangers in cooling mode. The corrected water temperature target for evaporating heat exchangers in cooling mode shall be calculated using Equation 9:

$$T_{out,adj} = T_{out,w} - \Delta T_{adj}$$

**4.6.1.3** Condensing heat exchangers in heating mode. The corrected water temperature target for condensing heat exchangers in heating mode shall be calculated using Equation 10:

$$T_{\text{out,adj}} = T_{\text{out,w}} + \Delta T_{\text{adj}}$$

**4.6.1.4** Evaporating heat exchangers in heating mode. The corrected water temperature target for evaporating heat exchangers in heating mode shall be calculated using Equation 11:

$$T_{\text{out,adj}} = T_{\text{out,w}} - \Delta T_{\text{adj}}$$

#### **4.6.1.5** *Special Consideration for Multiple Refrigerant Circuits.*

For units that have multiple refrigeration circuits for the evaporator or Condenser, and the following items are known for each heat exchanger: refrigerant saturation temperatures, inlet and outlet water temperatures, and water flow rates; an adjustment temperature  $\Delta T_{adj,i}$  shall be computed for each heat exchanger and then combined into a single water temperature adjustment. For series water circuits, the intermediate water temperatures are calculated when measurement is not practical. For this purpose a weighted average for the  $\Delta T_{adj,i}$  values shall be computed as follows:

$$\Delta T_{adj,weighted} = \frac{\Sigma(Q_i \cdot \Delta T_{adj,i})}{\Sigma(Q_i)}$$
8

Where 'i' is equal to the number of heat exchangers.

For this purpose, the weighted temperature adjustment,  $\Delta T_{adj,weighted}$ , shall be added to the condenser entering water temperature or subtracted from the evaporator leaving water temperature to simulate the additional fouling factor adjustment.

#### **4.6.1.6** *Derivation of Log Mean Temperature Difference (LMTD).*

This derivation is included for reference only:

$$\begin{split} \Delta T_{\text{LMTD}} &= \frac{\left(T_{\text{sat,r}} - T_{\text{in,w}}\right) - \left(T_{\text{sat,r}} - T_{\text{out,w}}\right)}{\ln\left[\frac{T_{\text{sat,r}} - T_{\text{in,w}}}{T_{\text{sat,r}} - T_{\text{out,w}}}\right]} \\ &= \frac{\left(T_{\text{out,w}} - T_{\text{in,w}}\right)}{\ln\left[\frac{\left(T_{\text{sat,r}} - T_{\text{out,w}}\right) + \left(T_{\text{out,w}} - T_{\text{in,w}}\right)}{T_{\text{sat,r}} - T_{\text{out,w}}}\right]} \\ &= \frac{\left(T_{out,w} - T_{in,w}\right)}{\ln\left[1 + \frac{\left(T_{out,w} - T_{in,w}\right)}{T_{\text{sat,r}} - T_{out,w}}\right]} \\ &= \frac{\Delta T_{range}}{\ln\left(1 + \frac{\Delta T_{range}}{\Delta T_{small,sp}}\right)} \end{split}$$

- 9
- **4.7** *Validation.* Measurement data validation shall be in accordance with ANSI/ASHRAE Standard 30 except as noted below.
  - **4.7.1** *Redundant Voltage Measurement.* Where redundant voltage measurement is required, the average voltage shall not differ by more than 2% from either measurement.
  - **4.7.2** Operating Condition Tolerances and Stability Criteria. Measured data shall be in accordance with Table 1.

	Table 1. Definition of Operating Condition Tolerances and Stability Criteria										
Measurement or Calculation Result		Applicable Operating Mode(s)	ing Data Samples		Operating Condition Tolerance Limits	Stability Criteria					
Net Capacity (Cooling or Heating)		Cooling, Heating, Heat Recovery	Q	-	Unit with Continuous Unloading: $^1$ Part Load test Capacity shall be within 2% of the target part-load Capacity $^2$ $\frac{\left \overline{Q} - Q_{target}\right }{Q_{100\%}} \leq 2.000\%$ Units with Discrete Capacity Steps: Part Load test points shall be taken at the capacity steps closest to the specified part-load rating points as stated in Table 6. If not within 2% of the target part-load Capacity $^2$ then interpolate per Section 5.4.3.2.	No requirement					
Evaporator	Entering Water Temperature Leaving Water Temperature Entering Water	Cooling	No Requirement		$s_T \le 0.10  ^{\circ}C$						
Condenser	Temperature  Leaving Water  Temperature				No Requirement	_					
Condenser	Entering Air Mean Dry Bulb Temperature <sup>3</sup> Entering Air Mean Wet Bulb Temperature <sup>3</sup>	Cooling with fan cycling	T	S <sub>T</sub>	$\left \overline{T} - T_{\text{target}}\right  \le 0.56 ^{\circ}\text{C}$	$S_T \le 0.42  ^{\circ}C$					
Evaporator	Entering Water Temperature <sup>3</sup>				Heating portion: No requirement  Defrost portion: $\left  \overline{T} - T_{\text{target}} \right  \leq 1.11 ^{\circ}\text{C}$	Heating portion: $s_T \le 0.10 ^{\circ}\text{C}$ Defrost portion: $s_T \le 0.28 ^{\circ}\text{C}$					
Evaporator	Leaving Water Temperature <sup>3</sup>	<sup>3</sup> Heating,		S <sub>T</sub>	Heating portion: $\left  \overline{T} - T_{target} \right  \le 0.28  ^{\circ}\text{C}$ Defrost portion: no requirement	Heating portion: $s_T \le 0.10 ^{\circ}\text{C}$ Defrost portion: no requirement					
Condenser	Leaving Water Temperature Entering Water Temperature	Heat Recovery	T	-1	$\left \overline{T} - T_{\text{target}}\right  \le 0.28 ^{\circ}\text{C}$ No Requirement	$s_T \le 0.10  ^{\circ}C$					

	Table 1. Definition of Operating Condition Tolerances and Stability Criteria (continued)								
Measurement or Calculation Result		Applicable Operating Mode(s)  Values Calculated Data Sample Sta			Operating Condition Tolerance Limits	Stability Criteria			
			Mean	Deviation					
	Entering Air	Cooling, Heating (non-frosting)			$\left  \overline{T} - T_{\text{target}} \right  \le 0.56  ^{\circ}\text{C}$	$s_T \le 0.42  ^{\circ}C$			
Evenemeter	Mean Dry Bulb Temperature <sup>1</sup>	Heating (frosting) <sup>4</sup>			Heating portion: $ \overline{T} - T_{target}  \le 1.11 ^{\circ}\text{C}$	Heating portion: $s_T \le 0.56$ °C			
Evaporator or	Temperature	, , , , , , , , , , , , , , , , , , ,	$\overline{\mathtt{T}}$	s <sub>T</sub>	Defrost portion: no requirement for $\overline{T}$	Defrost portion: $s_T \le 1.39$ °C			
Condenser	Entering Air	Cooling, Heating (non-frosting)	1	$J_{T}$	$\left  \overline{T} - T_{\text{target}} \right  \le 0.56  ^{\circ}\text{C}$	$s_T \le 0.28^{\circ}\text{C}$			
	Mean Wet Bulb Temperature <sup>1</sup>	Heating (frosting) <sup>4</sup>			Heating portion: $\left  \overline{T} - T_{\text{target}} \right  \le 0.83 ^{\circ}\text{C}$	Heating portion: $s_T \le 0.42$ °C			
	Temperature	ricating (nosting)			Defrost portion: no requirement for $\overline{T}$	No requirement			
Water Flow (Volumetric, Entering)		Cooling, Heating, Heat Recovery	$\overline{V}_w$	$s_{Vw}$	$\frac{\left \overline{V}_{w} - V_{w,\text{target}}\right }{V_{w,\text{target}}} \le 5.000\%$	$\frac{s_{V_w}}{\overline{V}_w} \le 0.750\%$			
(if multipha	Voltage <sup>5</sup> ase, this is the average of all phases)	Cooling, Heating, Heat Recovery	$\overline{ m V}$	s <sub>V</sub>	$\frac{\left \overline{V} - V_{\text{target}}\right }{V_{\text{target}}} \le 10.00\%$	$\frac{s_V}{\overline{V}} \le 0.500\%$			
	Frequency 5	Cooling, Heating, Heat Recovery	ū	$s_{\omega}$	$\frac{\left \overline{\omega} - \omega_{\text{target}}\right }{\omega_{\text{target}}} \le 1.000\%$	$\frac{s_{\omega}}{\overline{\omega}} \le 0.500\%$			
Condenserless Refrigerant Saturated Discharge Temperature		Cooling	$\overline{\mathtt{T}}$	s <sub>T</sub>	$\left \overline{T} - T_{\text{target}}\right  \le 0.28^{\circ}\text{C}$	$s_T \le 0.14  ^{\circ}C$			
Condenserless Liquid Temperature		Cooling	$\overline{\mathtt{T}}$	$s_{\mathrm{T}}$	$\left  \overline{T} - T_{\text{target}} \right  \le 0.56  ^{\circ}\text{C}$	$s_T \le 0.28  ^{\circ}C$			
Steam Turbine Pressure/Vacuum <sup>6</sup> Gas Turbine Inlet Gas Pressure <sup>6</sup>		Cooling, Heating, Heat Recovery	p	Sp	$\left  \overline{p} - p_{\text{rating}} \right  \le 3.45 \text{kPa}$	s <sub>p</sub> ≤ 1.72 kPa			
Governor (	Control Compressor Speed <sup>7</sup>	Cooling, Heating, Heat Recovery	n	s <sub>n</sub>	$\frac{\left \overline{n} - n_{\text{target}}\right }{n_{\text{target}}} \le 0.500\%$	$\frac{s_n}{\overline{n}} \le 0.250\%$			

#### Notes:

- 1. The target set point condenser entering temperatures (Table 6) are determined at the target part-load test point.
- 2. The  $\pm$  2.0% tolerance shall be calculated as 2.0% of the Full Load rated Capacity (ton<sub>R</sub>). For example, a nominal 50.0% part load point shall be tested between 48.0% and 52.0% of the Full Load Capacity to be used directly for IPLV.SI and NPLV.SI calculations. Outside this tolerance, interpolation shall be used.
- 3. The "heat portion" shall apply when the unit is in the heating mode except for the first ten minutes after terminating a defrost cycle. The "defrost portion" shall include the defrost cycle plus the first ten minutes after terminating the defrost cycle.
- 4. When computing average air temperatures for heating mode tests, omit data samples collected during the defrost portion of the cycle.
- 5. For electrically driven machines, voltage and frequency shall be maintained at the nameplate rating values within tolerance limits and stability criteria on voltage and frequency when measured at the locations specified by ANSI/ASHRAE Standard 30. For dual nameplate voltage ratings, tests shall be performed at the lower of the two voltages.
- 6. For steam turbine and gas turbine drive machines the pressure shall be maintained at the nameplate rating values within the tolerance limits.
- 7. For speed-controlled compressors the speed shall be maintained at the nameplate rating value within the tolerance limits.

**4.8** Air Temperature Measurement. In addition to Table 1, air temperature measurement shall be in accordance with Table 2. For evaporatively-cooled units and heat pump chillers operating in heating mode, either wet-bulb temperature or dewpoint shall be measured. If dewpoint is measured, wet-bulb temperature shall be calculated and recorded.

Table 2. Temperature Measurement Requirements									
Measurement	Measurement System Accuracy	Measurement Resolution	Selected, Installed, Operated, Maintained in Accordance with						
Dry-Bulb and Wet-Bulb Temperatures <sup>2</sup>	Per ANSI/ASHRAE Standard 30	Per ANSI/ASHRAE Standard 30							
Air Sampling Tree Average Temperature <sup>1</sup>	Per ANSI/ASHRAE Standard 30	Per ANSI/ASHRAE Standard 30	ANSI/ASHRAE Standard 41.1						
Dewpoint Temperature <sup>3</sup>	±0.2 K	≤ 0.05 K							

**4.9** Air Sampling Array Requirements. The air sampling array is an alternative to utilizing a thermopile grid. measurement devices shall be positioned to measure at the four (4) locations shown in Figure 1 within 5% of overall width and height, where W and H are condenser air inlet nominal face area width and height.

Where the W or H dimension is less than or equal to 60 cm, at least one (1) temperature measurement shall be used in that dimension. For example, if W = 60 cm and H = 120 cm, at least two (2) temperature measurements shall be used for that area.

Table 3 criteria for air distribution and control of air temperature shall be met. For evaporatively-cooled units and heat pump chillers operating in heating mode, either wet-bulb temperature or dewpoint shall be measured. If dewpoint is measured, wet-bulb temperature shall be calculated and recorded. Wet-bulb temperature is not required for other unit types.




Figure 1. Air Sampling Array

Table 3. Criteria for Air Distribution and Control of Air Temperature								
Item	Purpose	Deviation from Mean Value, °C						
Dry-bulb Temperature								
Mean measurement of an Air	Uniform temperature	±1.11 (≤700.0 kW)						
Sampling Array	distribution	±2.22 (>700.0 kW)						
Individual measurements in an Air Sampling Array	Uniform temperature distribution	±0.83						
Condenser discharge air recirculation measurement as compared to associated Air Sampling Array.	Recirculation Check	±2.80						
Wet-bulb Temperature								
Wet-bulb temperature at any individual temperature measurement station	Uniform humidity distribution	±0.56						

#### Section 5. Rating Requirements

#### **5.1** Rating Metrics.

**5.1.1** *Cooling Energy Efficiency*. The general form of Cooling Energy Efficiency is shown in Equation 14. This term is calculated at both design point and at part load conditions.

Note: Refer to Section 5.4.3.2.7 for part load degradation factor adjustment and Appendix C for atmospheric pressure adjustment.

**5.1.1.1** The Cooling Coefficient of Performance (COP<sub>R</sub>), kW/kW, shall be calculated using Equation 14:

$$COP_{R} = \frac{Q_{ev}}{W_{input}}$$

**5.1.2** *Heating Energy Efficiency*. The general forms of the Heating Energy Efficiency terms are listed as Equations 15 through 17. These terms are calculated at both design point and at part load conditions.

Note: Refer to Section 5.4.2.3.7 for part load degradation factor adjustment and Appendix C for atmospheric pressure adjustment.

**5.1.2.1** The Heating Coefficient of Performance (COP<sub>H</sub>), kW/kW, shall be calculated using Equation 15:

$$COP_{H} = \frac{Q_{cd}}{W_{input}}$$

**5.1.2.2** The Heat Recovery Coefficient of Performance (COP<sub>HR</sub>), kW/kW shall be calculated using Equation 16:

$$COP_{HR} = \frac{Q_{ev} + Q_{hrc}}{W_{input}}$$

**5.1.2.3** The Simultaneous Heating and Cooling Coefficient of Performance (COP<sub>SHC</sub>), kW/kW, shall be calculated using Equation 17:

$$COP_{SHC} = \frac{Q_{cd} + Q_{ev}}{W_{input}}$$

**5.1.3** *Net Refrigerating Capacity*. The Net Refrigerating Capacity, kW, for the Evaporator shall use the water temperatures, water mass flow rate and water properties at the Evaporator entering and leaving conditions and be calculated using Equation 18:

$$Q_{ev} = m_w \cdot c_n \cdot (T_{in} - T_{out})$$

Specific heat  $c_p$  is taken at the average of entering and leaving water temperatures. When expressing water flow rate in volumetric terms for ratings, the conversion from mass flow rate shall use water density corresponding to entering water temperature (Refer to Equation 37). The volumetric flow rate shall be calculated using Equation 19:

$$V_w = \frac{m_w}{\rho_{in}}$$

**5.1.4** *Net Heating Capacity*. The Net Heating Capacity, KW, for either a heat rejection, or heat recovery Condenser, and other heat rejection devices (e.g. oil coolers, inverters, etc.), shall use the water temperatures, water flow rate, and water properties at the entering and leaving conditions and be calculated using Equations 20 or 21:

$$Q_{cd} = m_w \cdot c_p \cdot (T_{out} - T_{in})$$

$$Q_{hrc} = m_w \cdot c_p \cdot (T_{out} - T_{in})$$
 21

Specific heat  $c_p$  is taken at the average of entering and leaving water temperatures. When expressing water flow rate in volumetric terms for ratings, the conversion from mass flow rate shall use water density corresponding to entering water temperature (Refer to Equations 19 and 37).

- **5.1.5** Water Pressure Drop. For this standard, the Water Pressure Drop shall include pressure losses due to nozzles, piping, or other interconnections included with the Water-chilling or Water-heating Package and shall include all pressure losses across the external unit connection points for water inlet and water outlet. For Published Ratings, this value is expressed in kPa at a reference water temperature of 15.6 °C. For test measurements, this is a differential pressure expressed in kPa. For the calculation of Water Pressure Drop, Refer to ANSI/ASHRAE Standard 30. Note the requirements for a single inlet and single outlet as described in Section 4.4.
- **5.2** Standard Ratings and Conditions. Standard Ratings for all Water-chilling Packages shall be established at the Standard Rating Conditions. These packages shall be rated for cooling, heat recovery, or heating performance at conditions specified in Table 4. Standard Ratings shall include a water-side Fouling Factor Allowance as specified in the notes section of Table 4. Chiller packages consisting of multiple units and rated as a single package shall be tested as rated.

Table 4.	Standard	Rating	Conditions
----------	----------	--------	------------

					Cooling Mode Heat Rejection Heat Exchanger												
									Evaporatively-cooled Entering Temperature <sup>5, 7</sup>		Air-cooled (AC) Entering Temperature <sup>5, 7</sup>		Without Condenser				
Operating Category	Conditions	Cooling Mode Evaporator <sup>2</sup>		Tower (Water Conditions) <sup>3</sup>		Heat/Recovery (Water Conditions) <sup>4</sup>		Air-cooled Refrigerant Temperature					Water & Evaporatively Cooled Refrigerant Temperature				
		Entering Temper ature,	Leaving Tempera ture,	Flow Rate,	Entering Tempera ture,	Leaving Temper ature,	Flow Rate,	Entering Tempera ture,	Leaving Tempera ture,	Dry-Bulb,	Wet- Bulb,	Dry- Bulb,	Wet- Bulb,	SDT,	LIQ,	SDT,	LIQ,
		°C	°C	L/(s·kW)	°C	°C	L/(s·kW)	°C	°C	°C	℃	°C	°C	°C	°C	°C	°C
All Cooling	Standard	12.00	7.00	Note - 8	30.00	35.00	Note - 9			35.00	24.00	35.0		52.0	41.0	41.00	37.00
AC Heat	Low		40.00	Note - 1								8.00	6.00				
Pump High	Medium		50.00	Note - 1								8.00	6.00				
Heating <sup>6</sup>	High		60.00	Note - 1								8.00	6.00				
AC Heat	Low		40.00	Note - 1								-8.00	-9.00				
Pump Low	Medium		50.00	Note - 1								-8.00	-9.00				
Heating <sup>6</sup>	High		60.00	Note - 1								-8.00	-9.00				
***	Low		7.00	Note - 8				35.00	40.00								
Water Cooled	Medium		7.00	Note - 8				42.00	50.00								
	High		7.00	Note - 8				50.00	60.00								
Heating	Boost		19.00	Note - 8				50.00	60.00			1					
	Low		7.00	Note - 8	24.00		Note - 9	35.00	40.00	4.00	3.00	4.00	3.00				
Heat	Medium		7.00	Note - 8	24.00		Note - 9	42.00	50.00	4.00	3.00	4.00	3.00				
Recovery	Hot Water 1		7.00	Note - 8	24.00		Note - 9	32.00	60.00	4.00	3.00	4.00	3.00				
	Hot Water 2		7.00	Note - 8	24.00		Note - 9	50.00	60.00	4.00	3.00	4.00	3.00				

#### Notes:

- 1. The water flow rate used for the heating tests of reverse cycle air to water heat pumps shall be the flow rate determined during the cooling test.
- 2. The rating Fouling Factor Allowance for the cooling mode Evaporator or the heating Condenser for AC reversible cycles shall be  $R_{\text{foul}} = 0.0180 \text{ m}^2 \cdot \text{K/kW}$ .
- 3. The rating Fouling Factor Allowance for tower heat exchangers shall be  $R_{\text{foul}} = 0.0440 \text{ m}^2 \cdot \text{K/kW}$ .
- 4. The rating Fouling Factor Allowance for heating and heat recovery heat exchangers shall be  $R_{foul} = 0.0180 \text{ m}^2 \cdot \text{K/kW}$  for closed loop and  $R_{foul} = 0.0440 \text{ m}^2 \cdot \text{K/kW}$  for open loop systems.
- 5. Evaporatively cooled Condensers and Air-cooled Condensers shall be rated with a Fouling Factor Allowance of zero,  $R_{foul} = 0.000 \text{ m}^2 \cdot \text{K/kW}$ .
- 6. A reversible cycle is assumed where the cooling mode Evaporator becomes the condenser circuit in the heating mode.
- 7. Air-cooled & evaporatively-cooled unit ratings are at standard atmospheric condition (sea level). Measured test data shall be corrected to an atmospheric pressure of 101.33 kPa per Appendix C.
- 8. Rated water flow is determined by the water temperatures at the rated Cooling Capacity.
- 9. Rated water flow is determined by the water temperatures at the rated Capacity and rated efficiency.

5.3 Application Rating Conditions. Full and part-load Application Ratings shall include the range of Rating Conditions listed in Table 5 or be within the operating limits of the equipment. For guidance to the industry, designing to large Fouling Factors significantly impacts the performance of the chiller. It is best to maintain heat transfer surfaces by cleaning or maintaining proper water treatment to avoid highly fouled conditions and the associated efficiency loss. From a test perspective, highly fouled conditions are simulated with clean tubes by testing at decreased Evaporator water temperatures and increased Condenser water temperatures. High Fouling Factors can increase or decrease these temperatures to conditions outside test loop or equipment capabilities. For this test standard, the application range for the water side fouling shall be between clean (0.000) and 0.180 m<sup>2</sup>·K/kW. Fouling Factors above these values are outside of the scope of this standard and shall be noted as such.

Table 5. Full and Part-load Application Rating Conditions								
		Evaporator	Condenser					
	Water Cooled			Water Cooled				
Cooling	Leaving Temperature <sup>1</sup> , °C	Temperature Difference Across Heat Exchanger <sup>5</sup> , K	Fouling Factor Allowance, m <sup>2</sup> · K/kW	Entering Temperature <sup>2</sup> , °C	Flow Rate <sup>5, 7</sup> , L/(s·kW)		Fouling Factor Allowance, m <sup>2</sup> ·K/kW	
	2.20 to 21.10	2.80 to 11.10	0.000 to 0.180	12.80 to 46.11	0.0179 to 0.1076		0.000 to 0.180	
				Air-cooled				
				Entering Air Dr	ry Bulb <sup>3,</sup> Atmos		pheric Pressure <sup>6</sup> , kPa	
				12.8 to 52.0		79.	79.70 to 104.8	
				Evaporatively Cooled				
				Entering Air Wet Bulb <sup>4</sup> , °C		Atmospheric Pressure <sup>6</sup> , kPa		
				10.0 to 26.7		79.70 to 104.8		
	Water Source Evaporator			Water Cooled Condenser				
Heating		r Temperature <sup>1</sup> , C	Fouling Factor Allowance, m <sup>2</sup> · K/kW	Leaving Water Temperature <sup>2</sup> , °C	Tempe Differ Across Excha	rence s Heat nger <sup>5</sup> ,	Fouling Factor Allowance, m <sup>2</sup> ·K/kW	
	4.44 to 26.67		0.000 to 0.180					
	Air Source Evaporator			40.56 to	2.80 to		0.000 to	
			mospheric	71.11	16.67		0.180	
			essure <sup>6</sup> , kPa 70 to 104.8					

#### Notes:

- 1. Evaporator water temperatures shall be published in rating increments of no more than 2.00 °C
- 2. Condenser water temperatures shall be published in rating increments of no more than 3.00 °C.
- 3. Entering air temperatures shall be published in rating increments of no more than 5.0 °C.
- 4. Air wet bulb temperatures shall be published in rating increments of no more than 1.5 °C.
- 5. Applies to design point only, not part-load points.
- 6. Rated altitude not exceeding 1980 m. Measured test data shall be corrected per Appendix C to the application rating atmospheric pressure.
- 7. The normalized flow rate is per unit of Evaporator Capacity.

- **5.3.1** For the purpose of this standard, published Application Ratings shall use a standardized relationship between rated geometric altitude ( $Z_H$ ) above mean sea level and atmospheric pressure ( $p_{atm}$ ). This enables chiller Application Ratings to be published based on the nominal altitude at the installation location without consideration of local weather variations on atmospheric pressure. Test data however shall be corrected on the basis of atmospheric pressure at the time of the test. See Section 7 and Appendix C.
- **5.4** *Part-load Ratings*. Water-chilling Packages shall be rated at 100%, 75%, 50%, and 25% load relative to the full-load rating Net Refrigerating Capacity at the conditions defined in Table 6. For chillers capable of operating in multiple modes (cooling, heating, and /or heat recovery), part-load ratings are only required for cooling mode operation.
  - **5.4.1** *Cooling Part-load Ratings.* Cooling mode Part-load ratings shall be presented in one of the four following ways:
    - **5.4.1.1** *IPLV.SI.* Based on the conditions defined in Table 6 and method defined in Section 5.4.3.
    - **5.4.1.2** *NPLV.SI*. Based on the conditions defined in Table 6 and method defined in Section 5.4.3. It is optional to publish NPLV.SI when Table 8, Note 5 applies.
    - **5.4.1.3** *Individual Part-load Data Point(s).* Individual part-load data point(s) used for calculating IPLV.SI or NPLV.SI as defined in Table 6.
    - **5.4.1.4** Other Part-load Points. Other part-load points, within the Application Rating limits of Table 5 and method defined in Section 5.4.4, that do not meet the requirements of Table 6, Notes 3, 4, 5, or 6 (i.e. variable water flow rates or other entering Condenser water temperatures). Neither IPLV.SI nor NPLV.SI shall be calculated for such points and shall not be a requirement for publication per Section 6.
  - **5.4.2** *Heating Part-load Ratings.* Heat Pump Water-heating Packages and Heat Recovery Water-chilling Packages can be rated at individual part load points. Neither IPLV.SI nor NPLV.SI shall be calculated for such points.
  - **5.4.3** Determination of Part-load Performance. For Water-chilling Packages covered by this standard, the IPLV.SI or NPLV.SI shall be calculated as follows:

Determine the Part-load energy efficiency at 100%, 75%, 50%, and 25% load points at the conditions specified in Table 6.

Use Equation 22 to calculate the IPLV.SI or NPLV.SI for units rated with COP<sub>R</sub>.

IPLV.SI or NPLV.SI = 
$$0.01 \cdot A + 0.42 \cdot B + 0.45 \cdot C + 0.12 \cdot D$$

22

For COP<sub>R</sub> where:

 $A = COP_R$  at 100% load

 $B = COP_R$  at 75% load

 $C = COP_R$  at 50% load

 $D = COP_R$  at 25% load

**5.4.3.1** For a derivation of Equation 22, and an example of an IPLV.IP or NPLV.IP calculation, see Appendix D. The weighting factors have been based on the weighted average of the most common building types and operations using average weather in 29 U.S. cities, with and without airside economizers.

Table 6. Part-load Conditions for Rating						
	IPLV.SI	NPLV.SI				
Evaporator (All Types)						
All loads LWT <sup>2</sup> , °C	7.00	User defined LWT				
Flow Rate <sup>3</sup> (L/s per kW)	Per Table 4	Per Table 4 <sup>3</sup>				
$R_{\text{foul}}$ , $m^2 \cdot K/kW$	0.018	User defined				
Water-cooled Condenser <sup>1,2</sup>						
100% load EWT, °C	30.00	User defined EWT				
75% load EWT, °C	24.50	Equation 24				
50% load EWT, °C	19.00	Equation 24				
25% load EWT, °C	19.00	Equation 24				
Flow rate, L/s per kW <sup>3</sup>	Note <sup>3</sup>	User defined flow rate				
R <sub>foul</sub> m <sup>2</sup> · K/kW	0.044	User defined				
Air-cooled Condenser <sup>1,47</sup>						
100% load EDB, ℃	35.0	User defined EDB				
75% load EDB, °C	27.0	Equation 23				
50% load EDB, ℃	19.0	Equation 23				
25% load EDB, ℃	13.0	Equation 23				
R <sub>foul</sub> , m <sup>2</sup> ·K/kW	0.000	User defined				
Evaporatively-cooled						
Condenser <sup>14,7</sup>						
100% load EWB, °C	24.00	User defined EWB				
75% load EWB, °C	20.50	Equation 25				
50% load EWB, °C	17.00	Equation 25				
25% load EWB, °C	13.50	Equation 25				
$R_{\text{foul}},  \text{m}^2 \cdot \text{K/kW}$	0.000	User defined				
Air-cooled Without Condenser						
100% load SDT, °C	52.00	User defined SDT				
75% load SDT, °C	42.00	Equation 26				
50% load SDT, °C	32.00	Equation 26				
25% load SDT, °C	22.00	Equation 26				
$R_{\text{foul}},  \text{m}^2 \cdot \text{K/kW}$	0.000	User defined				
Water-cooled or Evaporatively-						
cooled Without Condenser						
100% load SDT, °C	41.00	User defined SDT				
75% load SDT, °C	35.50	Equation 27 or 28				
50% load SDT, °C	30.00	Equation 27 or 28				
25% load SDT, °C	24.50	Equation 27 or 28				
R <sub>foul</sub> , m <sup>2</sup> ·K/kW	0.000	User defined				

#### Notes:

- 1. If the unit manufacturer's recommended minimum temperatures are greater than those specified in Table 6, then those shall be used in lieu of the specified temperatures. If head pressure control is active below the rating temperature, then tests shall be run per the Section 5.8 test procedure.
- 2. Correct for Fouling Factor Allowance by using the calculation method described in Section 4.6.
- 3. The flow rates are to be held constant at full-load values for all part-load conditions as per Table 4.
- 4. Air-cooled and evaporatively-cooled unit ratings are at standard atmospheric condition (sea level). Measured data shall be corrected to standard atmospheric pressure of 101.33 kPa per Appendix C.

**5.4.3.2** The IPLV.SI or NPLV.SI rating requires that the unit efficiency be determined at 100%, 75%, 50% and 25% at the conditions as specified in Table 6. If the unit, due to its capacity control logic cannot be operated at 75%, 50%, or 25% within  $\pm 2$ % Percent Load as required by Table 1, then the unit shall be operated at other load points and the 75%, 50%, or 25% capacity efficiencies shall be determined using interpolation as defined in 5.4.5. Extrapolation of data shall not be used. The capacity points as close as possible to the rating load shall be used.

For example, if the minimum actual Capacity is 33% then the curve can be used to determine the 50% capacity point, but not the 25% capacity point. When unit cannot be unloaded to or below the rating point refer to section 5.4.3.2.7 for the use of degradation procedure.

Note: %Load shown in the equations below is in decimal form (e.g.100 %Load = 1.0) and is defined in Section 3.12.

**5.4.3.2.1** *IPLV.SI Interpolation.* If the units cannot run at any of the 75%, 50% or 25% load points within a tolerance of  $\pm 2\%$  but is capable of running at load above and below the rating Percent Load of 75%, 50% or 25% interpolation of the test points shall be used to determine the rating efficiency using the Condenser entering condition listed in Table 6. The same Condenser temperature shall be used for both interpolation points. The capacity point closest to the desired rating load point shall be used.

Note: In the 2020 and later versions of AHRI Standard 551/591 (SI), the part-load rating Condenser temperatures have been fixed at the 100%, 75%, 50% and 25% load values shown in Table 6. In the 2018 and prior versions of the AHRI Standard 551/591 (SI) the Condenser temperature was a function of the actual load and required iteration if the Capacity measured was not what was assumed to get the Condenser temperature for the test. This change does not impact the units that can run at the 75%, 50%, and 25% load conditions; however, for interpolating ratings the Condenser temperature is now fixed at the 75%, 50% and 25% load rating points.

Two tests are run at different loads above and below the rating point at the same Condenser temperature. For example, if the unit is an air cooled chiller and the rating for 75% load is being determined, but the unit can only run at 80% load and 60% load, then the unit can be run at the 80% and 60% load at 27.0 °C ambient temperature. Figure 2 also shows the difference between the AHRI Standard 551/591 (SI)-2020 and the prior version of AHRI Standard 551/591 (SI) for this example air cooled 75% rating point.




Figure 2. Interpolated IPLV.SI Condition

In the Figure 2 example, the following calculations for interpolation are used (see Equations 32 and 33).

Point 1: (60%, 3.224)Point 2: (80%, 3.077)Interpolated Point:  $(75\%, \eta_{int})$ 

exponent = 
$$\log_{10}(3.224) + (0.75 - 0.60) \cdot \frac{[\log_{10}(3.077) - \log_{10}(3.224)]}{(0.80 - 0.60)} = 0.49319438$$

$$\eta_{int} = 10^{(0.49319438)} = 3.113 \ COP$$

**5.4.3.2.2** Entering air dry-bulb temperature (EDB), °C, for an Air-cooled Condenser at NPLV.SI part load conditions shall use Equation 23 where T<sub>100%</sub> is the selected 100% Load EDB temperature:

EDB = 
$$\begin{vmatrix} \frac{163}{112} (T_{100\%} - 13) \left( \% Load - 0.3125 \frac{4}{3} \right) + 13 & \text{for Load} > 31.25\% \\ 13 & \text{for Load} \le 31.25\% \end{vmatrix}$$

Note: In the case of an Air-cooled Chiller, the Load term used to calculate the EDB temperature is based on the adjusted Capacity after using the atmospheric pressure correction.

**5.4.3.2.3** Entering water temperature (EWT),  $^{\circ}$ C, for a Water-cooled Condenser at NPLV.SI part load conditions shall use Equation 24 where  $T_{100\%}$  is the selected 100% Load EWT:

EWT = 
$$\left| \frac{2(T_{100\%} - 19)(\%Load - \frac{1}{2}) + 19}{19} \right|$$
 for Load  $> 50.00\%$  for Load  $\le 50.00\%$ 

**5.4.3.2.4** Entering air wet-bulb temperature (EWB), °C, for an Evaporatively-cooled Condenser at NPLV.SI part load conditions shall use Equation 25:

$$EWB = (T_{100\%} - 10) \cdot \%Load + 10$$
 25

**5.4.3.2.5** Saturated discharge temperature (SDT), °C, for an air-cooled unit without Condenser at NPLV.SI part load conditions shall use Equation 26:

AC SDT = 
$$(T_{100\%} - 12) \cdot \%Load + 12$$
 26

**5.4.3.2.6** Saturated discharge temperature (SDT), °C, for a water-cooled or evaporatively-cooled unit without Condenser at NPLV.SI part load conditions shall use Equation 27 or 28:

water-cooled: SDT = 
$$(T_{100\%} - 19) \cdot \%Load + 19$$

evaporatively-cooled: SDT = 
$$(T_{100\%} - 19) \cdot \%Load + 19$$
 28

**5.4.3.2.7** If a unit cannot be unloaded to the 25%, 50%, or 75% capacity point, then the unit shall be run at the minimum step of unloading at the Condenser entering water or air temperature based on Table 6 for 25%, 50% or 75% capacity points as required. The efficiency shall then be determined by using Equation 29:

$$COP_{R,CD} = \frac{COP_{Test}}{C_D}$$
 29

**5.4.3.2.8** COP<sub>Test</sub> is the efficiency at the test conditions (after atmospheric pressure adjustment as per Appendix C, as applicable) and  $C_D$  is a degradation factor to account for cycling of the compressor for capacities less than the minimum step of Capacity.

C<sub>D</sub> shall be calculated using Equation 30:

$$C_D = (-0.13 \cdot LF) + 1.13$$

Where LF is the load factor calculated using Equation 31:

$$LF = \frac{(\%Load) (Q_{100\%})}{(Q_{\min\%Load})}$$
 31

Part-load unit Capacity is the measured or calculated unit Capacity from which Standard Rating points are determined using the method above.

**5.4.3.3** Procedures for Testing and Calculation of IPLV.SI or NPLV.SI for Continuous Capacity Control Units.

For fully continuous capacity controlled units or units with a combination of staged Capacity and continuous Capacity covered by this standard, the IPLV.SI or NPLV.SI shall be calculated using test data and or rating data using the following procedures.

For test purposes, units shall be provided with manual means to adjust the unit refrigeration Capacity by adjusting variable capacity compressor(s) Capacity and or the stages of refrigeration Capacity as defined by the manufacturer's instructions.

The following sequential steps shall be followed:

**5.4.3.3.1** Step 1. The unit shall be configured per the manufacturer's instructions, including setting of stages of refrigeration and variable capacity compressor loading percent for each of the four rating percent load rating points of 100%, 75%, 50%, and 25%.

The Condenser entering temperature shall be adjusted per the requirements of Table 6 as determined by the rating Percent Load of 100%, 75%, 50% and 25% and be within the required temperature limits per Table 1 for the 100% rating point and for the 75%, 50% and 25% points if the adjusted Capacity is within 2% of the rating Percent Load. If the adjusted measured Percent Load difference is outside the 2% tolerance, as defined by Table 1, then the interpolation procedure defined in 5.4.3.2 shall be used with a point above and below the rating Percent Load. If the unit can operate with head pressure control active during any of the tests at the specified Condenser temperature which can cause cycling and stable test conditions cannot be maintained, then the applicable procedures defined in Sections 5.4.4.2 and/or 5.8 shall be used.

If the unit is an air-cooled chiller or evaporatively-cooled, then the measured Capacity and efficiency shall be adjusted for atmospheric pressure using the procedures of Appendix C. No adjustment is required for water-cooled units.

The full-load Capacity shall be within the tolerance range defined by Table 7. If the Capacity is not in compliance with the requirements, the test shall be repeated.

If the adjusted part load test Capacity is within  $\pm 2\%$  of the target Percent Load of 75%, 50% and 25% then the adjusted efficiency can be used directly to calculate the IPLV.SI or NPLV.SI. If the adjusted Capacity of any point is not within the  $\pm 2\%$  tolerance as required by Table 1, then the test shall be repeated or move to Step 2 or Step 3.

**5.4.3.3.2** Step 2. If the unit, due to its capacity control logic cannot be operated at the rating 75%, 50%, or 25% Percent Load point within  $\pm 2\%$ , then additional test points for use in interpolation are required. Capacity staging and variable Capacity shall be selected to have one test as close as possible to the desired rating point with an adjusted Capacity above the desired rating Percent Load rating point of 75%, 50% and 25% and a second test as close as possible to the desired rating Percent Load with an adjusted Capacity below the desired rating Percent Load of 75%, 50%, and 25%.

The Condenser entering temperature shall be adjusted per the requirements of Table 6 for the rating point Percent Load and be within the required temperature limits per Table 1. The same Condenser entering air temperature shall be used for both interpolation points.

The test Capacity and efficiency for air and evaporatively-cooled chillers shall then be adjusted for atmospheric pressure using the procedures of Appendix C. No adjustment is required for water-

cooled units.

Interpolation per Section 5.4.5 between the two adjusted capacity points shall then be used to determine the efficiency at the rating 75%, 50% or 25% Percent Load point, using the entering Condenser temperature per Table 6 at the rating Percent Load. Data shall not be extrapolated and there shall be a test point above and below the rating Percent Load point.

**5.4.3.3.3** Step 3. If the unit cannot be unloaded to any of the 75%, 50%, or 25% rating points at the minimum stage of unloading then the unit shall be run at the minimum stage of Capacity for each of the test points where appropriate.

The Condenser entering temperature shall be adjusted per the requirements of Table 6 using the rating Percent Load of 75%, 50%, or 25% and be within the required temperature limits per Table 1. If the unit can operate with head pressure control active during the test at a specified Condenser temperature which can cause cycling and stable test conditions cannot be maintained, then the Section 5.8 test procedure shall be followed.

The Capacity and efficiency for air and evaporatively-cooled chillers shall then be adjusted for atmospheric pressure using the procedures of Appendix C. No adjustment is required for Water-cooled chillers.

If the data for the lowest stage of Capacity is above the desired rating point load with allowance for the 2% tolerance then the efficiency shall then be adjusted for cyclic degradation using the degradation procedures outlined in 5.4.3.2.7.

**5.4.3.3.4** Step 4. Once the adjusted efficiency for each of the 100%, 75%, 50% and 25% rating Percent Load rating points is determined using Steps 1, 2, or 3 as appropriate, then the IPLV.SI or NPLV.SI shall be calculated using Equation 22.

**5.4.3.4** Procedures for Testing and Calculation of IPLV.SI or NPLV.SI for Discrete Capacity Step Controlled Units.

For discrete capacity step controlled units, including units with only a single stage of Capacity, the IPLV.SI or NPLV.SI shall be calculated using test data and or rating data obtained using the following procedures.

For test purposes, units shall be provided with manual means to adjust the unit refrigeration Capacity by adjusting the stages of refrigeration Capacity as defined by the manufacturer's instructions.

The following sequential steps shall be followed:

**5.4.3.4.1** Step 1. The unit shall be configured per the manufacturer's instructions, including setting of stages of refrigeration for each of the 4 rating Percent Load rating points of 100%, 75%, 50%, and 25%.

The Condenser entering temperature shall be adjusted per the requirements of Table 6 as determined by the rating Percent Load of 100%, 50%, 75% and 25% and be within the required temperature limits per Table 1. If the unit can operate with head pressure control active during the test at the specified Condenser temperature which can cause cycling and stable test conditions cannot be maintained, then the Section 5.8 test procedure shall be followed.

If the unit is an air-cooled chiller, then the measured Capacity and efficiency shall be adjusted for atmospheric pressure using the procedures of Appendix C. No adjustment is required for Water-cooled units.

If the adjusted part load test Capacity is within 2% of the target Percent Load of 75%, 50% and 25% then the adjusted efficiency can be used directly to calculate the IPLV.SI or NPLV.SI. If the adjusted Capacity of any point is not within the 2% tolerance, then move to Step 2 or 3.

**5.4.3.4.2** Step 2. If the unit, due to its capacity control logic cannot be operated at the rating 75%, 50%, or 25% Percent Load point within 2%, then additional test points for use in interpolation as defined in Section 5.4.5 are required. Capacity staging shall be selected to have one test as close as possible to the desired rating point with an adjusted Capacity above the desired rating Percent Load rating point of 75%, 50% and 25% and a second test as close as possible to the desired rating Percent Load with an adjusted Capacity below the desired rating Percent Load of 75%, 50%, and 25%. Capacity staging with a Capacity greater or less than the capacity staging closest to the desired rating point shall not be used.

The Condenser entering temperature shall be adjusted per the requirements of Table 6 using the rating point Percent Load and be within the required temperature limits per Table 1. The rating point Percent Load Condenser entering temperature shall be used for both interpolation points.

The test Capacity and efficiency shall then be adjusted for atmospheric pressure using the procedures of Appendix C.

Interpolation per Section 5.4.5 between the two adjusted capacity points shall then be used to determine the efficiency at the rating 75%, 50% or 25% Percent Load point. Data shall not be extrapolated and there shall be a test point above and below the rating Percent Load point.

**5.4.3.4.3** Step 3. If the unit cannot be unloaded to any of the 75%, 50%, or 25% rating points within 2% at the minimum stage of unloading then the unit shall be run at the minimum stage of Capacity for each of the test points where appropriate.

The Condenser entering temperature shall be adjusted per the requirements of Table 6 using the rating Percent Load of 75%, 50%, or 25% and be within the required temperature limits per Table 1. If the unit can operate with head pressure control active during the test at the specified Condenser temperature which can cause cycling and stable test conditions cannot be maintained, then the Section 5.8 test procedure shall be followed.

The Capacity and efficiency shall then be adjusted for atmospheric pressure for air and evaporatively-cooled chillers using the procedures of Appendix C. No adjustment is required for Water-cooled units.

The efficiency shall then be adjusted for cyclic degradation using the procedures defined in 5.4.3.2.7.

- **5.4.3.4.4** *Step 4*. Once the adjusted efficiency for each of the 100%, 75%, 50% and 25% rating Percent Load rating points is determined using step 1, 2, or 3 as appropriate, then the IPLV.SI or NPLV.SI shall be calculated using Equation 22.
- **5.4.4** Determination of Part-load Performance within Application Rating Limits. Part load points not meeting the requirements of IPLV.SI or NPLV.SI, but within the Application Rating Condition limits in Table 5, shall be calculated as follows:
  - **5.4.4.1** For continuous capacity control chillers that can run at the application Percent Load within  $\pm 2\%$  of the desired Percent Load determine the part-load energy efficiency at the application Percent Load and Condenser entering temperature.
  - **5.4.4.2** If the chiller is expected to have capacity cycling at the Application Ratings Conditions, due to either compressor on/off staging or discrete step capacity control, then the rating method shall use logarithmic interpolation between two other non-cycling rating points, closest to the rating load listed in Table 6 with one point above and another point below the rating condition. The Condenser entering temperature shall be held constant at the desired part load rating point. Interpolation per Section 5.4.5 shall then be used to determine the efficiency at the Application Rating Conditions. Extrapolation shall not be used. For units operating in head pressure control, see Section 5.8.
  - **5.4.4.3** If the application Percent Load is below the lowest capacity stage of the unit then a performance point shall be determined at the application part load Condenser entering temperature and lowest stage of Capacity and the efficiency adjusted for cyclic degradation using the procedure in Section 5.4.3.2.7.

- **5.4.4.4** If the unit can operate with head pressure control active during the test at the specified applicable Percent Load and Condenser entering temperature, causing cycling such that stable test conditions cannot be maintained, then Section 5.8 test procedure shall be followed.
- **5.4.5** Interpolation of Efficiency Values. Calculations shall use the following method (Equations 32 and 33) when interpolating between two efficiency values  $\eta_1$  and  $\eta_2$  at different load points to determine an intermediate efficiency value  $\eta_{int}$  at another load point.

Point 1:  $(\%Load_1, \eta_1)$ Point 2:  $(\%Load_2, \eta_2)$ Interpolated Point:  $(\%Load_{int}, \eta_{int})$ 

exponent = 
$$\log_{10}(\eta_1) + (\%Load_{int} - \%Load_1) \cdot \frac{\left[\log_{10}(\eta_2) - \log_{10}(\eta_1)\right]}{(\%Load_2 - \%Load_1)}$$
 32

$$\eta_{int} = 10^{\text{(exponent)}}$$

- **5.5** *Publication of Ratings*. Wherever ratings are published or printed, they shall be consistent with the test method and procedures described in Sections 4 and 5 and ANSI/ASHRAE Standard 30, with consideration given to operating modes and sequence dependent (nondeterministic) control logic such as cycling of components.
- **5.6** Fouling Factor Allowances. When ratings are published, they shall include those with Fouling Factors as specified in Table 4 or within the ranges defined in Table 5.
  - **5.6.1** *Method of Establishing Clean and Fouled Ratings.* 
    - **5.6.1.1** A series of tests shall be run in accordance with the method outlined in Section 4 and ANSI/ASHRAE Standard 30 to establish the performance of the unit.
    - **5.6.1.2** Evaporator water-side and Condenser water-side or air-side heat transfer surfaces shall be considered clean during testing. Test conditions shall reflect Fouling Factors of zero (0.000) m2·K/kW.
    - **5.6.1.3** To determine the Capacity of the Water-chilling Package at the rated water-side fouling conditions, the procedure defined in Section 4.6 shall be used to determine an adjustment for the Evaporator and or Condenser water temperatures.

#### **5.7** *Tolerances*.

**5.7.1** *Tolerance Limit.* The tolerance limit for test results for net Capacity, full and part load Efficiency, and Water Pressure Drop shall be determined from Table 7. The tolerance limit (i.e. minimum or maximum acceptable value for Capacity, Efficiency, or Water Pressure Drop) shall be rounded to the number of Significant Figures in Table 8 prior to comparison with a test result rounded to the same number of Significant Figures.

The tolerance limits are intended to be used when testing a unit to verify and confirm performance. They take into consideration the following:

- **5.7.1.1** *Uncertainty of Measurement.* When testing a unit, there are variations that result from instrumentation accuracy and installation affects, as well as test facility stability.
- **5.7.1.2** *Uncertainty of Test Facilities*. The tested performance of the same unit tested in multiple facilities can vary due to setup variations.
- **5.7.1.3** *Uncertainty due to Manufacturing*. During the manufacturing of units, there are variations due to manufacturing production tolerances that can impact the performance from unit to unit.
- **5.7.1.4** *Uncertainty of Performance Prediction Models.* Due to the large complexity of options, manufacturers can use performance prediction models to determine ratings.

To comply with this standard, any test per Section 4.1 to verify published or reported values shall be in accordance with Table 7.

Table 7. Definition of Tolerances							
		Limits	Related Tolerance Equations <sup>2,3</sup>				
y	Cooling or heating Capacity for units with continuous unloading <sup>1</sup>	$Full Load minimum: \\ 100%- Tol_1 \\ Full Load maximum: \\ 100%+ Tol_1$					
Capacity	Cooling or heating Capacity for units with discrete capacity steps  Cooling or heating 100% - Tol <sub>1</sub> Full load maximum: no limit (Full Load shall be at the maximum stage of Capacity)		$Tol_1 = 0.105 - (0.07 \cdot \%Load) + \left(\frac{0.0833}{\Delta T_{FL} \cdot \%Load}\right)  34$ See Figure 3 for graphical representation of the Tol <sub>1</sub> tolerance.				
Efficiency	СОР	Minimum of: (rated COP) / (100%+ Tol <sub>1</sub> )					
	IPLV.SI Minimum of: NPLV.SI (rated COP <sub>R</sub> ) / (100%+ COP <sub>R</sub> Tol <sub>2</sub> )		$Tol_2 = 0.065 + \left(\frac{0.194}{\Delta T_{FL}}\right)$ 35 See Figure 4 for graphical representation of the Tol <sub>2</sub> tolerance.				
Water Pressure Drop ∆p <sub>corrected</sub> ≤		$\Delta p_{corrected} \leq Tol_3$	$Tol_{3} = \max \begin{cases} 1.15 \cdot \Delta p_{rated} \\ \Delta p_{rated} + 6 \text{ kPa} \end{cases} 36$				

#### Notes

- 1. The target set point Condenser entering temperatures (Table 6) are determined at the target part load test point.
- 2. For air-cooled units and evaporatively-cooled units, all tolerances are computed for values after the atmospheric correction is taken into account.
- 3. %Load,  $Tol_1$  and  $Tol_2$  are in decimal form (e.g. 100% Load = 1.0).

Figure 3 is a graphical representation of the related tolerance equation for Capacity and efficiency as noted in Table 7.




Figure 3. Allowable Tolerance (Tol<sub>1</sub>) Curves for Full and Part-load Points

Figure 4 is a graphical representation of the related tolerance equation for IPLV.SI and NPLV.SI as noted in Table 7. The PLV line shown can represent either IPLV.SI or NPLV.SI depending on use.



Figure 4. IPLV.SI and NPLV.SI Tolerance (Tol<sub>2</sub>) Curve

- **5.7.2** Allowable Operating Condition Tolerances. Tests shall be conducted while maintaining the tolerance limits on operating conditions defined in Table 1. Measurement values and calculation results shall not deviate from published rating values more than the operating condition tolerance limits determined from Table 1.
- **5.8** *Head Pressure Control*. For units that have head pressure control to ensure proper flow of refrigerant through the expansion valve during low Condenser temperature conditions, the head pressure controls shall be enabled and operated in automatic control mode. The setting shall be set at the factory settings or as defined in the installation instruction.

If during part load testing the head pressure control is engaged by the control logic, then it shall be used to control the operation

of the unit. If the unit can be run and stable conditions are obtained as required by Table 1, then a standard test shall be run. If the head pressure control results in cycling of the condenser fans and unstable conditions as defined in Table 1, then the following modified test procedure defined in Section 5.8.1 shall be used.

**5.8.1** Head Pressure Control Time Average Test Procedure. A series of two tests shall be run. Prior to the first test, the Condenser operating condition, as defined by Table 6, shall be approached from at least a 5.0 °C higher temperature until the entering air temperature is within the Operating Condition Tolerance Limits as defined by Table 1. When on conditions, the test shall be started and measurements shall be taken per the requirements in ANSI/ASHRAE Standard 30. During the test, the requirements of Table 1 for Condenser for cooling with fan cycling shall be satisfied. Note that ANSI/ASHRAE Standard 30 allows for longer test periods with longer time averages for measurements to permit meeting the test validity requirements in Table 1.

Following the first test completion, the Condenser condition shall be reduced at least 2.5 °C below the desired temperature. It shall then be gradually increased until the entering air temperature is within the Operating Condition Tolerance Limits as defined by Table 1. When on conditions, the second test shall be started and measurements shall be taken per the requirements in ANSI/ASHRAE Standard 30. During the test, the requirements of Table 1 for Condenser for cooling with fan cycling shall be satisfied. Note that ANSI/ASHRAE Standard 30 allows for longer test periods with longer time averages for measurements to permit meeting the test validity requirements in Table 1.

The test results for both tests shall then be averaged to determine the tested performance for the rating point.

**5.9** Refrigerant Tubing for Remote Condenser and Evaporator. Refrigerant tubing lengths shall be expressed in equivalent lengths. Equivalent lengths shall be calculated per Chapter 1 of the ASHRAE Refrigeration Handbook. Standard Ratings shall be established with at least 7.6 m length on each line of interconnecting refrigerant tubing. Refrigerant tubing shall be sized and insulated per the manufacturer's instructions. Application Ratings can be established at other tubing lengths.

#### Section 6. Minimum Data Requirements for Published Ratings

**6.1** Minimum Data Requirements for Published Ratings. As a minimum, Published Ratings shall include either Standard Ratings or Application Ratings, per either Section 5.2 or 5.3. Rated Capacity  $Q_{100\%}$ , for chillers rated at Standard Rating Conditions is the net Capacity at full-load AHRI Standard Rating Conditions per Table 1. Rated Capacity  $Q_{100\%}$ , for chillers rated at Application Rating Conditions is the net Capacity at full-load AHRI Application Rating Conditions within the range permitted in Table 5.

All claims to ratings within the scope of this standard shall include the statement "Rated in accordance with AHRI Standard 551/591 (SI)". All claims to ratings outside the scope of the standard shall include the statement "Outside the scope of AHRI Standard 551/591 (SI)". Wherever Application Ratings are published or printed, they shall include a statement of the conditions at which the ratings apply.

**6.2** *Published Ratings*. Published Ratings shall state all of the operating conditions used to establish the ratings and be rounded to the number of Significant Figures shown in Table 8, using the definitions, rounding rules and formats in Section 4.3.

			Table	8. Pul	blishe	d Val	ues <sup>1</sup>						
Published Values	Units	Significant Figures <sup>2</sup>	Water-cooled Chiller (Cooling)	Water-cooled Heat Recovery Chiller	Evaporatively Cooled Chiller	Air-cooled Chiller	Condenserless Chiller	Air-cooled HP (Cooling)	Air-cooled HP (Heating)	Air cooled Heat Recovery Chiller	Water to Water HP (Cooling)	Water to Water HP (Heating)	Simultaneous Heating and Cooling
General		T	1 1	T	T	ı		T	1	I			
Voltage <sup>3</sup>	V, kV	3	•	•	•		•	•	•		•	•	•
Frequency	Hz	2	•	•	•		•	•	•		•	•	•
Refrigerant Designation in accordance with ANSI/ASHRAE Standard 34	-	-	-	•	•	•	•	•	•	•	•	•	•
Model Number	-	-										•	
Operating Mode (Cooling, Heating, Simultaneous Heating and Cooling, or Heat Recovery)	-	-	•	•	-	•	•	•	•	•	•	•	•
Net Capacity	<u>-                                    </u>				•				•	•	•		
Full Load Refrigerating Capacity <sup>4</sup>		4	•	•	•	•	-			•	•	•	•
Heat Rejection or Heating Capacity	kW, MW	4		•			•		•	•		•	
Heat Recovery Capacity		4											
Efficiency	-			<del>-</del>	<del>-</del>	<u> </u>		<u>-</u>					
Cooling COP <sub>R</sub>		4										•	
Heating COP <sub>R</sub>		4										•	
Simultaneous Heating and Cooling COP <sub>SHC</sub>	W/W	4											•
Heat Recovery COP <sub>HR</sub>		4											
IPLV.SI or NPLV.SI <sup>5</sup>		4											
Power													
Total Input Power <sup>6,7,8,9,10</sup>		4											
Condenser Spray Pump Power [optional]	kW, W, MW	Note 11			•								
Fan Power [optional]		Note 11											
Cooling Mode Evaporator													
Entering Water <sup>12</sup>	°C	Note 13			•								
Leaving Water <sup>12</sup>	°C	Note 13			•								
Entering Flow L/s, m <sup>3</sup> /h		4	•	•	-	•		•	•	•	•	•	
Water Pressure Drop	kPa	3	•	•	•	•	•	•	•	•	•	•	•
Fouling Factor	m <sup>2</sup> ⋅K/kW, m <sup>2</sup> ⋅°C/kW	3	•	•	•	•	-	-	•	•	•	•	-

	Т	able 8. I	Publis	hed Va	alues	(contir	nued)						
Published Values	Units	Significant Figures <sup>2</sup>	Water-cooled Chiller (Cooling)	ŧ.			s	Air-cooled HP (Cooling)	Air-cooled HP (Heating)	Air cooled Heat Recovery Chiller	Water to Water HP (Cooling)	Water to Water HP (Heating)	Simultaneous Heating and Cooling
Cooling Mode Heat Rejection Exc	changer												
Tower Condenser													
Entering Water <sup>12</sup>	Entering Water <sup>12</sup> °C Note 13 • •												
Leaving Water <sup>12</sup>	°C	Note 13											
Entering Flow	L/s, m <sup>3</sup> /h	4	•										
Water Pressure Drop	kPa	3											
Fouling Factor	m²⋅K/kW, m²⋅°C/kW	3	•	•									
Heat Recovery Condenser													
Entering Water <sup>12</sup>	°C	Note 13											
Leaving Water <sup>12</sup>	°C	Note 13											
Entering Flow	L/s, m <sup>3</sup> /h	4											
Water Pressure Drop	kPa	3											
Fouling Factor	m <sup>2</sup> ·K/kW, m <sup>2</sup> ·°C/kW	3		•						•			
Dry-bulb air	°C	Note 13											
Heat Rejection Condenser		l.					Į.	Į.	Į.				
Entering Water <sup>12</sup>	°C	Note 13											•
Leaving Water <sup>12</sup>	°C	Note 13									•	•	
Entering Flow	L/s, m <sup>3</sup> /h	4									•	•	
Water Pressure Drop	kPa	3									•	•	
Fouling Factor	m²⋅K/kW, m²⋅°C/kW	3									•		•
Evaporatively Cooled	•		!									•	
Dry-bulb	°C	Note 13											
Wet-bulb	°C	Note 13											
Fouling Factor	m²·K/kW, m²·°C/kW	3			•								
Altitude or Atmospheric Pressure <sup>15</sup>	m, kPa	Note 15			-								
Air Cooled													
Dry-bulb	°C	Note 13											
Wet-bulb	°C	Note 13											
Altitude or Atmospheric Pressure <sup>15</sup>	m, kPa	Note 13				•		•					
Without Condenser													
Compressor Saturated Discharge Temperature	°C	Note 13					•						
Liquid Temperature or Subcooling	°C	Note 13					-						
Integral Pumps	I	ı	1										
Pump Power	W, kW, MW	4											

Water Pressure Drop	kPa	3	•	•	•	•	•	-	•			•	•
Table 8. Published Values (continued)													
Published Values	Units	Significant Figures <sup>2</sup>	Water-cooled Chiller (Cooling)	Water-cooled Heat Recovery Chiller	Evaporatively Cooled Chiller	Air-cooled Chiller	Condenserless Chiller	Air-cooled HP (Cooling)	Air-cooled HP (Heating)	Air Cooled Heat Recovery Chiller	Water to Water HP (Cooling)	Water to Water HP (Heating)	Simultaneous Heating and Cooling
Remote Condenser or Evaporator													
Equivalent length of each line of interconnecting refrigerant tubing	m	2	•	•	•	•	•	•	•	•	•	•	•

#### Notes:

- 1. Table key:  $\blacksquare$  = required,  $\square$  = optional
- 2. Published Ratings and final reported test values shall be rounded to the number of Significant Figures shown in this table.
- 3. A single published rating is can be used for dual nameplate voltage equipment. Refer to AHRI Standard 110.
- 4. For electric-drive packages provided with starters, transformers, gearboxes, or variable speed drives, whether self-contained or remote-mounted (free-standing), the input power shall include the power losses due to those components. Full Load Refrigerating Capacity is the Full Load Net Refrigerating Capacity at the Rating Conditions and shall equal the 'A' point IPLV.SI or NPLV.SI capacity.
- 5. It is optional to publish NPLV when any cooling mode part-load condition results in an Evaporator LWT greater than the Ccondenser EWT, EDB, EWB, or SDT at the same rating condition. Refer to Section 5.4 for IPLV.SI or NPLV.SI rating requirements.
- 6. Exclude input power to integrated water pumps, when present.
- 7. When a motor or other non-electric drive is not included with the Water-chilling or Water-heating Package, assume a speed control method consistent with the chiller manufacturer installation requirements, and use the compressor shaft input power when determining the Total Input Power.
- 8. For non-electric drive packages, such as turbine or engine drive, the input power shall include the losses due to the prime mover and other driveline components such as a gearbox.
- 9. When the Water-chilling or Water-heating Package does not include some components, which are provided by another party independently from the chiller manufacturer, the input power and any losses associated with those components shall be determined as follows:
  - a. For electric-drive packages rated for fixed-speed operation but not including a starter, use the compressor motor terminal input power when determining the Total Input Power.
  - b. For electric-drive packages rated for variable-speed operation but not including a variable speed drive, assume a variable speed control method and variable speed drive type consistent with the chiller manufacturer installation requirements, and use the compressor motor terminal input power when determining the Total Input Power.
- 10. Components that utilize Auxiliary Power shall be listed.
- 11. When published, Auxiliary Power values shall be displayed with the same precision as the Total Input Power (same number of decimal places if using the same unit of measure).
- 12. An alternate to providing entering and leaving water temperatures is to provide one of these along with the temperature difference across the heat exchanger.
- 13. Commonly used units of measure for temperature are not on an absolute scale; however, proper use of Significant Figures requires an absolute scale. For simplicity, this standard specifies the number of decimal places as follows:
  - a. Water temperatures round to two decimal places.
  - b. Refrigerant Temperatures (actual or saturated) round to one decimal place.
  - c. Air temperatures round to one decimal place.
- 14 This note is not used.
- 15. Altitude based on standard atmosphere; refer to Section 5.3.1 and Section 7 for conversion to atmospheric pressure. To provide adequate Significant Figures for conversion to atmospheric pressure, display altitude as an integer value. If rounding altitude, round to an increment not exceeding 5 m. Atmospheric pressure shall be published with four significant digits.

#### Section 7. Units of Measure, Conversions and Water Properties

- **7.1** Units of measure. The British thermal unit (Btu) used in this standard is the International Table Btu defined as  $1 Btu_{IT} = 1055.055 852 62 J$  (corresponding to 1 calorie = 4.1868 J). Throughout this standard, all instances of Btu without the 'IT' subscript shall use this definition.
- **7.2** Conversions. For units that require conversion the following factors in Table 9 shall be utilized:

Table 9. Conversion	Table 9. Conversion Factors											
To Convert From	То	Multiply By										
kilowatt (kW)	Btu/h	3,412.14										
cubic meter (m <sup>3</sup> )	liter (L)	1000										
minute (min)	second (s)	60										
cubic meter per second (m³/s)	liter per minute (L/min)	1.66667 E+7										

**7.3** Water Side Properties Calculation Methods. One of the following calculation methods shall be utilized. In both cases, the value of the water temperature or pressure to be used as input is dependent on the context of the calculation using the density and specific heat terms. This standard shall be used where discrepancies exist between these methods and those prescribed by ANSI/ASHRAE Standard 30.

Method 1. Use NIST REFPROP software (version 10.0 or later) to calculate physical properties density and specific heat, as a function of both pressure and temperature.

Method 2. Use polynomial Equations 37 and 38 respectively to calculate density and specific heat of water as a function of temperature only.

$$\rho = (\rho_4 \cdot T^4) + (\rho_3 \cdot T^3) + (\rho_2 \cdot T^2) + (\rho_1 \cdot T) + \rho_0$$
37

Where:

$$\begin{split} & \rho_0 = 1000.2 \text{ kg/m}^3 \\ & \rho_1 = 4.6734 \cdot 10^{-2} \text{ kg/m}^3 \\ & \rho_2 = -7.3948 \cdot 10^{-3} \text{ kg/m}^3 \\ & \rho_3 = 4.0229 \cdot 10^{-5} \text{ kg/m}^3 \\ & \rho_4 = -1.2556 \cdot 10^{-7} \text{kg/m}^3 \\ & T = \text{Water temperature (0 to 100) °C} \end{split}$$

$$c_{p} = (c_{p5} \cdot T^{5}) + (c_{p4} \cdot T^{4}) + (c_{p3} \cdot T^{3}) + (c_{p2} \cdot T^{2}) + (c_{p1} \cdot T) + c_{p0}$$
38

Where:

$$\begin{split} &C_{p0} = 4.2160 \text{ kJ/kg} \cdot \text{K} \\ &C_{p1} = -3.1103 \cdot 10^{-3} \text{ kJ/kg} \cdot \text{K} \\ &C_{p2} = 9.4433 \cdot 10^{-5} \text{ kJ/kg} \cdot \text{K} \\ &C_{p3} = -1.3901 \cdot 10^{-6} \text{ kJ/kg} \cdot \text{K} \\ &C_{p4} = 1.0770 \cdot 10^{-8} \text{ kJ/kg} \cdot \text{K} \\ &C_{p5} = -3.2220 \cdot 10^{-11} \text{ kJ/kg} \cdot \text{KT} = \text{Water temperature (0 to 100) °C} \end{split}$$

Note: Density and specific heat polynomial equations are curve fit from data generated by NIST REFPROP v10.0 (see Normative Appendix A) at 689.5 kPa and using a temperature range of 0 °C to 100 °C. The 689.5 kPa value used for the water property curve fits was established as a representative value to allow for the calculation of water side properties as a function of temperature only. This eliminates the complexity of measuring and calculating water side properties as a function of both

temperature and pressure. This assumption, in conjunction with a formulation for Capacity that does not make explicit use of enthalpy values, provides a mechanism for computing heat exchanger Capacity for fluids other than pure water where specific heat data are generally known but enthalpy curves are not available.

7.4 Converting Altitude to Atmospheric Pressure. Use Equation 39 to convert between altitude and atmospheric pressure. The relationship is based on the International Standard Atmosphere (ISA) and represents a mean value of typical weather variations. The ISA is defined by ICAO Document 7488/3. The slight difference between geometric altitude ( $Z_H$ ) and geopotential altitude ( $Z_H$ ) is ignored for the purposes of this standard ( $Z_H \cong H$ ).

$$p_{atm} = p_0 \cdot \left[ \frac{T_0}{T_0 + \beta \cdot (Z_H - Z_{H0})} \right]^{\left(\frac{g_0}{\beta} \cdot \frac{M_0}{R^*}\right)}$$

$$39$$

Where:

 $\beta = -0.0065 \, K/m$ 

 $Z_{H0}=0 m$ 

 $g_0 = 9.80665 \, m/s^2$ 

 $M_0 = 28.96442 \ kg/kmol$ 

 $R *= 8314.32 J/(K \cdot kmol)$ 

 $p_0 = 101.325 \, kPa$ 

 $T_0 = 288.15 K$ 

## **Section 8. Symbols and Subscripts**

**8.1** *Symbols and Subscripts.* The symbols and subscripts used are listed in Table 10:

	Table 10. Symbols and Subscripts		
Symbol	Description	Unit Name	Unit Symbol
A	Efficiency at 100% load. COP, EER, or kW/ton <sub>R</sub> depending on use.		varies
$A_{\mathrm{w}}$	Heat transfer surface area used in Fouling Factor adjustment calculations (water-side), as used in Appendix C.	square meter	m <sup>2</sup>
$A_{Q}$	Correction factor, Capacity, polynomial equation coefficient	dimensionless	-
$A_{\eta}$	Correction factor, efficiency, polynomial equation coefficient	dimensionless	-
В	Efficiency at 75% load. COP, EER, or kW/Ton depending on use.		varies
B <sub>Q</sub>	Correction factor, Capacity, polynomial equation coefficient	dimensionless	-
$B_{\eta}$	Correction factor, efficiency, polynomial equation coefficient	dimensionless	-
C	Efficiency at 50% load. COP, EER, or kW/Ton depending on use.		varies
$C_D$	Degradation factor	dimensionless	-
CF <sub>O</sub>	Atmospheric correction factor for Capacity	dimensionless	-
CF <sub>n</sub>	Atmospheric correction factor for efficiency	dimensionless	-
COPH	Efficiency, coefficient of performance, heating	dimensionless	-
COP <sub>HR</sub>	Efficiency, coefficient of performance, heat recovery	dimensionless	-
$COP_R$	Efficiency, coefficient of performance, cooling	dimensionless	-
COP <sub>R,CD</sub>	Efficiency, coefficient of performance, cooling, corrected with degradation factor	dimensionless	-
COP <sub>SHC</sub>	Efficiency, coefficient of performance, simultaneous cooling & heating	dimensionless	-
Cp	Specific heat at constant pressure	joule per kilogram kelvin	J/(kg·K)
$C_Q$	Correction factor, Capacity, polynomial equation coefficient	dimensionless	-
$C_{\eta}$	Correction factor, efficiency, polynomial equation coefficient	dimensionless	-
CWH	Cooling water hours	degree Fahrenheit hour	°F·h
D	Efficiency at 25% load. COP, EER, or kW/Ton depending on use.		varies
DBH	Dry bulb hours	degree Fahrenheit hour	°F·h
Do	Correction factor, Capacity, equation term	dimensionless	-
$D_{\eta}$	Correction factor, efficiency, equation term	dimensionless	-
EDB	Entering Dry Bulb Temperature	degree Celsius	°C
EER	Efficiency, Energy Efficiency Ratio	Btu per watt hour	Btu/(W·h)
EER <sub>CD</sub>	Efficiency, Energy Efficiency Ratio, corrected with degradation factor	Btu per watt hour	Btu/(W·h)
EER <sub>Test</sub>	Efficiency, Energy Efficiency Ratio, test value	Btu per watt hour	Btu/(W·h)
EWB	Entering wet bulb temperature	degree Celsius	°C
EWT	Entering Water Temperature	degree Celsius	°C
ECWT	Entering Condenser water temperature	degree Celsius	°C
$g, g_0$	Standard gravitational term	meter per second squared	m/s <sup>2</sup>

	Table 10. Symbols and Subscripts		
Symbol	Description	Unit Name	Unit Symbol
Н	Geopotential altitude (see section 7.3)	meter	m
IPLV	Efficiency, Integrated Part Load Value. kW/Ton, COP, or EER		varies
IPLV.IP	Efficiency, Integrated Part Load Value when calculated and reported in accordance with AHRI Standard 550/590 (I-P) in IP units. COP, EER, or kW/Ton	Btu per watt hour, kilowatt per kilowatt, or kilowatt per ton of refrigeration	Btu/(W·h), kW/kW or kW/ton <sub>R</sub>
IPLV.SI	Efficiency, Integrated Part Load Value when calculated and reported in accordance with AHRI Standard 551/591 (SI) in SI units.	dimensionless	-
kW/ton <sub>R</sub>	Efficiency, power input per Capacity	kilowatt per ton of refrigeration	kW/ton <sub>R</sub>
LF	Load factor	dimensionless	-
%Load	The ratio of the part-load rated net Capacity, stated in decimal format (e.g. $100\% = 1.0$ )	dimensionless	-
%Load <sub>1</sub> , %Load <sub>2</sub>	%Load used to interpolate, stated in decimal format (e.g.100% = 1.0)	dimensionless	-
LWT	Leaving Water Temperature	degree Celsius	°C
m <sub>w</sub>	Mass flow rate, water	kilogram per second	kg/s
$M_0$	Constant used in Equation 39	kilogram per kilomole	kg/kmol
ñ	Mean rotational speed (compressor), calculated from data samples	revolution per minute	RPM
NPLV	Efficiency, Non-standard Part Load Value. kW/Ton, COP, or EER depending on use.		varies
NPLV. IP	Efficiency, Non-standard Part Load Value when calculated and reported in accordance with AHRI Standard 550/590 in IP units. kW/Ton, COP, or EER depending on use.	Btu per watt hour, kilowatt per kilowatt, or kilowatt per ton of refrigeration	Btu/(W·h), kW/kW or kW/ton <sub>R</sub>
NPLV. SI	Efficiency, Non-standard Part Load Value when calculated and reported in accordance with AHRI Standard 551/591 in SI units.	dimensionless	-
OA	Outside air	degree Fahrenheit	°F
p	Pressure	kilopascal	kPa
p	Mean pressure, calculated from data samples	kilopascal	kPa
$p_{atm}$	Atmospheric pressure	kilopascal	kPa
$p_0$	Standard atmospheric pressure	kilopascal	kPa

	Table 10. Symbols and Subscripts		
Symbol	Description	Unit Name	Unit Symbol
Q	Capacity (heat flow rate); net Capacity	kilowatt	kW
$Q_{cd}$	Net Capacity, Condenser (heating)	kilowatt	kW
$Q_{ev}$	Net Capacity, Evaporator (cooling)	kilowatt	kW
$Q_{\mathrm{hrc}}$	Net Capacity, Condenser (heat recovery)	kilowatt	kW
$Q_{i}$	Heat transfer rate for each heat exchanger	kilowatt	kW
$Q_{test}$	Test results for net Capacity, uncorrected for atmospheric pressure	kilowatt	kW
$Q_{corrected, standard} \\$	Test results for net Capacity, corrected to standard atmospheric pressure	kilowatt	kW
$Q_{corrected, application} \\$	Test results for net Capacity, corrected to application rating atmospheric pressure	kilowatt	kW
$\mathrm{Q}_{100\%}$	Test results for unit net Capacity at 100% load point	kilowatt	kW
$Q_{min\%Load}$	The measured or calculated unit net Capacity at the minimum step of Capacity including atmospheric pressure corrections as applicable	kilowatt	kW
$Q_{target}$	Target test part-load net Capacity	kilowatt	kW
$\overline{\mathbb{Q}}$	Mean net Capacity, calculated from data samples	kilowatt	kW
R*	Constant used in Equation 39	Joules per Kelvin kilomole	J/(K·kmol)
$R_{ m foul}$	Fouling Factor Allowance	meter squared degree Celsius per watt or meter squared Kelvin per watt	m²·°C/W, m²·K/W
SDT	Saturated Discharge Temperature	degree Celsius	°C
S <sub>n</sub>	Standard deviation of governor speed		varies
Sp	Standard deviation of turbine pressure		varies
$s_T$	Standard deviation of temperature measurement samples		varies
$s_V$	Standard deviation of voltage		varies
$s_{\omega}$	Standard deviation of frequency		varies
S <sub>vw</sub>	Standard deviation of volumetric water flow measurement samples		varies

C1 - 1	Table 10. Symbols and Subscripts	TT14 NT	II-i G
Symbol	Description	Unit Name	Unit Symbol
T	Temperature	degree Celsius	°C
T	Mean temperature, calculated from data samples	degree Celsius	°C
$T_{in}$	Entering water temperature	degree Celsius	°C
$T_{in,w}$	Temperature, water entering	degree Celsius	°C
$Tol_1$	Tolerance 1, performance tolerance limit	dimensionless	-
Tol <sub>2</sub>	Tolerance 2, IPLV and NPLV performance tolerance limit	dimensionless	-
Tol <sub>3</sub>	Tolerance 3, Tolerance on water side pressure drop	kilopascal	kPa
$T_{out}$	Leaving water temperature	degree Celsius	°C
T <sub>out,w</sub>	Temperature, water leaving	degree Celsius	°C
T <sub>sat,r</sub>	Temperature, saturated refrigerant	degree Celsius	°C
$T_{target}$	Target test temperature	degree Celsius	°C
$T_0$	Conversion from degree Celsius to Kelvin	Kelvin	K
T <sub>100%</sub>	Selected 100% Load temperature	degree Celsius	°C
$V_{\rm w}$	Volumetric flow rate	cubic meter per second	m³/s
$\overline{V}_{w}$	Mean volumetric flow rate calculated from data samples	cubic meter per second	m³/s
$\overline{V}$	Mean Voltage calculated from data samples	volt	V
V	Voltage	volt	V
W <sub>input</sub>	Power, Total Input Power	kilowatt	kW
Z	Equation term (as used in Equation 5)	dimensionless	-
$Z_H, Z_{H0}$	Geometric altitude	meter	m
$\Delta p_{rated}$	Pressure differential at rated water temperatures (inlet to outlet)	kilopascal	kPa
$\Delta T_{adj}$	Temperature differential, additional temperature differential due to fouling	degree Celsius	°C
$\Delta T_{adj,i}$	Computed temperature adjustment for each heat exchanger	degree Celsius	°C
$\Delta T_{adj,weighted}$	Weighted temperature adjustment	degree Celsius	°C

	Table 10. Symbols and Subscripts		
Symbol	Description	Unit Name	Unit Symbol
$\Delta T_{\mathrm{FL}}$	Temperature differential, at rated full load design conditions	degree Celsius	°C
$\Delta T_{\rm ILMTD}$	Incremental log mean temperature difference	degree Celsius	°C
$\Delta T_{ m LMTD}$	Log mean temperature difference	degree Celsius	°C
$\Delta T_{range}$	Temperature differential when referenced to entering and leaving heat exchanger fluid temperatures	degree Celsius	°C
$\Delta T_{small,clean}$	Small temperature difference as tested in clean condition	degree Celsius	°C
$\Delta T_{ m small,sp}$	Small temperature difference as specified	degree Celsius	°C
β	Constants used in Equation 39	Kelvin per meter	K/m
$\eta_1,\eta_2$	Efficiency values used to interpolate (COP)	dimensionless	-
$\eta_{int}$	Interpolated efficiency (COP)	dimensionless	-
$\eta_{\text{test}}$	Test results for Efficiency (COP)), uncorrected for atmospheric pressure.	dimensionless	-
$\eta_{test,100\%}$	Efficiency (COP)) measured in Full Load test, for atmospheric pressure correction.	dimensionless	-
$\eta_{corrected,standard}$	Test results for Efficiency (COP), corrected to standard atmospheric pressure	dimensionless	-
$\eta_{corrected,application}$	Test results for Efficiency (COP), corrected to standard atmospheric pressure	dimensionless	-
ρ	Density	kilogram per meter cubed	kg/m <sup>3</sup>
$ ho_{in}$	Density of water entering the heat exchanger	kilogram per meter cubed	kg/m <sup>3</sup>
ω	Frequency (electrical)	Hertz	Hz
ū	Mean frequency (electrical), calculated from data samples	Hertz	Hz

#### Section 9. Marking and Nameplate Data

- **9.1** Marking and Nameplate Data. As a minimum, the nameplate shall display the following:
  - **9.1.1** Manufacturer's name and location
  - **9.1.2** Model number designation providing performance-essential identification
  - **9.1.3** Refrigerant designation (in accordance with ANSI/ASHRAE Standard 34)
  - **9.1.4** Voltage, phase and frequency
  - **9.1.5** Serial number
- **9.2** *Nameplate Voltage*. Where applicable, nameplate voltages for 60 Hertz systems shall include one or more of the equipment nameplate voltage ratings shown in Table 1 of AHRI Standard 110. Where applicable, nameplate voltages for 50 Hertz systems shall include one or more of the utilization voltages shown in Table 1 of IEC Standard 60038.

#### **Section 10. Conformance Conditions**

**10.1** Conformance. While conformance with this standard is voluntary, conformance shall not be claimed or implied for products or equipment within the standard's *Purpose* (Section 1) and *Scope* (Section 2) unless such product claims meet all of the requirements of the standard and all of the testing and rating requirements are measured and reported in complete compliance with the standard. Any product that has not met all the requirements of the standard cannot reference, state, or acknowledge the standard in any written, oral, or electronic communication.

#### Section 11. Operating Requirements

- **11.1** Operating Requirements. Chillers with air-cooled Condensers and published operability at an entering air dry-bulb temperature of 52.0 °C shall comply with provisions of this section.
  - **11.1.1** *High Temperature Operating Requirements.* 
    - **11.1.1.1** *High Temperature Condition.* The chiller shall be capable of an Application Rating at entering air dry-bulb temperature of 52.0 °C.
    - **11.1.1.2** Operability at High Temperature Condition. The chiller shall be capable of the following when operating at the above condition and following test requirements of Section 4.1. When all power to the equipment is momentarily interrupted for a period sufficient to cause the compressor to stop (loss of power not to exceed 5 seconds), and power is then restored, the unit shall be capable to resume continuous operation within one hour of restoration of power, and shall be capable to operate continuously without interruption for one hour thereafter. Operation and resetting of safety devices after power loss but prior to establishment of continuous operation can be used to meet this operability requirement. For information only, average cooling Capacity and input power are reported if conducting a test to demonstrate this capability.

## APPENDIX A. REFERENCES – NORMATIVE

- **A1** Listed here are all standards, handbooks and other publications essential to the formation and implementation of the standards. All references in this appendix are considered as part of the standard.
  - **A1.1** AHRI Standard 110-2016, *Air-Conditioning*, *Heating and Refrigerating Equipment Nameplate Voltages*, 2016, Air-Conditioning, Heating and Refrigeration Institute, 2311 Wilson Boulevard, Suite 400, Arlington, VA 22201, U.S.A.
  - **A1.2** AHRI Standard 550/590 (I-P)-2023, *Performance Rating of Water-Chilling and Heat Pump Water-Heating Packages Using the Vapor Compression Cycle*, 2018, Air-Conditioning, Heating and Refrigeration Institute, 2311 Wilson Boulevard, Suite 400, Arlington, VA 22201, U.S.A.
  - **A1.3** ANSI/AHRI/ASHRAE/ISO Standard 13256-2:1998 (RA 2012), *Water-to-Water and Brine-to-Water Heat Pumps Testing and Rating for Performance*, 1998, ASHRAE, 25 West 43<sup>rd</sup> Street, 4<sup>th</sup> Fl., New York, NY, 10036, U.S.A./ 180 Technology Parkway NW, Peachtree Corners, GA 30092, U.S.A.
  - **A1.4** ANSI/ASHRAE Standard 30-2019, *Method of Testing Liquid Chillers*, 2019, ASHRAE, 25 West 43<sup>rd</sup> Street, 4<sup>th</sup> Fl., New York, NY, 10036, U.S.A./ 180 Technology Parkway NW, Peachtree Corners, GA 30092, U.S.A.
  - **A1.5** ANSI/ASHRAE Standard 34-2019 with Addenda, *Number Designation and Safety Classification of Refrigerants*, 2016, ASHRAE, 25 West 43<sup>rd</sup> Street, 4<sup>th</sup> Fl., New York, NY, 10036, U.S.A./ 180 Technology Parkway NW, Peachtree Corners, GA 30092, U.S.A.
  - **A1.6** ANSI/ASHRAE Standard 41.1-2013, *Measurements Guide Section on Temperature Measurements*, 2013, ASHRAE, 25 West 43<sup>rd</sup> Street, 4<sup>th</sup> Fl., New York, NY, 10036, U.S.A./ 180 Technology Parkway NW, Peachtree Corners, GA 30092, U.S.A.
  - **A1.7** ASHRAE *Fundamentals Handbook*, 2021, ASHRAE, 180 Technology Parkway NW, Peachtree Corners, GA 30092, U.S.A.
  - **A1.8** ASHRAE *Refrigeration Handbook*, 2018, ASHRAE, 180 Technology Parkway NW, Peachtree Corners, GA 30092, U.S.A.
  - **A1.9** ASHRAE Terminology. ASHRAE. Accessed June 27, 2022. https://www.ashrae.org/technicalresources/free-resources/ashrae-terminology.
  - **A1.10** ICAO Document 7488/3-1993, *Manual of the ICAO Standard Atmosphere, Third Edition*. 1993, International Civil Aviation Organization, 999 Robert-Bourassa Boulevard, Montréal, Quebec H3C 5H7, Canada. <a href="http://aviadocs.net/icaodocs/Docs/ICAO">http://aviadocs.net/icaodocs/Docs/ICAO</a> Doc7488.pdf.
  - **A1.11** IEC Standard 60038-2009, *IEC Standard Voltages*, 2009, International Electrotechnical Commission, rue de Varembe, P.O. Box 131, 1211 Geneva 20, Switzerland.
  - **A1.12** NIST. Lemmon, E.W., Huber, M.L., McLinden, M.O. NIST Standard Reference Database 23: Reference Fluid Thermodynamic and Transport Properties-REFPROP, Version 10.0, National Institute of Standards and Technology, Standard Reference Data Program, Gaithersburg.

## **APPENDIX B. REFERENCES – INFORMATIVE**

- **B1** Listed here are standards, handbooks and other publications which may provide useful information and background but are not considered essential. References in this appendix are not considered part of the standard.
  - **B1.1** ANSI/ASHRAE Standard 140-2020, *Method of Test for Evaluating Building Performance Simulation Software*, 2020, ASHRAE, 25 West 43<sup>rd</sup> Street, 4<sup>th</sup> Fl., New York, NY, 10036, U.S.A./ 180 Technology Parkway NW, Peachtree Corners, GA 30092, U.S.A.
  - **B1.2** ANSI/ASHRAE Standard 90.1 (I-P)-1989, Energy Standard for Buildings Except for Low-Rise Residential Buildings, 1989, ASHRAE, 180 Technology Parkway NW, Peachtree Corners, GA 30092, U.S.A.
  - **B1.3** *Commercial Buildings Characteristics 1992*; April 1994, DOE/EIA-0246(92).

# APPENDIX C. ATMOSPHERIC PRESSURE ADJUSTMENT – NORMATIVE

C1 Purpose. This appendix prescribes a method of adjusting measured test data according to the local atmospheric pressure.

**C2** *Background.* In order to ensure that performance can be uniformly compared from one unit to another and from one manufacturer to another, performance testing for air-cooled and evaporatively-cooled chillers shall be corrected for air density variations. To accomplish this, use the following two (2) correction factors (CF<sub>Q</sub>, CFη) to correct test data at test load points back to standard atmospheric pressure at sea level, for Standard Rating Conditions, or to correct to another atmospheric pressure corresponding to a site altitude for Application Rating Conditions. These correction factors use an empirical method of correction based on industry average values across a wide variety of chillers. The correction factors are based on pressure rather than altitude, in order to include the effects of weather variations. Test data shall be corrected from actual tested atmospheric pressure to rated atmospheric pressure for comparison to Published Ratings. The correction multiplier for efficiency and Capacity at the 0% load point shall be 1.0. Intermediate correction multipliers at part-load points will be calculated at each part-load point where the % load value is based on the measured Capacity at that load point divided by the 100% load point measured Capacity.

Note: These factors are not intended to serve as selection code correction factors. For selection codes component models that properly adjust for variation in atmospheric pressure as related to fan, heat exchanger and compressor power and Capacity should be used.

The correction factors ( $CF_Q$ ,  $CF_\eta$ ) shall be limited to a value corresponding to an atmospheric pressure of 79.70 kPa (approximately 1981 meters altitude). Correction factors for measured atmospheric pressure readings below the minimum will be equal to the value determined at 70.7 kPa.

C3 Procedure for Correcting Test Data to Standard Rating Condition Atmospheric Pressure. Air-cooled and evaporatively-cooled chillers are tested at the local conditions. The data is then corrected to sea level and standard pressure, using Equations C1, C2, C3, C4, C5, and C6, by multiplying the measured data by the appropriate correction factor (CF). Both factors are in the form of a second order polynomial equations:

$$D_Q = A_Q \cdot p^2 + B_Q \cdot p + C_Q$$
 C1

$$D_h = A_{\eta} \cdot p^2 + B_{\eta} \cdot p + C_{\eta}$$
 C2

$$(CF_Q)_{P=P_{test}} = 1 + \left(\frac{Q_{\%Load}}{Q_{100\%}}\right) \cdot (D_Q - 1) \cdot exp\{-0.35 \cdot \left[ (3.41214 \cdot D_{\eta} \cdot \eta_{test,100\%}) - 9.6 \right] \}$$
 C3

$$(CF_{\eta})_{P=P_{test}} = 1 + \left(\frac{Q_{\%Load}}{Q_{100\%}}\right) \cdot (D_{\eta} - 1) \cdot exp\{-0.35 \cdot \left[ (3.41214 \cdot D_{\eta} \cdot \eta_{test,100\%}) - 9.6 \right] \}$$
 C4

$$Q_{corrected,standard} = Q_{test} (CF_Q)_{P=P_{test}}$$
 C5

$$\eta_{corrected,standard} = \eta_{test} (CF_{\eta})_{P=P_{test}}$$
C6

Where  $Q_{100\%}$  and  $\eta_{100\%}$  are test results at full load rating point for Standard Rating Conditions, or full load ratings for Application Rating Conditions.

	Table C1. Correction Factor (CF) Coefficients												
		Capacity D <sub>Q</sub> Efficiency D <sub>h</sub>											
Units of Measure for P	$A_Q$	$B_Q$	$C_Q$	$A_{\eta}$	$B_{\eta}$	$C_{\eta}$							
SI (kPa) 2.3713E-05 -5.9860E-03 1.36304E+00 5.1135E-05 -1.3064E-02 1.79872E+0													
Note: E indicates scientific notation, example: 1E-02 = 0.01													

C4 Procedure for Correcting Test Data to Application Rating Condition Atmospheric Pressure. First use the method in Section 7 to correct from tested atmospheric pressure to standard sea level atmospheric pressure. Then reverse the method to correct to the application rated atmospheric pressure  $P_{\text{rated}}$  (Equations C7 and C8).

$$Q_{corrected,application} = \frac{Q_{corrected,standard}}{(c_{P_Q})_{P=P_{rated}}}$$
 C7

$$\eta_{corrected,application} = \frac{\eta_{corrected,standard}}{(CF_{\eta})_{P=P_{rated}}}$$
 C8

# APPENDIX D. DERIVATION OF INTEGRATED PART-LOAD VALUE (IPLV.IP) – INFORMATIVE

**D1** *Purpose.* This appendix is an informative appendix that has been included in the standard to document the derivation of the Integrated Part-load Value (IPLV.IP) weighting factors and temperatures.

Note: This informative appendix has been included in this standard to document the derivation of the Integrated Partload Value (IPLV.IP) weighting factors and temperatures. This study was conducted in IP units and then converted to SI units in the final implementation in the standard. Therefore, the following section is only provided in IP units.

**D2** Background. Prior to the publication of ANSI/ASHRAE Standard 90.1-1989 which included an AHRI proposal for IPLV.IP, the Standard Rating Condition, design efficiency (full-load/design ambient), was the only widely accepted metric used to compare relative chiller efficiencies. A single chiller's design rating condition represents the performance at the simultaneous occurrence of both full-load and design ambient conditions which typically are the ASHRAE 1% weather conditions. The design efficiency contains no information representative of the chiller's operating efficiency at any off-design condition (part-load, reduced ambient).

The IPLV.IP metric was developed to create a numerical rating of a single chiller as simulated by 4 distinct operating conditions, established by taking into account blended climate data to incorporate various load and ambient operating conditions. The intent was to create a metric of part-load/reduced ambient efficiency that, in addition to the design rating, can provide a useful means for regulatory bodies to specify minimum chiller efficiency levels and for engineering firms to compare chillers of like technology. The IPLV.IP value was not intended to be used to predict the annualized energy consumption of a chiller in any specific application or operating conditions.

There are many issues to consider when estimating the efficiency of chillers in actual use. Neither IPLV.IP nor design rating metrics on their own can predict a building's energy use. Additionally, chiller efficiency is only a single component of many which contribute to the total energy consumption of a chiller plant. It is for this reason that the use of building energy analysis programs, compliant with ANSI/ASHRAE Standard 140, that are capable of modeling not only the building construction and weather data but also reflect how the building and chiller plant operate should be used. In this way the building designer and operator can better understand the contributions that the chiller and other chiller plant components make to the total chiller plant energy use. Modeling software can also be a useful tool for evaluating different operating sequences for the purpose of obtaining the lowest possible energy usage of the entire chiller plant. To use these tools, a complete operating model of the chiller, over the intended load and operating conditions, should be used.

In summary, it is best to use a comprehensive analysis that reflects the actual weather data, building load characteristics, operational hours, economizer capabilities and energy drawn by auxiliaries such as pumps and cooling towers, when calculating the chiller and system efficiency. The IPLV.IP (NPLV.IP) rating is used to compare the performance of similar technologies, enabling a side-by-side relative comparison, and to provide a second certifiable rating point that can be referenced by energy codes. A single metric, such as design efficiency or IPLV.IP should not be used to quantify energy savings.

**D3** *Equation and Definition of Terms.* 

**D3.1** The energy efficiency of a chiller is commonly expressed in one of the three following ratios: Coefficient of Performance ( $COP_R$ ), Energy Efficiency Ratio (EER) for cooling only and Total Input Power per Capacity ( $kW/ton_R$ ).

These three alternative ratios are related as follows:

 $COP_R = 0.293071 \text{ EER},$   $EER = 3.41214 \text{ COP}_R$   $kW/ton_R = 12/EER,$   $EER = 12/(kW/ton_R)$   $COP_R = 3.51685/(kW/ton_R)$ 

Equation D1 is used when an efficiency is expressed as EER [Btu/(W·h)] or COP<sub>R</sub> [W/W]:

IPLV.IP = 0.01A + 0.42B + 0.45C + 0.12D

D1

A = EER or COP<sub>R</sub> at 100% Capacity B = EER or COP<sub>R</sub> at 75% Capacity C = EER or COP<sub>R</sub> at 50% Capacity D = EER or COP<sub>R</sub> at 25% Capacity

Equation D2 is used when the efficiency is expressed in Total Input Power per Capacity, kW/ton<sub>R</sub>:

$$IPLV. IP = \frac{1}{\frac{0.01}{A} + \frac{0.45}{B} + \frac{0.45}{C} + \frac{0.12}{D}}$$
D2

Where, at operating conditions per Tables D-1 and D-3:

A = kW/ton<sub>R</sub> at 100% Capacity B = kW/ton<sub>R</sub> at 75% Capacity C = kW/ton<sub>R</sub> at 50% Capacity D = kW/ton<sub>R</sub> at 25% Capacity

The IPLV.IP or NPLV.IP rating requires that the unit efficiency be determined at 100%, 75%, 50% and 25% at the conditions as specified in Table 6. If the unit, due to its capacity control logic cannot be operated at 75%, 50%, or 25% Capacity efficiencies should be determined by plotting the efficiency versus the % load using straight line segments to connect the actual performance points. The 75%, 50%, or 25% load efficiencies can then be determined from the curve. Extrapolation of data is not used. An actual chiller capacity point equal to or less than the required rating point is used to plot the data. For example, if the minimum actual Capacity is 33% then the curve can be used to determine the 50% capacity point, but not the 25% capacity point.

If a unit cannot be unloaded to the 25%, 50%, or 75% capacity point, then the unit should be run at the minimum step of unloading at the Condenser entering water or air temperature based on Table D3 for the 25%, 50% or 75% capacity points as required. The efficiency is then be determined by using Equation D3:

$$EER_{CD} = \frac{EER_{Test}}{C_D}$$
 D3

Where  $C_D$  is a degradation factor to account for cycling of the compressor for capacities less than the minimum step of Capacity.  $C_D$  should be calculated using Equation D4:

$$C_D = (-0.13 \cdot LF) + 1.13$$

The load factor LF should be calculated using Equation D5:

$$LF = \frac{\text{\%Load} \cdot (\text{Full Load unit capacity})}{(\text{Part-Load unit Capacity})}$$

Where:

%Load is the standard rating point i.e. 75%, 50% and 25%.

Part-load unit Capacity is the measured or calculated unit Capacity from which standard rating points are determined using the method above.

**D3.2** Equation Constants. The constants 0.01, 0.42, 0.45 and 0.12 (refer to Equations D1 and D2) are based on the weighted average of the most common building types, and operating hours, using average USA weather data. To reduce the number of data points, the ASHRAE based bin data was reduced to a design bin and three bin groupings as illustrated in Figure D1.

**D3.3** Equation Derivation. The ASHRAE Temperature Bin Method was used to create four separate IPLV.IP or NPLV.IP formulas to represent the following building operation categories:

Group 1 - 24 hrs/day, 7 days/wk, 0°F and above

Group 2 - 24 hrs/day, 7 days/wk, 55°F and above

Group 3 - 12 hrs/day, 5 days/wk, 0°F and above

Group 4 - 12 hrs/day, 5 days/wk, 55°F and above





Figure D1. Ton<sub>R</sub>-hour Distribution Categories

The following assumptions were used:

- **D3.3.1** Modified ASHRAE Temperature Bin Method for energy calculations was used.
- **D3.3.2** Weather data was a weighted average of 29 cities across the U.S.A, specifically targeted because they represented areas where 80% of all chiller sales occurred over a 25 year period (1967-1992).
- **D3.3.3** Building types were a weighted average of all types (with chiller plants only) based on a DOE study of buildings in 1992 [DOE/EIA-0246(92)].
- **D3.3.4** Operational hours were a weighted average of various operations (with chiller plants only) taken from the DOE study of 1992 and a BOMA study (1995 BEE Report).
- **D3.3.5** A weighted average of buildings (with chiller plants only) with and without some form of economizer, based upon data from the DOE and BOMA reports, was included.
- **D3.3.6** The bulk of the load profile used in the last derivation of the equation was again used, which assumed that 38% of the buildings' load was average internal load (average of occupied vs. unoccupied internal load). It varies linearly with outdoor ambient and mean Condenser wet-bulb (MCWB) down to 50 °F DB, then flattens out below that to a minimum of 20% load.
- **D3.3.7** Point A was predetermined to be the design point of 100% load and 85°F ECWT/95 °F EDB for IPLV.IP or NPLV.IP. Other points were determined by distributional analysis of ton<sub>R</sub>-hours, MCWBs and EDBs. ECWTs were based upon actual MCWBs plus an 8 °F tower approach.

The individual equations that represent each operational type were then averaged in accordance with weightings obtained from the DOE and BOMA studies.

The load line was combined with the weather data hours (Figure D2) to create ton<sub>R</sub>-hours (Figure D3) for the temperature bin distributions. See graphs below:






Figure D2. Bin Groupings -Ton<sub>R</sub> Hours

A more detailed derivation of the Group 1 equation is presented here to illustrate the method. Groups 2, 3, and 4 are done similarly, but not shown here. In the chart below, note that the categories are distributed as follows:





Figure D3. Group 1 Ton<sub>R</sub>-hour Distribution Categories

Point A = 1 bin for Design Bin Point B = 4 bins for Peak Bin Point C = 4 bins for Low Bin

Point D = all bins below 55 °F for Min Bin

See Table D1 for Air Cooled and Table D2 for water-cooled calculations. The result is average weightings, ECWT's (or EDB's), and % Loads.

The next step is to begin again with Group 2 Ton Hour distribution as below. Note Group 2 is Group 1, but with 100% Economizer at 55 °F.



Operation is 24 hrs/day, 7 days/wk, 55 °F and above

Figure D4. Group 2 Ton<sub>R</sub>-hour Distribution Categories

After creating similar tables as in Tables D1 and D2 for Groups 2, 3, and 4, the resulting Group IPLV.IP or NPLV.IP equations are in Table D3.

The next step is to determine the % of each group which exists in buildings with central chiller plants, so that one final equation can be created from the four. From the DOE and BOMA studies, using goal seeking analysis, it was determined that:

Group 1 - 24.0%

Group 2 - 12.2%

Group 3 - 32.3%

Group 4 - 31.5%

This calculates to the following new equation: IPLV.IP equation (kW/ton<sub>R</sub>):

IPLV. IP = 
$$\frac{1}{\frac{0.014}{A} + \frac{0.416}{B} + \frac{0.446}{C} + \frac{0.124}{D}}$$

 $A = kW/ton_R$  @ 100% Load and 85°F ECWT or 95 °F EDB

 $B = kW/ton_R@76.1\%$  Load and 75.6°F ECWT or 82.1 °F EDB

C = kW/ton<sub>R</sub>@ 50.9% Load and 65.6°F ECWT or 65.8 °F EDB

 $D \ = \ kW/ton_R @ \ 32.2\% \ Load \ and \ 47.5°F \ ECWT \ or \ 39.5 \ °F \ EDB$ 

Rounding off and rationalizing:

IPLV. IP = 
$$\frac{1}{\frac{0.01}{A} + \frac{0.42}{B} + \frac{0.45}{C} + \frac{0.12}{D}}$$

 $A = kW/ton_R@ 100\%$  Load and 85 °F ECWT or 95 °F EDB

 $B = kWton_R@75\%$  Load and 75 °F ECWT or 80 °F EDB

 $C = kW/ton_R @ 50\% Load and 65 °F ECWT or 65 °F EDB$ 

 $D = kW/ton_R@ 25\%$  Load and 65 °F ECWT or 55 °F EDB

After rounding off and applying the rationale of where the manufacturers' and the current test facilities capabilities lie, the final Equation D2 is shown in Section D3.1.

				Table D	1. Group	1 Air-coole	d IPLV.IF	Data aı	nd Calcu	lation					
													C/S	Chiller	
							Min	Bin	Low	Bin	Peal	k Bin	Desi	esign Bin	
Outside Temp, °F	Average EDB, °F	OA EDB, °F	Total Hours, h	DBH, °F•h	Total, ton <sub>R</sub> •	Cooling Load, %	DBH, °F∙h	ton <sub>R</sub> •	DBH, °F•h	ton <sub>R</sub> •	DBH, °F∙h	ton <sub>R</sub> •	DBH, °F•h	ton <sub>R</sub> •	
95-99	97.5	97.5	37	3608	37	100%	0	0	0	0	0	0	3608	37	
90-94	92.5	92.5	120	11100	111	92%	0	0	0	0	11100	111	0	0	
85-89	87.5	87.5	303	26513	256	85%	0	0	0	0	26513	256	0	0	
80-84	82.5	82.5	517	42653	397	77%	0	0	0	0	42653	397	0	0	
75-79	77.5	77.5	780	60450	539	69%	0	0	0	0	60450	539	0	0	
70-74	72.5	72.5	929	67353	570	61%	0	0	67353	570	0	0	0	0	
65-69	67.5	67.5	894	60345	479	54%	0	0	60345	479	0	0	0	0	
60-64	62.5	62.5	856	53500	393	46%	0	0	53500	393	0	0	0	0	
55-59	57.5	57.5	777	44678	296	38%	0	0	44678	296	0	0	0	0	
50-54	52.5	52.5	678	35595	247	36%	35595	247	0	0	0	0	0	0	
45-49	47.5	47.5	586	27835	204	35%	27835	204	0	0	0	0	0	0	
40-44	42.5	42.5	550	23375	183	33%	23375	183	0	0	0	0	0	0	
35-39	37.5	37.5	518	19425	163	32%	19425	163	0	0	0	0	0	0	
30-34	32.5	32.5	467	15178	140	30%	15178	140	0	0	0	0	0	0	
25-29	27.5	27.5	299	8223	84	28%	8223	84	0	0	0	0	0	0	
20-24	22.5	22.5	183	4118	49	27%	4118	49	0	0	0	0	0	0	
15-19	17.5	17.5	111	1943	28	25%	1943	28	0	0	0	0	0	0	
10-14	12.5	12.5	68	850	16	23%	850	16	0	0	0	0	0	0	
05-09	7.5	7.5	40	300	9	22%	300	9	0	0	0	0	0	0	
00-04	2.5	2.5	47	118	9	20%	118	9	0	0	0	0	0	0	
Total	57.9	57.9	8760	507155	4210	DBH Total	136958	1132	225628	1738	140715	1303	3608	37	
						Weighting:		26.9%		41.3%		30.9%		0.9%	
						EDB °F:		38.6		65.4		81.8		95.0	
						Load:		31.9%		50.3%		75.7%		100%	
						Points		D		С		В		A	

				Table	D2. Gro	up 1 Wat	er-cooled IP	LV.IP Dat	a and Ca	lculation					
														C/S	Chiller
Outside				Total		Total		Mir	Bin	Low	Bin	Pea	k Bin	Desi	gn Bin
Temp, °F	Average EDB, °F	OA EWB, °F	CWH, °F•h	Hours,	CWH, °F•h	ton <sub>R</sub> -,	Cooling Load, %	CWH, °F•h	ton <sub>R</sub> -,	CWH, °F•h	ton <sub>R</sub> -,	CWH, °F•h	ton <sub>R</sub> -,	CWH , °F•h	ton <sub>R</sub> -,
95-99	97.5	72	80	37	2960	37	100%	0	0	0	0	0	0	2960	37
90-94	92.5	71	79	120	9480	111	92%	0	0	0	0	9480	111	0	0
85-89	87.5	69	77	303	23331	256	85%	0	0	0	0	23331	256	0	0
80-84	82.5	68	76	517	39292	397	77%	0	0	0	0	39292	397	0	0
75-79	77.5	66	74	780	57720	539	69%	0	0	0	0	57720	539	0	0
70-74	72.5	63	71	929	65959	570	61%	0	0	65959	570	0	0	0	0
65-69	67.5	59	67	894	59898	479	54%	0	0	59898	479	0	0	0	0
60-64	62.5	55	63	856	53928	393	46%	0	0	53928	393	0	0	0	0
55-59	57.5	50	59	777	45843	296	38%	0	0	45843	296	0	0	0	0
50-54	52.5	45	55	678	37290	247	36%	37290	247	0	0	0	0	0	0
45-49	47.5	41	52	586	30472	204	35%	30472	204	0	0	0	0	0	0
40-44	42.5	37	49	550	26950	183	33%	26950	183	0	0	0	0	0	0
35-39	37.5	32	45	518	23310	163	32%	23310	163	0	0	0	0	0	0
30-34	32.5	27	41	467	19147	140	30%	19147	140	0	0	0	0	0	0
25-29	27.5	22	40	299	11960	84	28%	11960	84	0	0	0	0	0	0
20-24	22.5	17	40	183	7320	49	27%	7320	49	0	0	0	0	0	0
15-19	17.5	13	40	111	4440	28	25%	4440	28	0	0	0	0	0	0
10-14	12.5	8	40	68	2720	16	23%	2720	16	0	0	0	0	0	0
05-09	7.5	4	40	40	1600	9	22%	1600	9	0	0	0	0	0	0
00-04	2.5	1	40	47	1880	9	20%	1880	9	0	0	0	0	0	0
Total	57.9	49.3	60.0	8760	525500	4210	CWH Total	167089	1132	225628	1738	129823	1303	2960	37
							Weighting:		26.9%		41.3%		30.9%		0.9%
							ECWT °F:		47.1		65.3		75.5		85.0
							Load:		31.9%		50.3%		75.7%		100%
							Points:		D		С		В		A

	Table D3. Group 1 – 4 IPLV.IP Summary								
Group 1	% Load	ECWT, °F	EDB, °F	Weight	Group 2	% Load	ECWT, °F	EDB, °F	Weight
A	100.0%	85.0	95.0	0.95%	A	100.0%	85.0	95.0	1.2%
В	75.7%	75.5	81.8	30.9%	В	75.7%	75.5	81.8	42.3%
C	50.3%	65.3	65.4	41.3%	C	50.3%	65.3	65.4	56.5%
D	31.9%	47.1	38.6	26.9%	D	N/A	N/A	N/A	0.0%
IPLV.IP =	0.009/A+	1 - 0.309/B+		- 0.269/D	IPLV.IP =	-			C + 0.0/D
Group 3	% Load	ECWT, °F	EDB, °F	Weight	Group 4	% Load	ECWT,	EDB, °F	Weight
A	100.0%	85.0	95.0	1.5%	A	100.0%	85.0	95.0	1.8%
В	75.7%	75.6	82.2	40.9%	В	76.4%	75.6	82.2	50.1%
С	50.3%	65.8	66.0	39.2%	C	51.3%	65.8	66.0	48.1%
D	31.9%	47.7	40.0	18.4%	D	N/A	N/A	N/A	0.0%
$ \begin{array}{c c} IPLV.IP & 1 \\  & 0.015/A + 0.409/B + 0.392/C + 0.184/D \end{array} $			IPLV.IP =	0.018/A	1 + 0.501/B		C + 0.0/D		

## APPENDIX E. AVERAGING - INFORMATIVE

- **E1** *Purpose*. This appendix describes a method to average data samples collected between each time stamp for the test data points collected in accordance with ANSI/ASHRAE Standard 30.
- E2 General. Per the requirements of ANSI/ASHRAE Standard 30, averaging of data samples between each time stamp can be employed and reported for each of the 30 or more data points required to be collected and reported at uniform time intervals. This averaging can be performed either within hardware or software, either within the measuring instrument or a data acquisition system, can use any method of averaging (e.g. simple moving average or a weighted moving average of trailing points), with the requirement that the time interval across which data samples are averaged to create each data point does not exceed 1/60 of the total test time period. If choosing to test for the minimum allowable time period of 15 minutes, then the method of averaging only uses samples from a time period not exceeding 15 seconds. Choosing a longer test time period allows a longer averaging time period (e.g. a 20 minute test period allows 20 second averaging). Recording or reporting of the data samples is not requiredare, due to the fact that some hardware implementations of averaging (also referred to as filtering or smoothing for some measurement instrument types) never indicate or communicate the internally collected samples. The resulting data points are then used to calculate the mean and standard deviation in accordance with Section C3.2, for use in judging compliance with the operating condition tolerance limit and the stability criteria found in Table 1.
- **E3** Examples. Two examples are provided using leaving Evaporator water temperature. The sample data (raw data) shown in Tables I1.2 and I2.2 and the summary of sample data shown in Tables E1.2 and E2.2 are provided for informational purposes only to demonstrate the concept, even though this data is not required to be recorded or reported. Visual representations of sample data are provided in Figures E1 and E2.

Example #1 is a data set that meets the target test condition of  $7.00\,^{\circ}\text{C}$  within the operating condition tolerance limit of  $\pm 0.28\,^{\circ}\text{C}$  and stability criteria to have a standard deviation not exceeding  $0.10\,^{\circ}\text{C}$  as found in Table 1 for leaving Evaporator water and cooling mode operation. Example #2 is a similar data set that does not meet the stability criteria. Both examples have chosen to use a 20 minute test time period. The data acquisition system is capable of collecting data samples at 5 second intervals. The maximum allowable averaging is employed by taking the average of 5 data samples collected over the trailing 20 second time period (t=0, -5, -10, -15, -20 seconds).

**E3.1** Example #1. Referring to Table E1.2, the data point value 7.31 for time = 0:00:30.0 was calculated as the average of sample values 7.28, 7.23, 7.37, 7.32, and 7.36 °C. The prior sample value of 7.16 °C was discarded since it is outside the allowable 20 second time interval for averaging.

Table E1.1. Summary of Example #1						
Item	Averaging	Count	Mean, °C	Standard Deviation, °C		
Data Samples (All Raw Data)	None	246	7.18	0.11		
Data Points (Averaged Data Samples)	Simple moving average for 20 seconds (using the trailing 5 samples)	41	7.18	0.08		

For the data points, the mean value is within the operating condition tolerance interval of 7.00±0.28 °C, and the standard deviation is within the stability criterion of less than or equal to 0.10 °C, so this test point is valid. Note that in this example, the use of averaging significantly reduced the standard deviation.

Tal	ble E1.2. Data	a for Example	e #1
	Data	Data Point	Data Point
Test Time	Sample (°C)	Time	(°C)
-0:00:25.0	7.38		
-0:00:20.0	7.35		
-0:00:15.0	7.40		
-0:00:10.0	7.12		
-0:00:05.0	7.37		
0:00:00.0	7.30	0:00:00.0	7.31
0:00:05.0	7.16	0.00.00.0	7.31
0:00:10.0	7.36		
0:00:15.0	7.32		
0:00:20.0	7.37		
0:00:25.0	7.23		
0:00:30.0	7.28	0:00:30.0	7.31
0:00:35.0	7.16	0.00.30.0	7.31
0:00:40.0	7.10		
0:00:40.0	7.29		
0:00:43.0	7.26		
0:00:50.0			
	7.39	0.01.00.0	7 22
0:01:00.0	7.35	0:01:00.0	7.33
0:01:05.0	7.32		
0:01:10.0	7.29		
0:01:15.0	7.24		
0:01:20.0	7.21		
0:01:25.0	7.16	0.01.20.0	7.00
0:01:30.0	7.23	0:01:30.0	7.23
0:01:35.0	7.23		
0:01:40.0	7.29		
0:01:45.0	7.17		
0:01:50.0	7.43		
0:01:55.0	7.14	0.02.00.0	7.20
0:02:00.0	7.39	0:02:00.0	7.28
0:02:05.0	7.30		
0:02:10.0	7.21		
0:02:15.0	7.20		
0:02:20.0	7.31		
0:02:25.0	7.19	0.02.22	
0:02:30.0	7.27	0:02:30.0	7.24
0:02:35.0	7.33		
0:02:40.0	7.21		
0:02:45.0	7.27		
0:02:50.0	7.42		
0:02:55.0	7.15		<u> </u>
0:03:00.0	7.32	0:03:00.0	7.27
0:03:05.0	7.39		
0:03:10.0	7.23		
0:03:15.0	7.21		
0:03:20.0	7.13		
0:03:25.0	7.28		
0:03:30.0	7.18	0:03:30.0	7.21
0:03:35.0	7.17		
0:03:40.0	7.17		
0:03:45.0	7.39		
0:03:50.0	7.38		
0:03:55.0	7.34		
			•

Table E1	.2. Data for E	xample #1 (C	ontinued)
	Data	Data Point	Data Point
Test Time	Sample (°C)	Time	(°C)
0:04:00.0	7.26	0:04:00.0	7.31
0:04:05.0	7.25	0.01.00.0	7.51
0:04:10.0	7.16		
-			
0:04:15.0	7.38		
0:04:20.0	7.24		
0:04:25.0	7.34		
0:04:30.0	7.32	0:04:30.0	7.29
0:04:35.0	7.39		
0:04:40.0	7.35		
0:04:45.0	7.17		
0:04:50.0	7.15		
0:04:55.0	7.16		
0:05:00.0	7.28	0:05:00.0	7.22
0:05:05.0	7.32	010010010	,,,,,
0:05:10.0	7.23		1
0:05:15.0	7.25		
0:05:13.0	7.32		+
			-
0:05:25.0	7.13	0.07.20.0	7.00
0:05:30.0	7.09	0:05:30.0	7.22
0:05:35.0	7.19		
0:05:40.0	7.17		
0:05:45.0	7.09		
0:05:50.0	7.12		
0:05:55.0	7.09		
0:06:00.0	7.17	0:06:00.0	7.13
0:06:05.0	7.14		
0:06:10.0	7.35		
0:06:15.0	7.06		
0:06:20.0	7.23		
0:06:25.0	7.11		
0:06:30.0	7.06	0:06:30.0	7.16
0:06:35.0	7.08	0.00.30.0	7.10
0:06:40.0	7.09		
0:06:45.0	7.27		1
0:06:50.0	7.26		
0:06:55.0	7.29	0.5=-	
0:07:00.0	7.04	0:07:00.0	7.19
0:07:05.0	7.19		1
0:07:10.0	7.07		
0:07:15.0	7.21		
0:07:20.0	7.03		
0:07:25.0	7.12		
0:07:30.0	7.04	0:07:30.0	7.09
0:07:35.0	7.13		
0:07:40.0	7.26		
0:07:45.0	7.26		
0:07:50.0	7.20		
0:07:55.0	7.07		
	1	0.00.00	7 22
0:08:00.0	7.22	0:08:00.0	7.22
0:08:05.0	7.23		1
0:08:10.0	7.22		-
0:08:15.0	7.19		
0:08:20.0	7.20		<u> </u>

Table E1	.2. Data for E	xample #1 (C	ontinued)
T T'	Data	Data Point	Data Point
Test Time	Sample (°C)	Time	(°C)
0:08:25.0	7.06		
0:08:30.0	7.14	0:08:30.0	7.16
0:08:35.0	7.01		
0:08:40.0	7.03		
0:08:45.0	7.12		
0:08:50.0	7.28		
0:08:55.0	7.03		
0:09:00.0	7.23	0:09:00.0	7.14
0:09:05.0	7.13	0.07.00.0	7.11
0:09:10.0	7.06		
0:09:15.0	7.09		
0:09:20.0	7.11		
0:09:25.0	7.11		
0:09:30.0	7.20	0:09:30.0	7.14
0:09:35.0	7.19	0.07.30.0	7.14
0:09:33.0	7.19		1
0:09:45.0	7.00		
0:09:43.0	7.19		
0:09:50.0	7.17		1
		0.10.00.0	7 15
0:10:00.0	7.26	0:10:00.0	7.15
0:10:05.0	7.08		
0:10:10.0	7.22		
0:10:15.0	7.18		
0:10:20.0	7.24		
0:10:25.0	7.14	0.10.20.0	7.17
0:10:30.0	7.08	0:10:30.0	7.17
0:10:35.0	7.29		
0:10:40.0	7.27		
0:10:45.0	7.09		
0:10:50.0	7.11		
0:10:55.0	7.08		
0:11:00.0	7.03	0:11:00.0	7.12
0:11:05.0	7.09		
0:11:10.0	7.08		
0:11:15.0	7.29		
0:11:20.0	7.14		
0:11:25.0	7.12		
0:11:30.0	7.13	0:11:30.0	7.15
0:11:35.0	7.27		
0:11:40.0	7.14		
0:11:45.0	7.17		
0:11:50.0	7.23		
0:11:55.0	7.28		
0:12:00.0	7.23	0:12:00.0	7.21
0:12:05.0	7.24		
0:12:10.0	7.11		
0:12:15.0	7.28		
0:12:20.0	7.29		
0:12:25.0	7.24		
0:12:30.0	7.07	0:12:30.0	7.20
0:12:35.0	7.33		
0:12:40.0	7.29		
0:12:45.0	7.31		
			1

Table E1	.2. Data for E	xample #1 (Co	ontinued)
Test Time	Data	Data Point	Data Point
Test Time	Sample (°C)	Time	(°C)
0:12:50.0	7.12		
0:12:55.0	7.24		
0:13:00.0	7.09	0:13:00.0	7.21
0:13:05.0	7.23		
0:13:10.0	7.25		
0:13:15.0	7.12		
0:13:20.0	7.25		
0:13:25.0	7.29		
0:13:30.0	7.06	0:13:30.0	7.19
0:13:35.0	7.06		
0:13:40.0	7.34		
0:13:45.0	7.32		
0:13:50.0	7.14		
0:13:55.0	7.15		
0:14:00.0	7.29	0:14:00.0	7.25
0:14:05.0	7.34		
0:14:10.0	7.08		
0:14:15.0	7.21		
0:14:20.0	7.24		
0:14:25.0	7.30		
0:14:30.0	7.25	0:14:30.0	7.22
0:14:35.0	7.08		
0:14:40.0	7.19		
0:14:45.0	7.31		
0:14:50.0	7.21		
0:14:55.0	7.16		
0:15:00.0	7.06	0:15:00.0	7.19
0:15:05.0	7.08		
0:15:10.0	7.10		
0:15:15.0	7.11		
0:15:20.0	7.03		
0:15:25.0	7.30		
0:15:30.0	7.07	0:15:30.0	7.12
0:15:35.0	7.29		
0:15:40.0	7.07		
0:15:45.0	7.05		
0:15:50.0	7.32		
0:15:55.0	7.21	0.16.00.0	7.10
0:16:00.0	7.28	0:16:00.0	7.19
0:16:05.0	7.09		
0:16:10.0	7.23		
0:16:15.0	7.02		
0:16:20.0	7.01		
0:16:25.0	7.13	0.15.20.0	<b>5</b> .00
0:16:30.0	7.00	0:16:30.0	7.08
0:16:35.0	7.08		
0:16:40.0	7.21		
0:16:45.0	7.09		
0:16:50.0	7.01		
0:16:55.0	7.06	0.17.00.0	7.07
0:17:00.0	6.99	0:17:00.0	7.07
0:17:05.0	7.27		
0:17:10.0	7.28		

Table E1.2. Data for Example #1 (Continued)						
T4 Ti	Data	Data Point	Data Point			
Test Time	Sample (°C)	Time	(°C)			
0:17:15.0	7.09					
0:17:20.0	7.13					
0:17:25.0	7.12					
0:17:30.0	6.99	0:17:30.0	7.12			
0:17:35.0	7.02					
0:17:40.0	7.01					
0:17:45.0	7.08					
0:17:50.0	7.01					
0:17:55.0	7.09					
0:18:00.0	7.26	0:18:00.0	7.09			
0:18:05.0	7.18					
0:18:10.0	7.01					
0:18:15.0	6.96					
0:18:20.0	7.02					
0:18:25.0	6.98					
0:18:30.0	7.23	0:18:30.0	7.04			
0:18:35.0	6.98		_			

Table E1.2. Data for Example #1 (Continued)					
Test Time	Data	Data Point	Data Point		
Test Time	Sample (°C)	Time	(°C)		
0:18:40.0	7.13				
0:18:45.0	6.97				
0:18:50.0	6.97				
0:18:55.0	7.14				
0:19:00.0	7.10	0:19:00.0	7.06		
0:19:05.0	7.12				
0:19:10.0	7.03				
0:19:15.0	7.01				
0:19:20.0	7.13				
0:19:25.0	7.16				
0:19:30.0	7.16	0:19:30.0	7.10		
0:19:35.0	7.16				
0:19:40.0	6.93				
0:19:45.0	7.11				
0:19:50.0	7.20				
0:19:55.0	7.23	_			
0:20:00.0	7.06	0:20:00.0	7.11		




Figure E1. Example #1 Charts

Left panel: Plot of the data samples (246) and data points (41) versus time.

Right panel: Plot of the mean and standard deviation of the data points. Solid black line indicates the test target condition. Dashed lines indicate the Table 1 limits. This test point is valid due to meeting both the operating condition tolerance limit and the stability criteria (inside the dashed lines).

**E3.2** Example #2. Referring to Table E2.2, the data point value 7.31 for time = 0:00:30.0 was calculated as the average of sample values 7.33, 7.25, 7.22, 7.27, and 7.47 °C. The prior sample value of 7.46 °C was discarded since it is outside the allowable 20 second time interval for averaging.

Table E2.1. Summary of Example #2.					
Item	Averaging	Count	Mean, °C	Standard Deviation, °C	
Data Samples (All Raw Data)	None	246	7.06	0.15	
Data Points (Averaged Data Samples)	Simple moving average for 20 seconds (using the trailing 5 samples)	41	7.06	0.12	

While the mean value is within the operating condition tolerance interval of 7.00±0.28 °C, the standard deviation exceeds the stability criterion of less than equal to 0.10 °C, so this test point is not valid and is either repeated, or operation continued and a new set of test data collected. Note that in this example, the use of averaging was not as effective as in the prior example for reducing the standard deviation, due to the water temperature change versus time, or lack of sufficient stability.

Table E2.2. Data for Example #2           Test Time         Data Sample (°C)         Data Point Time         Data Point (°C)           -0:00:25.0         7.26         -0:00:20.0         7.23           -0:00:15.0         7.26         -0:00:15.0         7.26           -0:00:10.0         7.29         -0:00:00.0         7.29           -0:00:05.0         7.39         0:00:00.0         7.29           0:00:05.0         7.46         0:00:00.0         7.29           0:00:15.0         7.47         0:00:15.0         7.27           0:00:20.0         7.27         0:00:20.0         7.21           0:00:25.0         7.25         0:00:30.0         7.31           0:00:35.0         7.44         0:00:30.0         7.31           0:00:45.0         7.23         0:00:50.0         7.21           0:00:50.0         7.22         0:00:50.0         7.31           0:01:00.0         7.38         0:01:00.0         7.31           0:01:10.0         7.22         0:01:10.0         7.22           0:01:10.0         7.22         0:01:10.0         7.22
Time         Sample (°C)         Time         (°C)           -0:00:25.0         7.26         (°C)         7.26           -0:00:15.0         7.26         (°C)         7.26           -0:00:10.0         7.29         (°C)         7.29           -0:00:05.0         7.39         (°C)         7.29           0:00:00.0         7.27         0:00:00.0         7.29           0:00:10.0         7.47         (°C)         7.29           0:00:15.0         7.27         (°C)         7.29           0:00:15.0         7.27         (°C)         7.29           0:00:20.0         7.22         (°C)         7.31           0:00:20.0         7.25         (°C)         7.31           0:00:30.0         7.33         0:00:30.0         7.31           0:00:40.0         7.32         (°C)         7.22           0:00:45.0         7.23         (°C)         7.31           0:00:50.0         7.22         (°C)         7.31           0:01:00.0         7.38         0:01:00.0         7.31           0:01:10.0         7.22         (°C)         7.22         (°C)
-0:00:25.0         7.26           -0:00:20.0         7.23           -0:00:15.0         7.26           -0:00:10.0         7.29           -0:00:05.0         7.39           0:00:05.0         7.46           0:00:10.0         7.47           0:00:15.0         7.27           0:00:20.0         7.22           0:00:25.0         7.25           0:00:30.0         7.33         0:00:30.0         7.31           0:00:35.0         7.44         0:00:40.0         7.32           0:00:45.0         7.23         0:00:50.0         7.22           0:00:55.0         7.39         0:01:00.0         7.31           0:01:05.0         7.28         0:01:10.0         7.22
-0:00:20.0         7.23           -0:00:15.0         7.26           -0:00:10.0         7.29           -0:00:05.0         7.39           0:00:00.0         7.27         0:00:00.0         7.29           0:00:05.0         7.46         0:00:10.0         7.47           0:00:15.0         7.27         0:00:20.0         7.22           0:00:25.0         7.25         0:00:30.0         7.31           0:00:35.0         7.44         0:00:40.0         7.32           0:00:45.0         7.23         0:00:50.0         7.22           0:00:55.0         7.39         0:01:00.0         7.31           0:01:05.0         7.28         0:01:10.0         7.22
-0:00:15.0         7.26           -0:00:10.0         7.29           -0:00:05.0         7.39           0:00:00.0         7.27         0:00:00.0         7.29           0:00:05.0         7.46         0:00:10.0         7.47           0:00:15.0         7.27         0:00:20.0         7.22           0:00:20.0         7.25         0:00:30.0         7.31           0:00:35.0         7.44         0:00:40.0         7.32           0:00:45.0         7.23         0:00:50.0         7.22           0:00:55.0         7.39         0:01:00.0         7.38         0:01:00.0         7.31           0:01:05.0         7.28         0:01:10.0         7.22         0:01:10.0         7.22
-0:00:10.0         7.29           -0:00:05.0         7.39           0:00:00.0         7.27         0:00:00.0         7.29           0:00:05.0         7.46         7.47         7.27         7.27         7.27         7.27         7.27         7.27         7.27         7.27         7.25         7.25         7.25         7.25         7.25         7.25         7.27         7.27         7.27         7.27         7.27         7.27         7.27         7.27         7.27         7.27         7.27         7.27         7.27         7.21         7.21         7.21         7.21         7.21         7.21         7.21         7.21         7.21         7.21         7.21         7.21         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.23         7.23         7.23         7.23         7.23         7.23         7.23         7.23         7.23         7.23         7.23         7.23         7.23         7.23         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.2
-0:00:05.0         7.39           0:00:00.0         7.27         0:00:00.0         7.29           0:00:05.0         7.46         7.47         7.27         7.27         7.27         7.27         7.27         7.27         7.27         7.22         7.25         7.25         7.25         7.25         7.25         7.25         7.27         7.27         7.27         7.27         7.27         7.27         7.28         7.29         7.29         7.29         7.21         7.21         7.21         7.21         7.21         7.21         7.21         7.21         7.21         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.22         7.23         7.23         7.23         7.23         7.23         7.23         7.24         7.22         7.23         7.24         7.22         7.23         7.23         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24         7.24 </td
0:00:00.0         7.27         0:00:00.0         7.29           0:00:05.0         7.46           7.29           0:00:10.0         7.47
0:00:05.0         7.46           0:00:10.0         7.47           0:00:15.0         7.27           0:00:20.0         7.22           0:00:25.0         7.25           0:00:30.0         7.33         0:00:30.0         7.31           0:00:35.0         7.44         0:00:40.0         7.32           0:00:45.0         7.23         0:00:50.0         7.22           0:00:55.0         7.39         0:01:00.0         7.31           0:01:05.0         7.28         0:01:10.0         7.22
0:00:10.0         7.47           0:00:15.0         7.27           0:00:20.0         7.22           0:00:25.0         7.25           0:00:30.0         7.33         0:00:30.0         7.31           0:00:35.0         7.44         0:00:40.0         7.32           0:00:45.0         7.23         0:00:50.0         7.22           0:00:55.0         7.39         0:01:00.0         7.31           0:01:05.0         7.28         0:01:10.0         7.22
0:00:15.0         7.27           0:00:20.0         7.22           0:00:25.0         7.25           0:00:30.0         7.33         0:00:30.0         7.31           0:00:35.0         7.44         0:00:40.0         7.32           0:00:45.0         7.23         0:00:50.0         7.22           0:00:55.0         7.39         0:01:00.0         7.38         0:01:00.0         7.31           0:01:05.0         7.28         0:01:10.0         7.22         0:01:10.0         0.01:00.0         7.22
0:00:20.0         7.22           0:00:25.0         7.25           0:00:30.0         7.33         0:00:30.0         7.31           0:00:35.0         7.44         0:00:40.0         7.32           0:00:45.0         7.23         0:00:50.0         7.22           0:00:55.0         7.39         0:01:00.0         7.38         0:01:00.0         7.31           0:01:05.0         7.28         0:01:10.0         7.22         0:01:10.0         7.22         0:01:00.0         7.31         0:01:05.0         7.28         0:01:10.0         7.22         0:01:05.0         7.22         0:01:05.0         7.22         0:01:05.0         7.28         0:01:05.0         7.22         0:01:05.0         7.22         0:01:05.0         7.22         0:01:05.0         7.22         0:01:05.0         7.22         0:01:05.0         7.22         0:01:05.0         7.22         0:01:05.0         7.22         0:01:05.0         7.22         0:01:05.0         7.22         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05.0         0:01:05
0:00:25.0         7.25           0:00:30.0         7.33         0:00:30.0         7.31           0:00:35.0         7.44         0:00:40.0         7.32           0:00:45.0         7.23         0:00:50.0         7.22           0:00:55.0         7.39         0:01:00.0         7.38         0:01:00.0         7.31           0:01:05.0         7.28         0:01:10.0         7.22         0:01:10.0         7.22         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.22         0:01:00.0         7.22         0:01:00.0         7.31         0:01:00.0         7.22         0:01:00.0         7.31         0:01:00.0         7.22         0:01:00.0         7.22         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         0:01:00.0         7.31         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0
0:00:25.0         7.25           0:00:30.0         7.33         0:00:30.0         7.31           0:00:35.0         7.44         0:00:40.0         7.32           0:00:45.0         7.23         0:00:50.0         7.22           0:00:55.0         7.39         0:01:00.0         7.38         0:01:00.0         7.31           0:01:05.0         7.28         0:01:10.0         7.22         0:01:10.0         7.22         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.22         0:01:00.0         7.22         0:01:00.0         7.31         0:01:00.0         7.22         0:01:00.0         7.31         0:01:00.0         7.22         0:01:00.0         7.22         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         7.31         0:01:00.0         0:01:00.0         7.31         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0         0:01:00.0
0:00:30.0       7.33       0:00:30.0       7.31         0:00:35.0       7.44       7.32       7.32         0:00:45.0       7.23       7.23       7.22         0:00:55.0       7.22       7.39       7.38       0:01:00.0       7.31         0:01:05.0       7.28       7.22       7.23
0:00:35.0     7.44       0:00:40.0     7.32       0:00:45.0     7.23       0:00:50.0     7.22       0:00:55.0     7.39       0:01:00.0     7.38     0:01:00.0     7.31       0:01:05.0     7.28       0:01:10.0     7.22
0:00:40.0     7.32       0:00:45.0     7.23       0:00:50.0     7.22       0:00:55.0     7.39       0:01:00.0     7.38     0:01:00.0     7.31       0:01:05.0     7.28       0:01:10.0     7.22
0:00:45.0     7.23       0:00:50.0     7.22       0:00:55.0     7.39       0:01:00.0     7.38     0:01:00.0     7.31       0:01:05.0     7.28       0:01:10.0     7.22
0:00:50.0     7.22       0:00:55.0     7.39       0:01:00.0     7.38     0:01:00.0     7.31       0:01:05.0     7.28       0:01:10.0     7.22
0:00:55.0     7.39       0:01:00.0     7.38     0:01:00.0     7.31       0:01:05.0     7.28       0:01:10.0     7.22
0:01:00.0     7.38     0:01:00.0     7.31       0:01:05.0     7.28       0:01:10.0     7.22
0:01:05.0 7.28 0:01:10.0 7.22
0:01:10.0 7.22
0.01.15 0 7 10
0:01:15.0 7.18
0:01:20.0 7.44
0:01:25.0 7.35
0:01:30.0 7.21 0:01:30.0 7.28
0:01:35.0 7.35
0:01:40.0 7.30
0:01:45.0 7.22
0:01:50.0 7.32
0:01:55.0 7.17
0:02:00.0 7.37 0:02:00.0 7.28
0:02:05.0 7.18
0:02:15.0 7.40
0:02:20.0 7.16
0:02:25.0 7.16
0:02:30.0 7.39 0:02:30.0 7.28
0:02:35.0 7.28
0:02:40.0 7.24
0:02:45.0 7.21
0:02:50.0 7.33
0:02:55.0 7.24
0:03:00.0 7.23 0:03:00.0 7.25
0:03:05.0 7.33
0:03:10.0 7.13
0:03:15.0 7.18
0:03:20.0 7.19
0:03:25.0 7.29
0:03:30.0 7.28 0:03:30.0 7.21
0:03:35.0 7.12
0:03:40.0 7.26
0:03:45.0 7.17
0:03:50.0 7.16
0:03:55.0 7.12

Table E2	2. Data for E	xample #2 (Co	ontinued)
T T:	Data	Data Point	Data Point
Test Time	Sample (°C)	Time	(°C)
0:04:00.0	7.22	0:04:00.0	7.19
0:04:05.0	7.11		
0:04:10.0	7.12		
0:04:15.0	7.18		
0:04:20.0	7.09		
0:04:25.0	7.22		
0:04:30.0	7.25	0:04:30.0	7.17
0:04:35.0	7.02		
0:04:40.0	7.04		
0:04:45.0	7.02		
0:04:50.0	7.13		
0:04:55.0	7.02		
0:05:00.0	7.15	0:05:00.0	7.07
0:05:05.0	7.06	0.05.00.0	7.07
0:05:10.0	7.19		
0:05:15.0	7.17		
0:05:20.0	7.17		
0:05:25.0	7.09		
0:05:30.0	7.19	0:05:30.0	7.14
0:05:35.0	7.19	0.05.50.0	7.14
0:05:40.0	7.19		
0:05:45.0	6.95		
0:05:50.0	7.10		
0:05:55.0	7.10		
	6.96	0.06.00 0	7.03
0:06:00.0	6.96	0:06:00.0	7.03
0:06:03.0			
0:06:10.0	7.06 7.04		
0:06:13.0	7.04		
0:06:20.0	7.17		
	6.95	0.06.20.0	7.05
0:06:30.0		0:06:30.0	7.03
0:06:33.0	7.16		
	7.14		
0:06:45.0	7.10		
0:06:50.0	7.04		
0:06:55.0	6.93	0.07.00 0	7.02
0:07:00.0	6.92	0:07:00.0	7.03
0:07:05.0	6.93		
0:07:10.0	7.13		
0:07:15.0	6.92		
0:07:20.0 0:07:25.0	6.93 6.93		
0:07:25.0		0.07.20.0	7.00
0:07:30.0	7.09 6.91	0:07:30.0	7.00
0:07:40.0	6.97		
0:07:45.0 0:07:50.0	7.00		
0:07:55.0	7.02 6.94		
		0.00.00	7.00
0:08:00.0	7.07	0:08:00.0	7.00
0:08:05.0	7.03		
0:08:10.0	6.87		
0:08:15.0	6.99		
0:08:20.0	7.05		

Table E2	.2. Data for E	xample #2 (C	ontinued)
	Data	Data Point	Data Point
Test Time	Sample (°C)	Time	(°C)
0:08:25.0	7.06	-	( - /
0:08:30.0	7.09	0:08:30.0	7.01
		0.00.50.0	7.01
0:08:35.0	6.96		
0:08:40.0	7.03		
0:08:45.0	7.03		
0:08:50.0	6.87		
0:08:55.0	7.04		
0:09:00.0	6.82	0:09:00.0	6.96
0:09:05.0	6.92		
0:09:10.0	6.96		
0:09:15.0	7.06		
0:09:20.0	6.86		
0:09:25.0	6.99		
0:09:30.0	6.81	0:09:30.0	6.94
0:09:35.0	6.88		
0:09:40.0	6.90		
0:09:45.0	7.06		
0:09:50.0	6.89		
0:09:55.0	6.86		
0:10:00.0	6.82	0:10:00.0	6.91
0:10:05.0	6.86	0.10.00.0	0.91
0:10:10.0	6.89		
0:10:15.0	7.05		
0:10:20.0	6.82		
0:10:25.0	7.04		
0:10:30.0	6.97	0:10:30.0	6.95
0:10:35.0	7.08		
0:10:40.0	6.89		
0:10:45.0	6.99		
0:10:50.0	7.02		
0:10:55.0	7.06		
0:10:33.0		0:11:00.0	6.97
	6.88	0.11.00.0	0.97
0:11:05.0	7.02		
0:11:10.0	6.90		
0:11:15.0	6.85		
0:11:20.0	6.94		
0:11:25.0	7.03		
0:11:30.0	6.91	0:11:30.0	6.93
0:11:35.0	7.09		
0:11:40.0	6.85		
0:11:45.0	6.87		
0:11:50.0	6.92		
0:11:55.0	7.09		
		0.12.00.0	6.07
0:12:00.0	7.11	0:12:00.0	6.97
0:12:05.0	6.93		
0:12:10.0	6.99		
0:12:15.0	6.89		
0:12:20.0	7.06		
0:12:25.0	7.04		
0:12:30.0	6.95	0:12:30.0	6.99
0:12:35.0	6.96		
0:12:40.0	6.88		
0:12:45.0	7.09		
0.12.73.0	1.07		1

Table E2.	.2. Data for E	xample #2 (Co	ontinued)
Test Time	Data	Data Point	Data Point
	Sample (°C)	Time	(°C)
0:12:50.0	6.99		
0:12:55.0	7.02		
0:13:00.0	6.91	0:13:00.0	6.98
0:13:05.0	6.88		
0:13:10.0	7.10		
0:13:15.0	6.92		
0:13:20.0	6.94		
0:13:25.0	7.13		
0:13:30.0	6.95	0:13:30.0	7.01
0:13:35.0	7.12		
0:13:40.0	6.99		
0:13:45.0	7.04		
0:13:50.0	6.93		
0:13:55.0	6.97		
0:14:00.0	7.12	0:14:00.0	7.01
0:14:05.0	7.12	5.11.00.0	7.01
0:14:10.0	6.89		
0:14:15.0	7.04		
0:14:20.0	7.04		
0:14:25.0	6.89		
0:14:25.0	6.93	0:14:30.0	6.97
0:14:35.0	6.91	0.14.50.0	0.97
0:14:35.0	7.12		
0:14:45.0	7.12		
0:14:50.0	6.93		
0:14:55.0	7.09	0.15.00.0	7.05
0:15:00.0	7.07	0:15:00.0	7.05
0:15:05.0	7.10		
0:15:10.0	6.93		
0:15:15.0	7.02		
0:15:20.0	7.03		
0:15:25.0	7.13	0.15.20.0	7.00
0:15:30.0	6.87	0:15:30.0	7.00
0:15:35.0	6.93		
0:15:40.0	7.13		
0:15:45.0	6.88		
0:15:50.0	7.03		
0:15:55.0	6.96	0.16.00.0	6.00
0:16:00.0	6.90	0:16:00.0	6.98
0:16:05.0	7.09		
0:16:10.0	7.10		
0:16:15.0	6.93		
0:16:20.0	7.09		
0:16:25.0	7.03		
0:16:30.0	6.99	0:16:30.0	7.03
0:16:35.0	7.08		
0:16:40.0	6.87		
0:16:45.0	7.02		
0:16:50.0	6.84		
0:16:55.0	7.09		
0:17:00.0	7.00	0:17:00.0	6.96
0:17:05.0	6.93		
0:17:10.0	6.91		

## ANSI/AHRI Standard 551/591-2023 (SI)\_\_\_\_\_

Table E2	.2. Data for E	xample #2 (C	ontinued)
Test Time	Data	Data Point	Data Point
Test Time	Sample (°C)	Time	(°C)
0:17:15.0	6.89		
0:17:20.0	7.09		
0:17:25.0	6.94		
0:17:30.0	6.84	0:17:30.0	6.93
0:17:35.0	7.08		
0:17:40.0	7.02		
0:17:45.0	7.06		
0:17:50.0	7.01		
0:17:55.0	6.86		
0:18:00.0	6.96	0:18:00.0	6.98
0:18:05.0	7.08		
0:18:10.0	7.07		
0:18:15.0	6.91		
0:18:20.0	6.99		
0:18:25.0	7.08		
0:18:30.0	6.98	0:18:30.0	7.01
0:18:35.0	6.92		

Table E2	2. Data for E	xample #2 (Co	ontinued)
Test Time	Data	Data Point	Data Point
Test Time	Sample (°C)	Time	(°C)
0:18:40.0	6.96		
0:18:45.0	7.06		
0:18:50.0	7.02		
0:18:55.0	6.90		
0:19:00.0	6.98	0:19:00.0	6.98
0:19:05.0	7.00		
0:19:10.0	6.99		
0:19:15.0	6.94		
0:19:20.0	6.89		
0:19:25.0	6.88		
0:19:30.0	6.87	0:19:30.0	6.91
0:19:35.0	6.87		
0:19:40.0	7.04		
0:19:45.0	7.02		
0:19:50.0	7.07		
0:19:55.0	6.98		
0:20:00.0	7.08	0:20:00.0	7.04




Figure E2. Example #2 Charts

Left panel: Plot of the data samples (246) and data points (41) versus time.

Right panel: Plot of the mean and standard deviation of the data points. Solid black line indicates the test target condition. Dashed lines indicate the Table 1 limits. This test point is invalid due to not meeting the stability criteria (outside the dashed lines).

## APPENDIX F. EXAMPLES – INFORMATIVE

- **F1** Purpose. This appendix provides example calculations to clarify the requirements of the standard.
- **F2** Examples. Example calculations are detailed below for fouling factor correction, concurrent redundant verification, IPLV.SI and NPLV.SI, tolerance limits, and atmospheric pressure adjustment.
  - **F2.1** Fouling Factor Correction Condenser Fouling Inside Tubes.

Specified Fouling Factor Allowance, R<sub>foul</sub> = 0.0440 m<sup>2</sup>·K/kW

Condenser load,  $Q_{cd} = 850.0 \text{ kW}$ 

Specified Condenser leaving water temp, T<sub>out,w</sub> = 35.00 °C

Specified Condenser entering water temp, T<sub>in,w</sub> = 30.00 °C

Specified saturated condensing temperature with specified fouling, T<sub>sat,r</sub> = 38.00 °C

Inside tube surface area,  $A = 50 \text{ m}^2$  (since fouling is inside tubes in this example)

$$\Delta T_{\text{range}} = |T_{\text{out,w}} - T_{\text{in,w}}| = 35.00 - 30.00 = 5.00 \text{ K}$$

$$\Delta T_{\text{small.sp}} = |T_{\text{sat.r}} - T_{\text{out.w}}| = 38.00 - 35.00 = 3.00 \text{ K}$$

$$\Delta T_{\text{LMTD}} = \frac{\Delta T_{\text{range}}}{\ln\left(1 + \frac{\Delta T_{\text{range}}}{\Delta T_{\text{small sp}}}\right)} = \frac{5.00}{\ln\left(1 + \frac{5.00}{3.00}\right)} = 5.0977 \text{ K}$$

$$\Delta T_{ILMTD} = R_{foul} \left( \frac{Q_{cd}}{A_{w}} \right) = 0.0440 \cdot \left( \frac{850}{50} \right) = 0.748 \text{ K}$$

$$Z = \frac{\Delta T_{range}}{\Delta T_{LMTD} - \Delta T_{LMTD}} = \frac{5.00}{5.0977 - 0.748} = 1.148$$

$$\Delta T_{\text{small,clean}} = \frac{\Delta T_{\text{range}}}{e^{Z} - 1} = \frac{10.00}{e^{1.148} - 1} = 2.52 \text{ K}$$

$$\Delta T_{\text{adj}} = \Delta T_{\text{small,sp}} - \Delta T_{\text{small,clean}} = 3.00 - 2.52 = 0.48 \text{ K}$$

The target Condenser water temperature for testing is then raised 0.48 K to simulate the Fouling Factor Allowance of 0.0440 m<sup>2</sup>·K/kW. When operating in cooling mode, the entering Condenser water temperature is be:  $T_{in,adj} = 30.00 + 0.48 = 30.48$  °C. When operating in heating mode, the leaving Condenser water temperature is:  $T_{out,adj} = 35.00 + 0.48 = 35.48$  °C.

- **F2.2** Concurrent Redundant Verification.
  - **F2.2.1** *Net Refrigeration Capacity.*

 $T_{in,1} = 12.00$  °C,  $T_{in,2} = 12.03$  °C (difference of 0.03 K is acceptable)

 $T_{out,1} = 7.00$  °C,  $T_{out,2} = 6.94$  °C (difference 0.06 K is acceptable)

 $m_{w,1} = 12.72 \text{ kg/s}$ ,  $m_{w,2} = 12.48 \text{ kg/s}$  (difference of 1.8% is acceptable)

$$T_{in,avg} = 12.02 \, ^{\circ}C$$

$$T_{out,avg} = 6.97 \, ^{\circ}C$$

$$m_{w,avg} = 12.60 \text{ kg/s}$$

Properties of water are calculated per Section 7.2 as follows:

 $c_p = 4.194 \text{ kJ/kg} \cdot \text{K}$  using an average entering and leaving temperature of  $(12.02 + 6.97)/2 = 9.50 \, ^{\circ}\text{C}$ 

Net Refrigeration Capacity:

$$\begin{aligned} &Q_{ev} = 12.60 \text{ kg/s} \cdot 4.194 \text{ kJ/kg} \cdot \text{K} \cdot (12.02 \text{ °C} - 6.97 \text{ °C}) \\ &Q_{ev} = 266.86 \text{ kW} \\ &\textbf{F2.2.2} \qquad \textit{Voltage}. \end{aligned}$$

$$V_{1,a} = 386 \text{ V}, \quad V_{1,b} = 389 \text{ V}$$
  
 $V_{2,a} = 388 \text{ V}, \quad V_{2,b} = 380 \text{ V}$   
 $V_{3,a} = 386 \text{ V}, \quad V_{3,b} = 389 \text{ V}$ 

$$V_{a,avg}\!=387$$
 V,  $V_{b,avg}\!=389$  V (difference of 0.52% is acceptable)  $V_{avg}\!=388$  V

### **F2.3** *IPLV.SI and NPLV.SI.*

#### **F2.3.1** *IPLV.SI* with Proportional Capacity Control for a Water-cooled Chiller.

The chiller is a water-cooled centrifugal chiller with proportional capacity control that can be tested at each of the four rating Percent Load points of 100%, 75%, 50% and 25% as defined in Table 6 for standard rating conditions per Table 4. For the 50% point the chiller could not be adjusted to be within 2% of the required rating point load of 50% so two tests were run and interpolation was used. Table F1 shows the test results required to calculate IPLV.SI.

	Table F1. Example F2.3.1 Test Results											
Test No	Target Rating % Load, %	Target Capacity, kW	Measured Net Capacity, kW	Measured % Load, %	Different from Target Capacity, %	Target Condenser EWT, °C	Measured Power, kW	Efficiency, W/W				
1	100.0	1750	1802	103.0	2.971	30.00	296.0	6.088				
2	75.0	1313	1333	76.17	1.171	24.50	196.6	6.780				
3	50.0	875.0	931.0	53.20	3.200	29.00	140.7	6.618				
4	50.0	875.0	836.5	47.80	-2.200	19.00	131.1	6.379				
5	25.0	437.5	455.0	26.00	1.000	19.00	97.50	4.667				

Test 1 can be used for the Full Load IPLV.SI rating point A directly as the Capacity is within 3% of the target per Table 7. Test 2 can also be used for the IPLV.SI rating point B because it is within 2% of the target Capacity per Table 1. Test 3 cannot be used directly for the IPLV.SI rating point C because the Capacity is 3.2% greater than the required load of 50%, and the allowable tolerance of  $\pm 2\%$  as defined in Table 1. Another test could be run to try to get the Capacity within 2%, but for this test series it was chosen to run a lower capacity test for to use for interpolation. Test 5 can be used directly for the IPLV.SI rating point D because the Capacity is within 1% of the target Capacity for 25% load. Table F2 shows the IPLV.SI rating point data that can then be used to calculate the IPLV.SI.

	Table F2. Example F2.3.1 Calculations											
Rating Point	Target Rating % Load, %	Measured Net Capacity, kW	Measured Power, kW	Efficiency, W/W	Comment							
A	100.0	1802	296.0	6.088	Use test point 1 directly.							
В	75.0	1333	196.6	6.780	Use test point 2 directly.							
С	50.0	6.475	Interpolated test 3 and 4.									
D	25.0	455.0	97.50	4.667	Use test point 5 directly.							

The IPLV.SI calculations are shown below using the rating data for IPLV.SI ratings points A, B, C and D.

IPLV. SI = 
$$(0.01 \cdot 6.088) + (0.42 \cdot 6.780) + (0.45 \cdot 6.475) + (0.12 \cdot 4.667) = 6.382 \frac{W}{W}$$

#### **F2.3.2** *NPLV.SI* with Proportional Capacity Control for a Water-cooled Chiller.

The chiller is a water-cooled centrifugal chiller that has proportional capacity control, and can be run at the 100%, 75%, and 50% part-load rating points, but is not able to unload below 27.7% and the required 25% test point D cannot be run. Because this unit is a Configurable Unit and was selected for the lift associated with these non-standard operating conditions the IPLV.SI rating metric should not be used and instead the NPLV.SI metric used with the NPLV.SI conditions and requirements of Table 6. Table F3 shows the test results required to calculate NPLV.SI.

	Table F3. Example F2.3.2 Test Results												
Test No	Target Rating % Load, %	Target Capacity, kW	Measured Net Capacity, kW	Measured % Load, %	Different from Target Capacity, %	Target Condenser EWT, °C	Measured Power, kW	Efficiency, W/W					
1	100.0	2730	2743	100.5	0.476	32.0	507.9	5.400					
2	75.00	2048	2075	76.0	1.007	25.5	316.9	6.549					
3	50.00	1365	1360	49.8	-0.183	19.0	183.3	7.419					
4	25.00	682.5	755.9	27.7	2.688	19.0	136.9	5.520					

Test 1 is within the allowable Capacity tolerance as defined in Table 7 so the test data can be used directly in the NPLV.SI calculations for rating point A. Tests 2 and 3 are within the allowable tolerance of  $\pm 2\%$  in Table 1, so they can also be used to directly for the NPLV.SI rating points B and C, respectively. Test 4 was run at the lowest Capacity unloading capability of the chiller and the capacity load of 27.7% is outside the allowable tolerance of  $\pm 2\%$  in Table 1 so it cannot be used directly. Because this is the lowest capacity point it is not acceptable to use interpolation where a rating point above and below the 25% is used. Extrapolation cannot be used. Therefore, for NPLV.SI rating point D determination a degradation factor is applied to the measured efficiency to reflect that the unit cycles at a 25% load point. Table F4 shows the data that can then be used to calculate the NPLV.SI.

	Table F4. Example F2.3.2 Calculations												
Rating Point Rating % Load, % Weasured Net Capacity, kW Load, % kW LF CD Efficiency, W/W Comment													
A	100.0	2743	507.9	ı	ı	5.400	Use Test 1 directly.						
В	75.00	2075	316.9	-	-	6.549	Use Test 2 directly.						
С	50.00	1360	183.3	-	-	7.419	Use Test 3 directly.						
D	25.00	-	-	0.902935	1.012619	5.520	Use Test 4 with C <sub>D.</sub>						

The following is a summary of the calculations for the degradation of rating Test 4:

$$LF = \frac{0.25 \cdot 2730}{755.9} = 0.902935$$

$$C_D = (-0.13 \cdot 0.902935) + 1.13 = 1.012619$$

$$COP_{R25\%,CD} = 1.012619 \cdot 0.5451 = 5.520 \frac{W}{W}$$

With the data for the 4 NPLV.SI rating points A, B, C, and D the NPLV.SI can then be calculated using Equation 18

NPLV. SI = 
$$(0.01 \cdot 5.400) + (0.42 \cdot 6.549) + (0.45 \cdot 7.419) + (0.12 \cdot 5.520) = 6.740 \frac{W}{W}$$

#### **F2.3.3** *IPLV.SI with 10 Stages of Capacity Control for an Air-cooled Chiller.*

The chiller is an air-cooled chiller with 10 stages of Capacity that can unload down to a minimum of 15% of rated load. Only 7 stages of capacity control are used for the computation of rating point data for the IPLV.SI calculations. The standard procedures require that for interpolation capacity points closest to the desired ratings point are used. Larger or smaller capacity points from other stages cannot be used. Because this is an air-cooled chiller the test performance is corrected to standard atmospheric pressure of 101.33 kPa using the procedures in Appendix C. The test data was run when the atmospheric pressure was 99.42 kPa. Table F5 shows the test required to calculate IPLV.SI including corrections for atmospheric pressure.

	Table F5. Example F2.3.3 Test Results												
Test No	Target Rating % Load, %	Target Capacity, kW	Measured Net Capacity, kW	Measured Total Power, kW	Measured Efficiency, W/W	Capacity Correction Factor	Efficiency Correction Factor	Corrected Capacity, kW	Corrected Efficiency, W/W	Corrected Measured % Load, %	Different from target Capacity,	Target EDB, °C	
1	100.0	528.0	521.7	170.3	3.063	1.0017	1.0039	522.5	3.075	98.97	-1.035	35.0	
2	75.0	396.0	438.2	125.8	3.484	1.0014	1.0033	438.9	3.495	83.12	8.117	27.0	
3	75.0	396.0	372.1	93.8	3.966	1.0012	1.0028	372.5	3.977	70.55	-4.449	27.0	
4	50.0	264.0	290.0	66.8	4.341	1.0009	1.0022	290.3	4.350	54.98	4.984	19.0	
5	50.0	264.0	221.1	49.5	4.464	1.0007	1.0016	221.2	4.471	41.90	-8.104	19.0	
6	25.0	132.0	159.1	36.2	4.391	1.0005	1.0012	159.2	4.397	30.15	5.149	13.0	
7	25.0	132.0	79.2	19.0	4.166	1.0003	1.0006	79.22	4.169	15.00	-9.996	13.0	

Before using the test data to calculate the IPLV.SI the data is corrected for the atmospheric pressure of 99.42 kPa per Appendix C. The calculations for test point 2 are shown below as an example of the atmospheric correction calculations.

Correction factor  $D_Q = 0.000023713 \cdot 99.420^2 - 0.005986 \cdot 99.420 + 1.36304 = 1.0023$ Correction factor  $D_{\eta} = 0.00051135 \cdot 99.42^2 - 0.013064 \cdot 99.42 + 1.79872 = 1.0053$ 

 $\begin{aligned} &\text{Correction Factor } CF_Q = 1 + (438.2/521.7) \cdot (1.0023\text{-}1) \cdot exp[-0.35 \cdot (3.412 \cdot 1.0053 \cdot 10.44\text{-}9.6)] = 1.0014 \\ &\text{Correction Factor } CF_\eta = 1 + (438.2/521.7) \cdot (1.0053\text{-}1) \cdot exp[-0.35 \cdot (4.412 \cdot 1.0053 \cdot 10.44\text{-}9.6)] = 1.0033 \end{aligned}$ 

Corrected Capacity  $Q_{corrected} = 438.2 \cdot 1.0014 = 438.9 \text{ kW}$ Corrected efficiency  $\eta_{corrected} = 3.484 \cdot 1.0033 = 3.495 \text{ COP}_R$ 

Once the corrections are made then the following Table F6 shows the calculations that are done to determine the IPLV.SI rating points.

	Table F6. Example F2.3.3 Calculations											
Rating Point	o   %   Oad   Canacity   Power   LE   Ca   The Comment											
A	100.0	521.7	170.3	-	-	3.075	Use test 1 directly.					
В	75.00	ı	-	-	ı	3.799	Interpolate test 2 and 3.					
С	50.00	-	-	-	-	4.396	Interpolate test 4 and 5.					
D	25.00	-	-	-	-	4.318	Interpolate test 6 and 7.					

Test 1 is within the allowable Capacity tolerance of 5% as defined in Table 7 so the atmospheric pressure corrected test data can be used directly in the IPLV.SI calculations for rating point A. For rating points B, C, and D the measured Capacity is greater or less than the required load  $\pm 2\%$  as required by Table 1, so interpolation is used. There are stages of Capacity to either side of the 75%, 50%, and 25% rating points that allow for interpolation. The capacity stages closest to the rating points are used (Figure F1). So, for rating points B interpolation is used using atmospheric corrected test 2 and 3 and similar interpolation for rating points C and D.




Figure F1. Rating Point Interpolation

An example of the interpolation is shown below for the 25% point D calculation.

Desired Rating Point D % Load = 25%

Test Point 1 % Load = 30.15%

Test Point 1 Efficiency = 4.397 W/W

Test Point 2 % Load = 15.00%

Test Point 2 Efficiency = 4.169 W/W

exponent = 
$$\log_{10}(4.169) + (.3015 - .1500) \cdot \frac{\left[\log_{10}(4.397) - \log_{10}(4.169)\right]}{(0.3015 - 0.1500)}$$
  
= 0.63526398

$$\eta_{int} = 10^{(0.63526398)} = 4.318 \frac{W}{W}$$

The IPLV.SI can then be calculated using the efficiencies determined from the interpolation for the IPLV.SI rating point A, B, C and D.

IPLV. SI = 
$$(0.01 \cdot 3.075) + (0.42 \cdot 3.799) + (0.45 \cdot 4.396) + (0.12 \cdot 4.318) = 4.123 \frac{W}{W}$$

### **F2.3.4** *IPLV.SI with 3 Stages of Capacity Control for an Air-cooled Chiller.*

The chiller is an air-cooled chiller with 3 stages of Capacity the last stage of Capacity greater than the required 25% rating point. The degradation factor (C<sub>D</sub>) is used for rating point D. This unit also has a head pressure control system that reduces the number of operating condenser fans and it has a hysteresis to prevent rapid cycling so for test point D two tests (test 6 and test 7) were run as defined by 5.8 to determine the average performance. Test 6 was run by approaching from a 5 °C warmer ambient temperature to the desired 13 °C temperature which resulted in all the condenser fans running. Test 7 was run by approaching from a -5 °C colder ambient temperature to the desired 13 °C and this resulted in partial condenser fan operation. The two tests are then averaged as required by section 5.8 Because this is an air-cooled chiller, the test performance is be corrected to standard atmospheric pressure of 101.33 kPa using the procedures in Appendix C. The test data was run when the atmospheric pressure was 97.91 kPa. Table F7 shows the test required to calculate IPLV.SI including corrections for atmospheric pressure.

	Table F7. Example F2.3.4 Test Results													
Test No	Target Rating % Load	Target Capacity,	Net	Measured Total Power, kW	Measured	Capacity Correction Factor	Efficiency Correction Factor		Corrected Efficiency, W/W	Measured	Difference from target Capacity, %	Target EDB, °C		
1	100.0	387.0	387.7	138.1	2.807	1.0042	1.0096	389.3	2.834	100.6	0.599	35.00		
2	75.0	387.0	430.5	127.4	3.379	1.0046	1.0106	432.5	3.415	111.8	11.75	27.00		
3	75.0	290.3	279.0	77.70	3.591	1.0030	1.0069	279.8	3.615	72.31	-2.693	27.00		
4	50.0	193.5	303.6	73.71	4.119	1.0033	1.0075	304.6	4.150	78.71	28.71	19.00		
5	50.0	96.8	180.4	43.20	4.176	1.0019	1.0045	180.8	4.195	46.71	21.71	19.00		
6	25.0	96.8	163.6	40.90	4.000	1.0018	1.0040	163.9	4.016	42.35	17.35	13.00		
7	25.0	96.8	155.4	40.08	3.877	1.0017	1.0038	155.7	3.892	40.23	15.23	13.00		
Avg 6,7	25.0	96.8	159.5	40.49	3.939	1.0017	1.0039	159.8	3.955	41.29	16.29	13.00		

Test 1 is within the allowable Capacity tolerance of 5% as defined in Table 7 so the atmospheric pressure corrected test data can be used directly in the IPLV.SI calculations for rating point A. Tests 2 and 3 are not within the allowable  $\pm 2\%$  for Capacity as required by Table 1, so rating point B is determined by interpolation. The same is true for rating point C where again interpolation is used. For rating point D the average of test 6 and 7 should be used as required by section 5.8 for head pressure control. As the average corrected Capacity is greater than the  $\pm 2\%$  for Capacity required by Table 1 a degradation calculation is used. Table F8 shows the data that can then be used to calculate the IPLV.SI.

	Table F8. Example F2.3.4 Calculations											
Rating Point		Measured Net Capacity, kW	Measured Power, kW	LF	$C_D$	Efficiency, W/W	Comment					
A	100.0	387.7	138.1	=	ı	2.834	Use test 1 directly.					
В	75.00	=	-	-	-	3.601	Interpolate test 1 and 2.					
С	50.00	-	-	=	-	4.190	Interpolate test 2 and 3.					
D	25.00	-	-	0.605524	1.051282	3.762	Use test 4 with C <sub>D.</sub>					

The following is a summary of the calculations for the degradation of the average 6,7 test data:

$$LF = \frac{0.25 \cdot 387.0}{159.8} = 0.605524$$

$$C_D = (-0.13 \cdot 0.605524) + 1.13 = 1.051282$$

$$COP_{25\%,CD} = \frac{3.955}{1.051282} = 3.762 \text{ W/W}$$

The IPLV.SI can then be calculated using the efficiencies determined from the interpolation for the IPLV.SI rating point A, B, C and D.

IPLV. 
$$SI = (0.01 \cdot 2.834) + (0.42 \cdot 3.601) + (0.45 \cdot 4.190) + (0.12 \cdot 3.762) = 3.878 \text{ W/W}$$

#### **F2.3.5** *IPLV.SI* with 1 Stage of Capacity Control for a Water-cooled Chiller.

The chiller is a water-cooled chiller with 1 stage of Capacity, so the degradation procedure factor (C<sub>D</sub>) defined in section 5.4.3.2.7 is used to generate the rating data for the 75%, 50%, and 25% IPLV.SI rating points. The unit can only run at full-load, thus additional performance information is use with the unit running at the 24.50 °C entering Condenser water temperature for the B rating point and at 19.00 °C Condenser entering water for

the C and D rating point. The Condenser water temperature is 19.00 °C for both the 50% and 25% rating points because the load is equal to or less than 50%, thus only 3 test points are required to generate the IPLV.SI rating data. Table F9 shows the test required to calculate IPLV.SI.

	Table F9. Example F2.3.5 Test Results												
Test No	Target Rating % Load, %	Target Capacity, kW	Measured Net Capacity, kW	Measured % Load	Different from Target Capacity	Target Condenser EWT, °C	Measured Power, kW	Efficiency, W/W					
1	100.0	53.00	54.06	102.00	2.000	30.00	11.90	4.543					
2	75.0	39.75	61.13	115.33	40.33	24.50	10.60	5.767					
3	50.0	26.50	69.96	132.00	82.00	19.00	11.30	6.191					

Test 1 is within the allowable Capacity tolerance of 5.00% as defined in Table 7 so the test data can be used directly in the IPLV.SI calculations for rating point A. For the B, C, and D rating points degradation factors are applied to the ratings test results. The IPLV.SI rating point data is shown in Table F10.

	Table F10. Example F2.3.5 Calculations										
Rating Point	Target Rating % Load, %	Measured Net Capacity, kW	Measured Power, kW	LF	$C_D$	Efficiency, W/W	Comment				
A	100.0	54.06	11.90	-	=	4.543	Use test 1 directly				
В	75.00	-	-	0.650289	1.045462	6.029	Use test 2 with C <sub>D</sub>				
С	50.00	-	-	0.378788	1.080758	6.691	Use test 3 with C <sub>D</sub>				
D	25.00	-	-	0.189394	1.105379	5.601	Use test 4 with C <sub>D</sub>				

The IPLV.SI can then be calculated using the efficiencies determined from the degradation factor method for the IPLV.SI rating points A, B, C and D.

$$IPLV. SI = (0.01 \cdot 4.543) + (0.42 \cdot 6.029) + (0.45 \cdot 6.691) + (0.12 \cdot 5.601) = 6.229 \frac{W}{W}$$

#### **F2.3.6** *IPLV.SI* with Continuous Unloading for an Air-cooled Chiller.

The chiller is an air-cooled chiller with continuous unloading. Because this is an air-cooled chiller, the test performance is corrected to standard atmospheric pressure of 101.33 kPa using the procedures in Appendix C. The test data was run when the atmospheric pressure was 93.08 kPa. Table F11 shows the test required to calculate IPLV.SI including corrections for atmospheric pressure.

	Table F11. Example F2.3.6 Test Results											
Test No	Target Rating % Load, %	Target Capacity, kW	Not	Measured Total Power, kW	Measured Efficiency, W/W				Corrected Efficiency, W/W	% Load,	Different from Target Capacity, %	Target EDB,
1	100.0	704.0	694.1	243.5	2.851	1.0099	1.0226	701.0	2.915	99.58	-0.423	35.0
2	75.0	528.0	524.8	146.0	3.595	1.0075	1.0171	528.8	3.656	75.11	0.109	27.0
3	50.0	352.0	352.7	87.00	4.054	1.0050	1.0115	354.5	4.101	50.35	0.352	19.0
4	25.0	176.0	198.9	51.30	3.877	1.0028	1.0065	199.44	3.902	28.33	3.330	13.0

Test 1 is within the allowable Capacity tolerance of 5.00% as defined in Table 7 so the test data can be used directly in the IPLV.SI calculations for rating point A. Tests 2 and 3 can be used for rating points B and C respectively as they are within the  $\pm 2\%$  for Capacity as required by Table 1. Test 4 cannot be used directly because the Capacity is 3.33% above the  $\pm 2\%$  for Capacity as required by Table 1 and because it is the lowest

unloading capability of the unit, a degradation factor ( $C_D$ ) is applied. Table F12 shows the data that can then be used to calculate the IPLV.SI.

	Table F12. Example F2.3.6 Calculations									
Rating Point	Target Rating % Load, %	Corrected Capacity, kW	Corrected Efficiency, W/W	LF	$C_D$	Efficiency, W/W	Comment			
A	100.0	694.1	2.915	-	-	2.915	Use test 1 directly.			
В	75.00	524.8	3.656	-	-	3.656	Use test 2 directly.			
С	50.00	352.7	4.101	-	-	4.101	Use test 3 directly.			
D	25.00	198.9	3.902	0.882450	1.015282	3.843	Use test 4 with C <sub>D.</sub>			

The IPLV.SI can be calculated using the efficiencies determined from IPLV.SI rating point A, B, C and D.

$$IPLV. SI = (0.01 \cdot 2.915) + (0.42 \cdot 3.656) + (0.45 \cdot 4.101) + (0.12 \cdot 3.843) = 3.871 \text{ W/W}$$

**F2.3.7** IPLV.SI with Proportional Capacity Control for an Evaporatively Cooled Chiller

The chiller is an evaporatively-cooled chiller with proportional capacity control. Because this is an air-cooled chiller, the test performance is corrected to standard atmospheric pressure of 101.33 kPa using the procedures in Appendix C. The test data was run when the atmospheric pressure was 97.22 kPa. Table F13 shows the test required to calculate IPLV.SI including corrections for atmospheric pressure.

	Table F13. Example F2.3.7 Test Results											
Test No	Target Rating % Load, %	Target Capacity, kW	Net	Measured Total Power, kW	Measured	1 2			Corrected Efficiency, W/W	Measured % Load,		Target EWB,
1	100.0	528.0	531.5	125.2	4.245	1.0009	1.0020	532.0	4.254	100.76	0.76	24.0
2	75.0	396.0	401.3	84.55	4.746	1.0007	1.0015	401.5	4.753	76.05	1.05	20.5
3	50.0	264.0	258.7	57.27	4.517	1.0004	1.0010	258.8	4.522	49.02	-0.98	17.0
4	25.0	132.0	147.8	45.82	3.227	1.0002	1.0006	147.9	3.228	28.01	3.01	13.5

Test 1 is within the allowable Capacity tolerance of 5.00% as defined in Table 7 so the test data can be used directly in the IPLV.SI calculations for rating point A. Tests 2 and 3 can be used for rating points B and C respectively as they are within the  $\pm 2\%$  for Capacity as required by Table 1. Test 4 can only unload to 28.01% and therefore is above the  $\pm 2\%$  for Capacity as required by Table 1 and because it is the lowest unloading capability of the unit, a degradation factor ( $C_D$ ) is applied. Table F14 shows the data that can then be used to calculate the IPLV.SI.

	Table F14. Example F2.3.7 Calculations										
Rating Point	Target Rating % Load, %	Corrected Capacity, kW	Corrected Efficiency, W/W	LF	$C_D$	Efficiency, W/W	Comment				
A	100.0	531.5	4.254	-	-	4.254	Use test 1 directly.				
В	75.00	401.3	4.753	-	-	4.753	Use test 2 directly.				
С	50.00	258.7	4.522	-	-	4.522	Use test 3 directly.				
D	25.00	-	-	0.892637	1.013957	3.184	Use test 4 with C <sub>D.</sub>				

The IPLV.SI can be calculated using the efficiencies determined from IPLV.SI rating points A, B, C and D.

IPLV. 
$$SI = (0.01 \cdot 4.254) + (0.42 \cdot 4.753) + (0.45 \cdot 4.522) + (0.12 \cdot 3.184) = 4.456 \text{ W/W}$$

F2.4 Tolerance Limits. The tolerance limit on Capacity and efficiency is determined from Section 5.6.1.

#### F2.4.1 COP at Full-load.

Rated Full-load Performance:

Rated Capacity = 300.0 kW Rated Power = 101.0 kWCooling  $\Delta T_{FL} = 5.00 \text{ K}$ 

$$COP_R = \frac{300.0 \text{ kW}}{101.0 \text{ kW}} = 2.970 \frac{\text{W}}{\text{W}}$$

Tolerance Limit = 
$$Tol_1 = 0.105 \cdot (0.07 \cdot 1.00) \cdot \left(\frac{0.0833}{5.00 \cdot 1.00}\right) = 0.0517$$

Minimum Allowable Capacity =  $(1.00 - 0.0517) \cdot 300.0 \text{ kW} = 284.5 \text{ kW}$ 

$$\text{Minimum Allowable COP}_{R} = \frac{2.970 \frac{W}{W}}{1.00 + 0.0517} = 2.824 \frac{W}{W}$$

#### F2.4.2 COP at Part-load.

Rated Part-load Performance:

Power at 69.5% Rated Capacity = 59.00 kW 69.5% Rated Capacity = 208.5 kW Cooling  $\Delta T_{FL}$ = 5.00 K

$$COP_R = \frac{208.5 \text{ kW}}{59.00 \text{ kW}} = 3.534 \frac{\text{W}}{\text{W}}$$

Tolerance Limit =  $Tol_1 = 0.105 \cdot (0.07 \cdot 0.695) \cdot \left(\frac{0.0833}{5.00 \cdot 0.695}\right) = 0.0803$ 

$$\begin{aligned} & \text{Minimum Allowable Capacity} = (100\% - 0.0830) \cdot 208.5 \text{ kW} = 191.8 \text{ kW} \\ & \text{Minimum Allowable COP}_R = \frac{3.524 \frac{W}{W}}{1.00 + 0.083} = 3.271 \frac{W}{W} \end{aligned}$$

Atmospheric Pressure Adjustment. The atmospheric pressure adjustment is determined in accordance with F2.5 Appendix C.

#### F2.5.1 Altitude of 1080 m.

A chiller has Published Ratings of 700.0 kW and 3.100 COP<sub>R</sub> at sea level. The chiller is tested at an altitude of approximately 1080 meters.

The measured test results:

Capacity  $Q_{tested} = 693.2 \text{ kW}$ Efficiency  $\eta_{tested} = 3.021 \text{ COP}_{R}$ Air pressure P = 98.07 kPa

Correction function  $D_Q = 0.000023713 \cdot 98.07^2 - 0.0059860 \cdot 98.07 + 1.36304 = 1.0041$ 

Correction function  $D_h = 0.000051135.98.07^2 - 0.013064.98.07 + 1.79872 = 1.0093$ 

Correction function CFq =  $1 + (693.2/693.2)(1.0041-1) \cdot \exp[-0.35 \cdot (3.41214 \cdot 1.0093 \cdot 3.021-9.6)] = 1.0031$ 

Correction function  $CF\eta = 1 + (693.2/693.2)(1.0093-1) \cdot \exp[-0.35 \cdot (3.41214 \cdot 1.0093 \cdot 3.021 - 9.6)] = 1.0070$ 

Corrected test Capacity Q<sub>corrected standard</sub> = 693.2 · 1.0031= 695.3 kW

Corrected test efficiency  $\eta_{\text{corrected standard}} = 3.021 \cdot 1.0070 = 3.042 \text{ COP}_{R}$ 

Part load efficiency and capacity correction factors for the following example are determined using the same calculation process as for the 0 and 100% Load Point example:

With a part load test result Capacity of 560.0 kW and a 693.2 kW test result for 100% load point Capacity. The chiller is tested at an altitude of about 1080 meters.

The measured test results for the part load test:

Capacity  $Q_{test}$  = 560.0 kW Efficiency  $\eta_{tested,100\%}$  = 3.021 COP Efficiency  $\eta_{test}$  = 3.686 COP Air Pressure  $P_{test}$  = 98.07 kPa

Correction function  $D_0 = 0.000023713 \cdot 98.07^2 - 0.0059860 \cdot 98.07 + 1.36304 = 1.0041$ 

Correction function  $D\eta = 0.000051135 \cdot 98.07^2 - 0.013064 \cdot 98.07 + 1.79872 = 1.0093$ 

Correction Factor CFq =  $1 + (560.0/693.2) \cdot (1.0041-1) \cdot \exp[-0.35 \cdot (3.41214 \cdot 1.0093 \cdot 3.021-9.6)] = 1.0011$ 

Correction Factor CF $\eta$  = 1+ (560.0/693.2) ·(1.0093-1) ·exp[-0.35·(3.41214·1.0093·3.021-9.6)] = 1.0026

Corrected test Capacity Q<sub>corrected,standard</sub> = 560.0·1.0011 = 560.6 kW

Corrected test efficiency  $\eta_{corrected,standard} = 3.021 \cdot 1.0026 = 3.029 \text{ COP}$ 

### **F2.5.2** *Altitude of 300 m.*

The same chiller from the example in Section F2.5.1 also has published Application Ratings of 697.6 kW and 3.076 COP at 300 meters, corresponding to rated atmospheric pressure of 100.23 kPa. The chiller is tested at an altitude of about 1080 meters.

The measured test results:

Capacity  $Q_{tested}$  = 693.2 kW Efficiency  $\eta_{tested}$  = 3.021 COP Air pressure  $P_{test}$  = 98.07 kPa

From prior example calculations:

Corrected test Capacity  $Q_{corrected,standard} = 695.3 \text{ kW}$ Corrected test efficiency  $\eta_{corrected,standard} = 3.042 \text{ COP}$ 

Next calculate correction factors for the application rating value of  $P_{rated} = 100.23$  kPa:

Correction function  $D_0 = 0.000023713 \cdot 100.23^2 - 0.0059860 \cdot 100.23 + 1.36304 = 1.0013$ 

Correction function  $D\eta = 0.000051135 \cdot 100.23^2 - 0.013064 \cdot 100.23 + 1.79872 = 1.0030$ 

Correction Factor CFq =  $1 + (693.2/693.2) \cdot (1.0013-1) \cdot \exp[-0.35 \cdot (3.41214 \cdot 1.0030 \cdot 3.686 - 9.6)] = 1.0010$ 

Correction Factor CF $\eta$  = 1+ (693.2/693.2) ·(1.0030-1) ·exp[-0.35·(3.41214·1.0030·3.686-9.6)] = 1.0023

Corrected test Capacity Q<sub>corrected,application</sub> = 695.3 / 1.0010 = 694.6 kW

Corrected test efficiency  $\eta_{corrected,application} = 3.042 / 1.0023 = 3.035 COP$ 

# APPENDIX G. INDIAN RATING CONDITIONS – INFORMATIVE

**G1** *Purpose*. This appendix is an informative appendix that defines optional rating conditions relevant to the Indian Standard IS 16590:2017, *Water cooled Chilling Packages Using the Vapor Compression Cycle – Specification*. This does not address further requirements in the Indian Standard IS 16590:2017 around construction, safety, installation, or sound power ratings. The requirements of the Indian Standard IS 16590:2017 apply to units of any size with AC supply voltage of 250 V, 50 Hz single phase up to and including 11 kV, 50 Hz three phase.

**G2** Indian Standard Ratings and Conditions. Indian Standard Rating Conditions specified in Table G1 are used for cooling performance.

	Table G1. Indian Standard Rating Conditions									
					C	ooling Mod	e Heat Reject	ion Heat E	xchanger	
Operating Category	Conditions	Cooling Mode Evaporator <sup>1</sup>		Tower (Water Conditions) <sup>2</sup>			Air-cooled (AC) Entering Temperature <sup>3, 4</sup>			
		Entering Temperat ure, °C	Leaving Temper ature, °C	Flow Rate L/(s·kW)	Entering Temper ature, °C	Leaving Temperat ure, °C	Flow Rate, $L/(s \cdot kW)$	Dry- Bulb, °C	Wet-Bulb,	
All Cooling	Standard	12.00	7.00	$(0.0478)^5$	30.00	35.00	Note 5	39.0		

#### Notes:

- 1. The rating Fouling Factor Allowance for the cooling mode evaporator is  $R_{\text{foul}} = 0.0440 \text{ m} \cdot 2 \cdot \text{K/kW}$ .
- 2. The rating Fouling Factor Allowance tower heat exchangers is  $R_{\text{foul}} = 0.0880 \text{ m} \cdot \text{K/kW}$ .
- 3. Air-cooled Condensers are rated with a Fouling Factor Allowance of zero, R<sub>foul</sub> = 0.000 m<sup>2</sup>·K/kW.
- 4. Air-cooled unit ratings are at standard atmospheric conditions (sea level). Measured test data is corrected to atmospheric pressure of 101.33 kPa per Appendix C.
- 5. Rated water flow is determined by the water temperatures at the rated Capacity and rated efficiency.

G3 Indian Application Rating Conditions. Full and Part-load Application Ratings include the range of rating conditions specified in Table G2 or within the operating limits of the equipment.

	Table G2. Indian Full and Part-load Application Rating Conditions									
		Evaporator			Condenser					
		Water Cooled			Water Cooled					
	Leaving Temperature <sup>1,</sup> °C	Temperature Difference Across Heat Exchanger <sup>2</sup> , K	Fouling Factor Allowance, m <sup>2</sup> ·K/kW	Entering Temperature <sup>3</sup> , °C	Flow Rate <sup>4, 5</sup> , L/(s·kW)	Fouling Factor Allowance, m <sup>2</sup> ·K/kW				
Cooling				20.0 to 35.0	0.018 to 0.108	≤ 0.180				
	4.40 to 10.00	2.50 to 8.00	≤ 0.180	Air-cooled						
	10.00	6.00		Entering Air Dry Bulb <sup>2,6</sup> , °C						
					20.0 to 46.0					

#### Notes:

- 1. Leaving evaporator water temperatures are published in rating increments of no more than 2.0 °C.
- 2. Atmospheric pressure in the range of 79.70 to 104.8 kPa, rated altitude not exceeding 1980 m. Measured test data is corrected per Appendix F to the application rating atmospheric pressure.
- 3. Entering water temperatures are published in rating increments of no more than 2.0 °C.
- 4. Applies to design point only, not part-load points.
- 5. The normalized flow rate is per unit of evaporator Capacity.
- 6. Entering air temperatures are published in rating increments of no more than 3.5 °C.

G4 Part-load Rating Conditions. Part-load Rating Conditions shall be specified as per Table G3.

Та	ble G3. Part-load Conditions for Ratings
	ISEER
Evaporator (All types)	
All loads LWT, °C¹	7.00
Flow Rate (L/s per kW) <sup>2</sup>	Note 2
$R_{\text{foul.}}, m^2 \cdot K/kW$	0.0440
Water-cooled Condenser <sup>1,3</sup>	
100% load EWT, °C	30.00
75% load EWT, °C	26.00
50% load EWT, °C	23.00
25% load EWT, °C	20.00
Flow rate, L/s per kW <sup>2</sup>	Note 2
R <sub>foul</sub> m <sup>2</sup> ·K/kW	0.0880
Air-cooled Condenser <sup>1, 4</sup>	
100% load EDB, ℃	39.0
75% load EDB, °C	32.0
50% load EDB, °C	26.0
25% load EDB, °C	20.0
R <sub>foul</sub> m <sup>2</sup> ·K/kW	0.000

#### Notes:

- 1. Correct for Fouling Factor Allowance by using the calculation method described in Section 4.6.
- 2. The flow rates are to be held constant sufficient to create 5.00  $\Delta$ °C at full-load values for all part-load conditions as per Table G1.
- 3. If the unit manufacturer's recommended minimum temperatures are greater than those specified in Table G3, then those can be used instead of the specified temperatures. If head pressure control is active below the rating temperature, then tests should be run at a temperature above which head pressure control is activated.
- 4. Air-cooled unit ratings are at standard atmospheric condition (sea level). Measured data is corrected to standard atmospheric pressure of 101.33 kPa per Appendix C.

- **G5** *Indian Standard Rating Metrics*. Ratings are calculated as defined in Section 5, with the addition of India Seasonal Energy Efficiency Ratio, ISEER.
  - **G5.1** Background. The ISEER metric was created to define a uniform procedure for the calculation of a single value number that is a representation of the Part-load efficiency of a chiller using Indian weighting factors and temperatures.

**G5.2** Equations and Definitions of Terms. Equation G1 is used when an efficiency is expressed as COP<sub>R</sub> [W/W]:

ISEER = 
$$A \cdot COP_{100\%} + B \cdot COP_{75\%} + C \cdot COP_{50\%} + D \cdot COP_{25\%}$$

Where:

 $COP_{100\%} = COP$  at full load rating point and operating conditions

 $COP_{75\%} = COP$  at 75% load point and operating conditions

 $COP_{50\%} = COP$  at 50% load point and operating conditions

 $COP_{25\%} = COP$  at 25% load point and operating conditions

And:

A = weighting factor for 100% load

B = weighting factor for 75% load

C = weighting factor for 50% load

D = weighting factor for 25% load

Table G4. Weighting Coefficients A to D for Calculation of ISEER								
Load Point, % 100 75 50 25								
Weighting Coefficient	A=0.06	B=0.48	C=0.36	D=0.10				

**G5.3** Procedure for Testing and Calculation of ISEER for Discrete Capacity Controlled Units. If the unit has discrete steps of unloading, but due to its capacity control logic cannot be operated at 75%, 50% or 25% Capacity, then the unit should be operated at other load points and the 75%, 50%, or 25% capacity efficiencies should be determined by interpolating between the two operating points that frame the rating point. The required condenser entering temperature at the requested load point should be used and a capacity test run at each unloading stage on either side of the desired part load rating point then should be interpolated to obtain the desired part load point rating.

For example, if the unit has capacity stages at 33% and 66% nominal displacement, then the 50% point can be determined by obtaining the Capacity and efficiency at the 66% unloading stage at 50% entering temperature and another test, at the 33% unloading stage at the 50% entering temperature.

Extrapolation of data is not be used and the desired rating point is framed by two actual operating points. An actual chiller capacity point, equal to or less than the required rating point is used to plot the data. For example, if the minimum actual Capacity is 33%, then the curve can be used to determine the 50% capacity point, but not the 25% capacity point.

If a unit cannot be unloaded to the 25%, 50%, or 75% capacity point, then the unit should be run at the minimum step of unloading at the condenser entering temperature based on Table G4 for 25%, 50% or 75% capacity points as required. The efficiency is then determined by using Equation G2:

$$COP_{R,CD} = \frac{COP_{Test}}{C_D}$$
 G2

Full load Capacity is the Capacity at the full load 100% rating point as defined in Table G5. The part load Capacity of the unit is the Capacity obtained when the machine is run at its lowest stage of Capacity at the desired load point rating conditions.

For Water-cooled units where a unit has been selected for operating conditions that do not allow operation at the full load condenser entering fluid conditions, then an ISEER cannot be calculated. For these applications, ISEER can be determined, using the same procedures as defined above except that for the full load rating point the machine is run at the maximum design entering condenser temperature. The 75%, 50%, and 25% points are then run at the temperatures defined in Table G5 unless the unit does not operate at these conditions and then the maximum option temperature is used.

For example, if a Water-cooled chiller was selected for 30  $^{\circ}$ C full load condenser entering fluid temperature then the 100% point can be determined at a 30  $^{\circ}$ C entering conditions. For ISEER rating the 75% can then be determined at a 26  $^{\circ}$ C entering temperature, the 50% at 23  $^{\circ}$ C and the 25% point at 20  $^{\circ}$ C.

	Table G5. Chiller Part-load Values Data									
<b></b>	Target Rating	a.	Measured Net	0/7 1	Temp of	Measured	Efficiency,			
Testing No.	% Load, %	Step	Capacity, kW	%Load	Entering Air, °C	Power, kW	$COP_R$			
1	100.0	1 (100%)	350.0	100.0	39.90	92.30	3.790			
2	100.0	1 (100%)	392.0	112.0	32.00	101.8	3.850			
3	75.00	2 (66%)	245.0	70.00	32.00	56.30	4.350			
4	50.00	2 (66%)	256.0	73.00	26.00	57.50	4.450			
5	50.00	3 (33%)	141.0	40.00	26.00	30.70	4.590			
6	25.00	3 (33%)	146.9	42.00	20.00	33.30	4.410			